

 \bigtriangledown

VOL. 17, NO. 11

JANUARY 1937



PUBLIC ROADS ... A Journal of Highway Research

Issued by the

UNITED STATES DEPARTMENT OF AGRICULTURE

BUREAU OF PUBLIC ROADS

Volume 17, No. 11

January 1937

Page

- - Willard Building, Washington, D. C.

- - Federal Building, Civic Center, San Francisco, Calif.

The reports of research published in this magazine are necessarily qualified by the conditions of the tests from which the data are obtained. Whenever it is deemed possible to do so, generalizations are drawn from the results of the tests; and, unless this is done, the conclusions formulated must be considered as specifically pertinent only to described conditions.

In This Issue

Experimental Bituminous Treatment of Sandy-Soil Roads . 249

THE BUREAU OF PUBLIC ROADS -**REGIONAL HEADOUARTERS**

DISTRICT OFFICES

DISTRICT No. 1. Oregon, Washington, and Montana. Post Office Building, Portland, Oreg.	DISTRICT No. 8. Alabama, Georgia, Florida, Mississippi, and Tennessee. Post Office Building, Montgomery, Ala.
DISTRICT No. 2. California, Arizona, and Nevada. Federal Building, Civic Center, San Francisco, Calif.	J,
DISTRICT No. 3. Colorado, New Mexico, and Wyoming. 237 Custom House, Nineteenth and Stout Sts., Denver, Colo.	District rios to. Delaware, maryland, Onto, I ennoyivania, and District
DISTRICT No. 4. Minnesota, North Dakota, South Dakota, and Wisconsin. 907 Post Office Building. St. Paul, Minn. DISTRICT No. 5. Iowa, Kansas, Missouri, and Nebraska.	Willard Building, Washington, D. C. DISTRICT No. 11. Alaska.
Masonic Temple Building, Nineteenth and Douglas Sts., Omaha, Nebr.	Room 419, Federal and Territorial Building, Juneau, Alaska. DISTRICT No. 12. Idaho and Utah.
DISTRICT No. 6. Arkansas, Louisiana, Oklahoma, and Texas. Room 502, United States Court House, Fort Worth, Tex.	Federal Building, Ogden, Utah. DISTRICT No. 14. North Carolina, South Carolina, Virginia, and West
DISTRICT No. 7. Illinois, Indiana, Kentucky, and Michigan. South Chicago Post Office Building, Chicago, Ill.	Virginia.

Because of the necessarily limited edition of this publication it is impossible to distribute it free to any person or institution other than State and county officials actually engaged in planning or constructing public highways, instructors in highway engineering, and periodicals upon an exchange basis. At the present time additions to the free mailing list can be made only as vacancies occur. Those desiring to obtain PUBLIC ROADS can do so by sending \$1 per year (foreign subscription \$1.50), or 10 cents per single copy, to the Superintendent of Documents, United States Government Printing Office, Washington, D. C.

CERTIFICATE: By direction of the Secretary of Agriculture, the matter contained herein is published as administrative information and is required for the proper transaction of the public business.

EXPERIMENTAL BITUMINOUS TREATMENT OF SANDY-SOIL ROADS

REPORT ON EXPERIMENTS IN SOUTH CAROLINA

Reported by PAUL F. CRITZ, Associate Highway Engineer, United States Bureau of Public Roads and H. L. SLIGH, Division Engineer, South Carolina State Highway Department

A BITUMINOUS experimental road was constructed in Horry County, S. C., in 1927. It is still in service, and the necessary maintenance has been such that the original construction has been preserved on about one-half of the project and the remainder has been modified only by the type of surface treatments applied.

The purpose of this experiment was to obtain information as to practicable methods of stabilizing the surfaces of roads built of the local materials characteristic of the southeastern coastal plain. Materials such as clays and mineral aggregates ordinarily considered satisfactory for stabilizing were not economically available and consequently bituminous materials were selected as the stabilizing agent.

At the time this road was built little information was available for the guidance of the engineers in the design of the sections and methods of construction. Since these experimental sections were built, however, considerable progress has been made in the field of low-cost bituminous road construction, and it is interesting to note that all of the materials and equipment and practically the same methods used in this experiment are in common use at the present time.

A better understanding of the methods and materials that give greater assurance of successful construction today has been made possible in a large measure by the information obtained from experimental roads. The fact that much of the road work done today by the State of South Carolina is based upon results obtained from this experiment indicates that it has been of considerable value.

ECONOMICAL METHOD OF STABILIZING SANDY SOILS NEEDED

Various methods of bituminous treatment to improve low-type roads have been employed by practically every State. Although many different materials and methods have been used, the improvements may be divided roughly into two classes: (1) The mat type of treatment, which is constructed not less than 1 inch thick; and (2) the surface-treatment type, in which the treatment is usually not more than 1 inch thick. Both types depend, as does any flexible surface, directly upon the base for support.

A wide variety of bituminous materials and aggregates have been used successfully for such work, and while different types of surfaces have resulted, there has been no special difficulty in providing a satisfactory surface for roads whose bases and subgrades were capable of supporting traffic.

For those localities where the roads were composed of loosely bound soil, such as sand or mixtures of sand, silt, and clay that were inherently weak, the problem of improvement was more difficult. Such a condition is found in the South Atlantic coastal area in general, and the eastern part of South Carolina in particular.

An appreciable mileage of the roads in this territory traverses relatively low, swampy areas that offer little

 $114288^{\circ} - 37 - 1$

opportunity for adequate drainage of the right-of-way because the ground-water level in many places is approximately at the elevation of the ground surface.

The locality these roads serve is mainly agricultural but pleasure resorts on the coast attract numbers of visitors. The traffic carried is variable in character and volume, ranging from fast-moving passenger cars to slow-moving, steel-tired vehicles carrying relatively heavy loads.

The soil composing these roads is predominantly sand containing clay and silt in varying proportions. As a rule no uniformity of composition exists, with the result that a satisfactory surface condition is the exception rather than the rule. The sand is composed of poorly graded, small-size particles. The clay possesses little binding power and slakes rapidly, breaking up in both wet and dry weather.

The combining of sand and clay produces a material which crumbles and becomes excessively dusty in dry weather. With continued dry weather traffic quickly cuts into the soil until the road becomes all but impassable. In wet weather water quickly softens the sand-clay and also causes the road to become almost impassable.

The stability of the surface, therefore, is as variable as the composition of the road material. On a given day the sandier portions might be extremely loose and difficult to travel over, while the portions containing some clay would be more stable but most likely would be very dusty. On the following day, if it had rained and the road was very moist, the sandier portions might present the better surface for traffic and the areas abounding in clay would be sloppy and rutted. Upon drying, these latter areas would regain some stability but the sandier portions would rapidly lose the stability provided by the moisture they had held temporarily. In all weather such surfaces are difficult to maintain in any condition approaching smoothness.

Obviously, the serviceability of a road of this kind is very limited and is not increased permanently by ordinary routine maintenance. In addition, the cost of maintenance under such conditions becomes an economic loss, especially when compared with the maintenance costs after the experimental surfaces were built. This later maintenance added to the permanent improvement of the road to such an extent that its cost in a large measure could be credited to betterment rather than to maintenance alone.

With a considerable mileage of such roads in need of immediate improvement, and with a relatively small amount of funds available for such work, South Carolina was confronted with a problem somewhat greater than existed in those States where the untreated roads were providing a satisfactory degree of serviceability and where it was necessary only to design a treatment that would either increase or make relatively permanent their present serviceability.

VARIOUS TARS AND ASPHALTS USED ON SECTIONS OF EXPERIMENT

Experience has shown the suitability of sand as road surfacing material when mixed with a satisfactory binder. It is also recognized that sand, properly confined, has high bearing value irrespective of its grading. Consequently, the problem in South Carolina was that of so treating the sand or mixture of sand, silt, and inferior clay that advantage might be taken of these inherent qualities.

To develop a satisfactory and economical method of improving these loosely bonded, sand-clay roads, the South Carolina State Highway Department, in cooperation with the Bureau of Public Roads, constructed an experimental highway during 1927. This highway, 20.6 miles in length and approximately 20 feet wide, extends north and west from the northwest city limits of Conway, S. C., to Galivants Ferry, S. C. The road on which the experimental sections were built was typical of those of the Atlantic coastal area and, in general, was quite unsatisfactory as a highway. Portions of it, passing through low, swampy areas, were poorly drained. Throughout its length there existed combinations of sand and clay ranging from practically pure sand to mixtures fairly high in clay. Its behavior in wet and dry weather was typical of the loosely bound, sand-clay roads of this area whose behavior has already been described.

Part of the project lies on United States Highway No. 701 and all of it lies on United States Highway No. 501, which is an arterial highway to the coast. During the spring and summer months it carries both heavy and light, fast-moving traffic. During the cropmarketing seasons the main traffic is heavily loaded vehicles, a fair portion of which is on narrow steel tires.

The experimental road was constructed during the period from May to October 1927 and was divided into eight experiments, some of which were subdivided into sections. Bituminous mats were constructed on all sections; some were designed to serve as wearing surfaces and others to serve as bases to which additional surface treatments were applied. Some of the sections were designed for machine maintenance and others for maintenance such as is ordinarily applied to macadam-like surfaces. One experimental section, a double-application surface treatment laid directly upon the sand-clay soil, was included for comparison with the other experimental sections of the project and also with similar treatments successfully applied in other parts of the State where the roadbed soil was believed more suitable for such treatment. Locations and descriptions of the experimental sections are shown in figures 1, 2, 3, and 4, which also show the extent and character of the various re-treatments applied.

Both hot- and cold-application tars and asphalts were used in construction. The cold-application tars had consistencies of 8–13, 18–25, and 25–35 specific viscosity, Engler, at 40° C., and the hot-application tar had a float of 155 at 32° C. The tar of 8–13 viscosity was used to prime an untreated base preceding surface treatment; the tar of 18–25 viscosity was used as a binder in the mixed base and for the surface enrichment of the mix without the addition of a mineral cover; and the tar of 25–35 viscosity and the hot tar were used as binders with stone cover in the surface treatment of mixed bases.

Two types of the cold-application asphaltic materials were used—rapid-curing and slow-curing materials. The former were various grades of asphalt cements ranging in penetration from 85 to 180, cut back to low viscosity with a heavy naphtha distillate. The latter were slow-curing, liquid asphaltic materials produced by different processes of refining. Both the rapid- and slow-curing asphaltic materials were used as binders in the mixed bases and for surface treatment of the mixed bases. When used for surface treatment, the rapidcuring cutbacks were used with mineral aggregate cover while the slow-curing oils were used only for surface enrichment with no mineral cover material.

The hot-application material was an asphaltic cement and was used only in surface treatment with stone cover. All asphaltic materials came from a single refinery as did all tar products used in the experiments. Analyses of these materials are given in tables 1 and 2, with the exception of the slow-curing oil E and the 25–35 viscosity tar, analyses for which are not available. Amounts used in each section are given in figures 1, 2, 3, and 4.

Crushed granite, pea gravel, sand, and treated material bladed from the mixed mats were used as cover materials. The mechanical analyses of the stone, gravel, and sand are given in table 3.

BITUMINOUS MATS BUILT USING EXISTING ROAD MATERIALS

Prior to actual construction of the experimental sections, the road had received the customary routine maintenance but little had been done in the way of permanent improvement. Drainage structures had been installed where there was considerable run-off and slight fills and cuts had been made. In general the grade, with respect to the adjoining area, was low in comparison with standards of drainage and grade in use at the present time.

The stationing begins at Conway and, for the purpose of this report, the road may be considered as extending east and west. References to "east" or the "east end of an experiment" are therefore to be taken to mean the beginning of the experimental section or the end nearest Conway.

The initial step in constructing the mixed base was preparation of the roadbed soil for treatment. This involved scarifying to the depth desired and pulverizing the loosened material with disk harrows and blade graders. On some sections the soil was already in such a loose condition that the blade grader, without scarifying, readily converted it into a well pulverized mass. As the material was loosened, it was moved to the roadside into windrows until the amount necessary for the required thickness of mat had been accumulated and was then spread over the full width of the road.

After the material was evenly distributed, usually in half-mile units, bituminous material was applied with 600-gallon pressure distributors. The total amount of bitumen was spread in two or more applications, and after each application a disc harrow turned the mixture of bitumen and soil. The object of this preliminary mixing was to prevent the early loss of light constituents of the bitumen, to protect passing traffic, and to prevent the accumulation of pools of bitumen in depressions and wheel tracks.

Final mixing was done by power-drawn graders which bladed the mixture back and forth across the road until it presented a homogeneous appearance. Because of varying composition and grading of the soil, some portions of the unit under construction might appear too lean or too rich. Additional bitumen or soil was worked into such portions until they appeared satis-

0	1	1
4	0	T

	EXPERIMENT-I SECTION-A CONSTRUCTION	EXPERIMENT-I SECTION-B CONSTRUCTION
STA.		110 120 130 140 150
MIXED BASE	2-INCH, USING 1.30 GALLONS ISO-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	2-INCH, USING 1.30 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPMTHA
PRIME	0.18 GALLON 150-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA 0.35 GALLON 150-200 PENETRATION ASPHALT, HOT	0.16 GALLON 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA 0.35 GALLON 150-200 PENETRATION ASPHALT, HOT
COVER	SO POUNDS $I_4^{\mu} - \frac{1}{4}^{\mu}$ GRANITE	50 POUNDS $1\frac{1}{2} - \frac{1}{2}^{*}$ GRANITE
	RE-TREATMENTS	RE-TREATMENTS
JULY 1927		0.50 GAL. 85-100 C 8. PEA GRAVEL
DEC. 1927		lessend
DEC. 1928	1° 1°	
DEC. 1920	0.24 GAL 150-180 C B. 20 LBS $\frac{3}{4}^{-} - \frac{1}{4}^{-}$ GRANITE	many services and a service an
OCT. 1929	25LBS 2 - 4 STONE 35LBS 2 - 4 STONE	0.38 GAL. 150-200 C B. 30 LBS. $\frac{3}{4} - \frac{1}{4}$ STONE
APR. 1930	0 48 GAL 150-200 C.B. 80 LBS $\frac{3}{4} - \frac{1}{4}$ STONE 0 32 GAL. 150-200 C.B. 45 LBS $\frac{3}{4} - \frac{1}{4}$ STONE	
MAY 1931	0.31 GAL 150-200 C.B. (ALSO ON) REMIXED. NO OIL ADDED. SEAL, 045	0.31 GAL. 150-200 C.B. 40 LBS $\frac{3^u}{4} = \frac{1^o}{4}$ STONE
	40LBS 3 - 4 STONE A GAL. 150-200 C B. 50LBS. 1 - 4 STONE E	······································
MAY 1932	******	
MAY 1933	0.65 GAL 85-100 C. 8. 60 LBS. $\frac{3^{\prime\prime}}{4} - \frac{1^{\prime\prime}}{4}$ STONE	0.65 GAL. 85-100 C.B. 60 LBS. 34 14 STONE
JUNE 1934	0.35 GAL 85-100 C.B. 40 LBS. $\frac{3}{4} - \frac{1}{4}$ STONE	0.35 GAL 85-100 C 8. 40 LBS: $\frac{3^{\prime\prime}}{4}$ = $\frac{3^{\prime\prime}}{4}$ STONE
	Kenner and and the second s	here and the second sec
	EXPERIMENT-2 SECTION-A CONSTRUCTION	EXPERIMENT-2 SECTION-B CONSTRUCTION
STA.	150 160 170 180	190 200 205
MIXED BASE	2-INCH, USING 2.06 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	2-INCH, USING 1.86 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
SEAL	0.33 GALLON 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	0.39 GALLON 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
COVER	40-45 POUNDS 14"-1" GRANITE	20 POUNDS PEA GRAVEL
	RE-TREATMENTS	RE-TREATMENTS
JULY 1927		
DEC. 1927	0.27 GAL. 85-100 C.B. 15 LBS. SAND	0.20 GAL. 85 - 100 C B. 20185.PEA GRAVEL
DEC. 1928	an a constant of the second of	0.24 GAL. 85-100 C.B. 20 LBS. PEA GRAVEL
		The a state to be
OCT. 1929		RÉMIXED WITH NO DIL ADDED. SEAL, 0.39 GAL. 85-100 C B. COVER, 40 LBS.PEA GRAVEL 85-100 C B. COVER, 40 LBS.PEA GRAVEL
APR. 1930		
MAY 193		0.31 GAL. 85-100 C.B. 35LBS.PEA GRAVEL
MAY 193		and a second and the second and the second and the second s
	······································	
MAY 193	0.65 GAL. 85-100 C.B. 60 LBS. $\frac{3^2}{4} - \frac{1^{\prime\prime}}{4}$ STONE	**************************************
JUNE 1934		0.62 GAL 85-100 C.B. 45 LBS.PEA GRAVEL AND 5 LBS. SAND
	EXPERIMENT-2 SECTION -C	EXPERIMENT-2 SECTION-D
	CONSTRUCTION	CONSTRUCTION .
STA MIXED BASI	205 210 215 220 221 2-INCH,USING 2.16 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	225 230 235 2-INCH,USING 2.20 GALLONS 100-120 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
PRIME		
SEAL	0.40 GALLON 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	0.40 GALLON 100-120 PENETRATION ASPHALTCUT BACK WITH NAPHTHA
COVER	20 POUNDS SAND RE-TREATMENTS	20 POUNDS SAND RE-TREATMENTS
JULY 192		
	······································	······································
DEC. 192	Concernation and a concernation of the concern	0.29 GAL 100-120 C B SAND REMAED WITH I.SO GALS. 85-100 C B. SEAL, 0.39 GAL
DEC. 192	REMIXED WITH SOGALS 85 -100 C.B. SEAL, 0.39 GAL 85 -100 C.B. COVER, 40 LBS SAND	85-100 C B. COVER; 40 LBS. SAND
OCT. 192	COVER, 40 LBS, SAND REMIXED WITH NO OIL ADDED. SEAL, 0.39 GAL, 85 -100 C.B. COVER, 50 LBS, 15* Å STONE	REMIXED NO OIL ADDED SEAL, 0.36 GAL 100-120 C B. COVER,50 LBS 15 - 1 STONE 30 LBS 3 - 1 STONE
APR. 193		REMIXED NO OIL ADDED SEAL, 0.3 4 GAL. 100-120 C.B. COVER. 30LBS & STONE
		CARK OFRS & \$ STOKE
MAY 193	······································	······································
MAY 193	2 0.39 GAL. 150-200 C.B. 35 LB5. 34 - 4 STONE	0.39 GAL ISO-200C B 35LBS $\frac{3}{4}^{-1} \frac{1}{4}^{*}$ STONE
MAY 193	3	
JUNE 193	***************************************	0.49 GAL. 85 - 100 C. B. 45 L BS $\frac{1}{2} + \frac{1}{4} = 5$ TONE
JONE 195	a construction and a solution and a	CITTERT COLORIAN CONTRACTOR CONTRACTOR CONTRACTOR CONTRACTOR
	EXPERIMENT-2 SECTION-E	EXPERIMENT-2 SECTION -F CONSTRUCTION
STA	CONSTRUCTION 235 245 255 265	275 285 295
MIXED BAS	2-INCH, USING 2.37 GALLONS 100-120 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	2-INCH, USING 1.95 GALLONS 100-120 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
PRIME	0.44 GALLON 100-120 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	0.48 GALLON 100-120 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
COVER	20 POUNDS PEA GRAVEL	45 POUNDS $I_4^{-1} = T$ STONE
L	RE-TREATMENTS	RE-TREATMENTS
JULY 192	7	
DEC. 192	7. 0.29 GAL. 100-120 C.B. PEA GRAVEL	0.29 GAL. 100-120 C.B. 50 LBS. 12 - 2 STONE
	Construction and and and and and and and and and an	1
DEC. 192	3	
OCT. 192		
APR. 193	0 0.26 GAL.100-120 C.B. 40 LBS.PEA GRAVEL	
MAY 193	Terreterenterenterenterenterenterenteren	0.33 GAL 85-100 C 8.0N LEFT SIDE, 0.33 GAL, 150-180 C.B. ON RIGHT SIDE, 40 LBS, 4 - 5 STONE
	· · · · · · · · · · · · · · · · · · ·	farmer and a contraction of the
MAY 193	frances and	
MAY 193	3	
JUNE 193	4	

FIGURE 1.—CHART SHOWING CONSTRUCTION AND CHARACTER OF RE-TREATMENTS APPLIED TO EXPERIMENTAL SECTIONS 1 TO 2-F, INCLUSIVE.

	EXPERIMENT-2 SECTION-G	EXPERIMENT- 2 SECTION- H
STA.	CONSTRUCTION 307 313	CONSTRUCTION 317 321 325 329 333
MIXED BASE	2-INCH, USING 2.20 GALLONS ISO-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	2-INCH, USING 2.78 GALLONS 150-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
PRIME		0.33 GALLON 150-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
COVER	0.50 GALLON 150-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA 45 POUNDS $ \frac{4}{4}^{T} - \frac{4}{4}^{T}$ STONE	20 POUNDS PEA GRAVEL
	RE-TREATMENTS	RE-TREATMENTS
JULY 1927		
DEC. 1927	REMIXED, ADDING 1.00 GAL. 150-180 C.B. SEAL, 0.35 GAL. 150-180 C.B. 30 LBS. 14 - 4 STONE	REMIXED, ADDING 1.00 GAL. 150-180 C.B. SEAL, 0.20 GAL. 150-180 C.B. 20 LBS. PEA GRAVEL.
DEC. 1928	(and the second and the second s	0.26 GAL. 150 - 180 C.B. 20 LBS. 4 - H STONE
		Concernance and a concernance and the concerna
OCT, 1929		
APR. 1930	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	0.35 GAL. 150 - 200 C.B. 45 L.BS. $\frac{3^2}{4} - \frac{1^4}{4}$ STONE
MAY 1931	0.33 GAL, 85-100 C.B. ON LEFT SIDE 0.33 GAL 150-180 C.B. ON RIGHT SIDE 40LBS $\frac{3^4}{4} - \frac{1'}{4}$ STONE	
MAY 1932		
MAY 1933		0.47 GAL. 85-100 C B. 40 LBS $\frac{2^6}{4} = \frac{1}{4}$ STONE
		funner and a contraction and a
JUNE 1934		
	EXPERIMENT-2 SECTION I	EXPERIMENT 3
STA.	CONSTRUCTION 333 337 341 345 350	CONSTRUCTION 360 370 380 390 400
MIXED BASE	2-INCH, USING 2.00 GALLONS 150-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	2-INCH, USING 1.60 GALLONS SLOW-CURING OIL A
PRIME	0.40 GALLON ISO-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	SURFACE ENRICHMENT - 0.65 GALLONS SLOW - CURING OIL A
COVER	20 FOUNDS SAND	TREATED SOILS
	RE-TREAT MENTS	RE-TREATMENTS
JULY 1927		
DEC 1927	REMIXED, ADDING 1.00 GAL. 150-180 C.B. SEAL, 0.20 GAL 150-180 C.B. 20 LBS. SAND	
DEC. 1928	$\begin{array}{c} 0.26 \text{ Gal} 150-180 \text{ C.B. } 20 \text{ LBS} \frac{3}{2} = \frac{1}{4} \text{ STONE} \end{array}$	REMIXED WITH 142 GALS. SLOW-CURING OIL A REMIXED WITH 2.05 GALS. SLOW-CURING OIL A
OCT. 1929	Summer and a construction of the	Construction and the construction of the const
APR. 1930	0.36 GAL 150-200 C.B. 45LBS. $\frac{3}{2}^{+} \sim \frac{1}{4}$ STONE	
MAY 1931		
MAY 1932		
MAY 1933	0.47 GAL 85-100 C 8. 40 LBS $\frac{3}{4}^{a} - \frac{1}{4}^{a}$ STONE	REMIXED WITH 0.49 GAL. SLOW-CURING OIL A
JUNE 1934	<u>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u>	<u>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u>
L		
L	EXPERIMENT- 4 SECTION- A CONSTRUCTION	EXPERIMENT-4 SECTION-B CONSTRUCTION
STA.	CONSTRUCTION 420 426	CONSTRUCTION 430 440 450 452
MIXED BASE	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C
	CONSTRUCTION 420 426	CONSTRUCTION 430 440 450 452
MIXED BASE PRIME	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE NONE	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE
MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE NONE	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE NONE	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 1.08 GALS 7 REMIXED WITH 0.54 GAL.	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 1.08 GALS 7 REMIXED WITH 0.54 GAL.	CONSTRUCTION 430 440 450 452 3-INCH, USING 2:50 GALLONS SLOW-CURING OIL C NONE NONE NONE
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 1.08 GALS 7 REMIXED WITH 0.54 GAL.	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 1.08 GALS 7 REMIXED WITH 0.54 GAL.	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1931	CONSTRUCTION 400 410 420 420 420 420 420 420 420 420 420 42	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GAL. SLOW-CURING OIL C
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931	CONSTRUCTION 400 410 420 420 420 420 420 420 420 420 420 42	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GAL. SLOW-CURING OIL C NONE NONE <td< td=""></td<>
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1931	CONSTRUCTION 400 410 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 1.05 GALS REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS	CONSTRUCTION 430 440 450 450 450 450 450 450 450 450 45
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1932	400 410 420 426 3-INCH, USING 3.0I GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A 2 T2 GALS SLOW-CURING OIL A 2 T2 GALS SLOW-CURING OIL A SLOW-CURING OIL A	CONSTRUCTION 430 440 450 450 450 450 450 450 450 450 45
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 108 GALS. REMIXED WITH 0.54 GAL. REMIXED WITH 108 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A ACCONCURING OIL A SLOW-CURING OIL A CONSTRUCTION CONSTRUCTION	CONSTRUCTION 430 440 450 450 450 450 450 450 450 450 45
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1933 JUNE 1934 JUNE 1934	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS. REMIXED WITH 1.07 GALS. SLOW-CURING OIL A CAREMIXED WITH 1.07 GALS. CAREMIXED WITH 1.07 GALS. SLOW-CURING OIL A CAREMIXED WITH 1.07 GALS. CAREMIXED WITH 1.07 GALS. SLOW-CURING OIL A CAREMIXED WITH 1.07 GALS. CAREMIXED WITH 1.07 GALS. SLOW-CURING OIL A CONSTRUCTION 272 GALS SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-4 SECTION-C CONSTRUCTION 450 470 471	CONSTRUCTION 430 440 450 450 450 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RETREATMENTS REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION EXPERIMENT-S SECTION-A CONSTRUCTION SQU 485 490 495 SQU 503
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 108 GALS. REMIXED WITH 0.54 GAL. REMIXED WITH 108 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A ACCONCURING OIL A SLOW-CURING OIL A CONSTRUCTION CONSTRUCTION	CONSTRUCTION 430 440 450 450 450 450 450 450 450 450 45
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 CALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS. REMIXED WITH 1.07 GALS. SLOW-CURING OIL A CONSTRUCTION 272 GALS SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-4 SECTION-C CONSTRUCTION 470 477 3-INCH, USING 3.02 CALLONS SLOW-CURING OIL D NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RETREATMENTS REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION -A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION -A CONSTRUCTION 480 485 490 495 500 503 2-INCH, USING 2.40 GALLONS 83-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E SOUP-CURING OIL E SOUP-CURING OIL E
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934 JUNE 1934 STA. MIXED BASE PRIME	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A L REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A L REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A L EXPERIMENT-S SECTION -A CONSTRUCTION SLOW-CURING OIL A L EXPERIMENT-S SECTION -A CONSTRUCTION SURFACE ENRICHMENT - 0.42 GALLONS SIG 490 495 500 503 2-INCH, USING 2.40 GALLONS SIG 50-IBO PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 CALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS. REMIXED WITH 1.07 GALS. SLOW-CURING OIL A CONSTRUCTION 272 GALS SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-4 SECTION-C CONSTRUCTION 470 477 3-INCH, USING 3.02 CALLONS SLOW-CURING OIL D NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RETREATMENTS REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION -A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION -A CONSTRUCTION 480 485 490 495 500 503 2-INCH, USING 2.40 GALLONS 83-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E SOUP-CURING OIL E SOUP-CURING OIL E
MIXED BASE PRIME SEAL COVER ULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1931 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 0.83 GALL SLOW-CURING OIL C REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS. REMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS SLOW-CURING OIL A TREATED TOP SOIL TREATED TOPSOIL TREATED TOPSOIL
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 AFR 1930 MAY 1931 JUNE 1934 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GAL. SLOW-CURING OIL C REMIXED WITH 0.83 GAL. SLOW-CURING OIL C REMIXED WITH 1.07 GALS. REMIXED WITH 0.83 GAL. SLOW-CURING OIL C REMIXED WITH 1.07 GALS. SLOW-CURING OIL A REMIXED WITH 1.07 GALS. LAND 2.72 GALS, SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS, SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS, SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 2.72 GALS, SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 4.00 4.85 SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 4.00 4.85 SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 4.00 4.85 SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A LAND 4.00 4.85
MIXED BASE PRIME SEAL COVER ULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1931 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 AFR 1930 MAY 1931 JUNE 1934 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OL C NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS REMIXED WITH 0.83 GAL. SLOW-CURING OL C REMIXED WITH 0.83 GAL. SLOW-CURING OL C REMIXED WITH 1.07 GALS. REMIXED WITH 0.83 GAL. SLOW-CURING OL A SLOW-CURING OL A SLOW-CURING OL A SLOW-CURING OL A REMIXED WITH 1.07 GALS. SLOW-CURING OL A SLOW-CURING OL A SLOW-CURING OL A EXPERIMENT-S SECTION -A CONSTRUCTION SLOW-CURING OL A 480 485 490 495 500 503 2:INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OL E TREATED TOPSOL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1928	CONSTRUCTION 400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS REMIXED WITH 0.54 GAL SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH 1.07 GALS REMIXED WITH 1.07 GALS SLOW-CURING OIL A REMIXED WITH 1.07 GALS SLOW-CURING OIL A SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 212 GALS SLOW-CURING OIL A 470 432 460 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1929 DEC. 1929 DEC. 1929	400 410 420 426 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A 2 AEMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A 2 AEMIXED WITH 1.07 GALS. SLOW-CURING OIL A Yee EXPERIMENT-4 SECTION-C CONSTRUCTION 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1929 APR. 1930 MAY 1931	400 410 420 426 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A 2 AEMIXED WITH 1.07 GALS. SLOW-CURING OIL A SLOW-CURING OIL A 2 AEMIXED WITH 1.07 GALS. SLOW-CURING OIL A Yee EXPERIMENT-4 SECTION-C CONSTRUCTION 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER DEC. 1927 DEC. 1927 DEC. 1927 DEC 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 APR. 1930 MAY 1931 MAY 1932	400 410 420 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH LOS GALS. REMIXED WITH 0.54 CAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A REMIXED WITH LOS GALS. REMIXED WITH 1.03 GALS. REMIXED WITH 1.03 GALS. REMIXED WITH LOS GALS. REMIXED WITH 1.03 GALS. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-4 SECTION-C CONSTRUCTION 470 477 452 460 470 477 NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RETREATMENTS REMIXED WITH 0.87 CAL SLOW-CURING OIL D 1	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS
MIXED BASE PRIME SEAL COVER DEC. 1927 DEC. 1927 DEC. 1927 DEC 1928 OCT. 1929 APR 1930 MAY 1931 MAY 1933 JUNE 1934 STA. MIXED BASE PRIME SEAL COVER JULY 1927 DEC. 1927 DEC. 1927 DEC. 1928 APR. 1930 MAY 1931 MAY 1932	400 410 420 426 426 3-INCH, USING 3.01 GALLONS SLOW-CURING OIL B NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS REMIXED WITH 1.08 GALS. REMIXED WITH 0.54 GAL. SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A 2 AED ZEREMIXED WITH 1.07 GALS. SLOW-CURING OIL A Yes 2 AED ZEREMIXED WITH 1.07 GALS. SLOW-CURING OIL A Yes 2 ZERGALS SLOW-CURING OIL A SLOW-CURING OIL A Yes Yes 2 AED ZEREMINENT-4 SECTION-C CONSTRUCTION 470 477 3-INCH, USING 3.02 GALLONS SLOW-CURING OIL D NONE <	CONSTRUCTION 430 440 450 450 452 3-INCH, USING 2.50 GALLONS SLOW-CURING OIL C NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE NONE RE-TREATMENTS RE-TREATMENTS NONE NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL C NONE NONE REMIXED WITH 0.83 GAL SLOW-CURING OIL C SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A CONSTRUCTION SLOW-CURING OIL A SLOW-CURING OIL A SLOW-CURING OIL A EXPERIMENT-S SECTION-A CONSTRUCTION SQ0 SQ3 2-INCH, USING 2.40 GALLONS 85-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA SURFACE ENRICHMENT - 0.42 GALLON SLOW-CURING OIL E TREATED TOPSOIL TREATED TOPSOIL RE-TREATMENTS RE-TREATMENTS RE-TREATMENTS

FIGURE 2.—CHART SHOWING CONSTRUCTION AND CHARACTER OF RE-TREATMENTS APPLIED TO EXPERIMENTAL SECTIONS 2-G TO 5-A, INCLUSIVE.

JUNE 1934

	EXPERIMENT-5 SECTION-B	EXPERIMENT-5 SECTION-C
6T.4	CONSTRUCTION 503 512 521 530	CONSTRUCTION 540 550 556
STA.	2-INCH, USING 2.20 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	3-INCH, USING 2.90 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
PRIME	SURFACE ENRICHMENT- 0.40 GALLON 1 50-180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	SURFACE ENRICHMENT- 0.42 GALLON 150 -180 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
SEAL		
COVER	TREATED TOPSOIL RE-TREATMENTS	TREATED TOPSOIL RE-TREATMENTS
JULY 1927		
DEC. 1927		
DEC. 1928		
OCT. 1929		
APR. 1930		
MAY 1931		
MAY 1932		
MAY 1933	0.46 GAL.85 - 100 C.B. 40 LBS. 3 ⁵ - 1 ⁿ STONE	0.46 GAL. 85-100 C.B. 40 LBS. $\frac{3^n}{4} - \frac{1}{4}$ STONE
	Construction and the construction of the const	concentration and the second for the second se
JUNE 1934		
	EXPERIMENT-5 SECTION-D	EXPERIMENT-6 SECTION - A
	CONSTRUCTION	CONSTRUCTION
STA.	556 560 570 580 582 3-INCH, USING 3.01 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	590 600 600 2-INCH, USING 2.72 GALLIONS 18-25 SPECIFIC VISCOSITY TAR
PRIME	SURFACE ENRICHMENT - 0.42 GALLON SLOW CURING OIL E	SURFACE ENRICHMENT - 0.27 GALLON 18-25 SPECIFIC VISCOSITY TAR
SEAL		
COVER	TREATED TOPSOIL RE-TREATMENTS	TREATED TOPSOIL
JULY 1927	RETIKEAIMENIS	RE-TREATMENTS
DEC. 1927		
DEC. 1928		
OCT 1929	0.39 GAL. 85-100 C.B. 40 LBS: $\frac{1}{2}$ · $\frac{1}{4}$ STONE	
	concernance and a conce	
APR. 1930		······································
MAY 1931		0.36 GAL 35-50 SP. VIS. TAR 37 LBS $\frac{3}{4}^{-}$ $\frac{1}{4}^{''}$ STONE
MAY 1932		<u></u>
MAY 1933		
	0.46 GAL.85 - 100 C.B. 40 LBS. $\frac{3}{4}$ - $\frac{1}{4}$ " STONE	
JUNE 1934		
	EXPERIMENT-6 SECTION-B	EXPERIMENT-6 SECTION-C
	CONSTRUCTION	CONSTRUCTION
MIXED BASE	610 620 630 636 3-INCH,USING 3.72 GALLONS 18-25 SPECIFIC VISCOSITY TAR	640 660 688 2-INCH, USING 2.75 GALLONS 18-25 SPECIFIC VISCOSIŤÝ TAR
PRIME	SURFACE ENRICHMENT - 0.28 GALLON 18-25 SPECIFIC VISCOSITY TAR	0.26 GALLON 18-25 SPECIFIC VISCOSITY TAR
SEAL		0.37 GALLON 25-35 SPECIFIC VISCOSITY TAR
COVER	TREATED TOPSOIL RE-TREATMENTS	60 POUNDS I 🚛 – 🛣 STONE RE – TREATMENTS
JULY 1927		
DEC 1927		
DEC. 1928		
OCT. 1929		
APR. 1930		
MAY 1931	0.36 GAL. 35-50 SP. VIS. TAR, 37 LBS. $\frac{3}{4}^{-} - \frac{1}{4}^{-}$ STONE	0.36 GAL. 35-50 SP.VIS. TAR, 37 LBS. $\frac{3}{4}^{-1} - \frac{1}{4}^{-1}$ STONE
MAY 1932		
MAY 1933		
JUNE 1934		
	EXPERIMENT-6 SECTION-D	EXPERIMENT-6 SECTION-E
	CONSTRUCTION 688.690 700 710 720 730 742	CONSTRUCTION 750 760 770 780 790 794
MIXED BASE	688.690 700 710 720 730 742 2-INCH, USING 2.59 GALLONS 18-25 SPECIFIC VISCOSITY TAR	
PRIME		2-INCH, USING 18-25 SPECIFIC VISCOSITY TAR, CALLONS PER SQUARE YARD AS FOLLOWS: 1.77 - 2.93 - 2.08 0.25 GALLON 18-25 SPECIFIC VISCOSITY TAR
	0.27 GALLON 18-25 SPECIFIC VISCOSITY TAR	
SEAL	0.27 GALLON 18-25 SPECIFIC VISCOSITY TAR 0.35 GALLON HOT TAR (GRADE 2)	0.32 GALLON HOT TAR (GRADE 2)
SEAL COVER	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER	0.35GALLON HOT TAR (GRADE 2)	0.32 GALLON HOT TAR (GRADE 2)
JULY 1927	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
JULY 1927	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER JULY 1927 DEC. 1927 DEC. 1928	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER JULY 1927 DEC. 1927 DEC. 1928	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929	0.35 GALLON HOT TAR (GRADE 2) 60 POUNDS $I_4^{\pm -} \frac{1}{4}$ 'S TONE	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS 14° 4″ 5TONE
COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR. 1930	0.35GALION HOT TAR (GRADE 2) 60POUNDS I ⁺ ₄ * STONE RE-TREATMENTS	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS '# \$\$TONE RE-TREATMENTS
COVER JULY 1927 DEC. 1927 DEC. 1928 OCT. 1929 APR. 1930 MAY 1931	0.35GALION HOT TAR (GRADE 2) 60POUNDS I ⁺ ₄ * STONE RE-TREATMENTS	0.32 GALLON HOT TAR (GRADE 2) 60 POUNDS '# \$\$TONE RE-TREATMENTS

FIGURE 3.—CHART Showing Construction and Character of Re-treatments Applied to Experimental Sections 5-B to 6-E, Inclusive.

-
3
2
10
~
2
-
0
0
2
-
5
0)
-
3
2
8
12
~
0
2
0
.6
4
0
2
2
10
nst
2
0
0
0
~
3
· ~
~
0
0
00
2
00
-
0
.0
2
0
40
2
~
2
C
(2)
. ~
~
haltic mate
~
Priling
0
2
SI
ast
asp
f asp
of asp
of as1
of as1
s of asp
es of asp
ses of asp
ses of asp
yses of asp
lyses of asp
alyses of asp
valyses of asy
nalyses of as ₁
Inalyses of asp
Analyses of asp
-Analyses of asp
-Analyses of asp
-Analyses of asp
Analyses of asp
LAnalyses of asp
1Analyses of asp
1Analyses of asp
a 1Analyses of asp
E 1Analyses of asp
LE 1Analyses of asp
BLE 1.—Analyses of asp
BLE 1.—Analyses of asp
ABLE 1Analyses of asp
ABLE 1Analyses of
ABLE 1Analyses of
TABLE 1Analyses of asy

Asphaltic cement	150-200 penetra- tion	4 tests	Construc- tion	1927	7-A, B, 7-A, B,	eosltu2 Juentseri	952 0.956 0.959 0.938 0.949 0.949 0.949 0.950 1.01-1.03 156 150 20 20 20 225-275 100-1.03 156 150 20 20 22 225-275 100-1.03 156 57 45 30 22 23 23-3 157 44 23 24.2 23 24.2 23-4 156 22.7 25.3 24.2 24.3 20-43 30-43 170 135 92.6 23.4 23.7 25.4 20.1 30-43 100 100 95.5 100 91.36 90.45 90.40 0.09-0.20 100 105 13 91.4 13 91.4 110+ 110 110+ 91.3 90.4 10 91.9 97-26 110 110+ 110+ 110+ 110+ 110+ 110+ 110 110+ 9
	200 ation	35424	Re- treat- ment	1931	1-A, B	e s t r u Z treatment	0, 950 23, 2 23, 2 23, 4 10, 10 13, 8 23, 4 10, 10 13, 8 23, 4 23, 4 24,
	150-200 penetration	32646	Re- treat- ment	1929	1-A, B, 8	Surface treatment	0. 949 366 366 37 309 380 390,85 13,9 104 11044
		35425	Re- treat- ment	1931	2-F, G	Surface treatment	0.949 0.949 28.2 28.2 23.42 112.4 114.4 114.4 110.4 99.156 99.156 99.55 114.4 110.4 99.85 99.85 110.4 10
	penetration	30992	Re- treat- ment	1928	1-A, 2-H, I	Surface treatment	0.938 203 232 232 232 232 252 9 9 9 9 9 9 9 9 9 9 9 9 9 177 6 5 5 5 173 6 100
phtha		29882	Re- treat- ment	1927	2-G, H, I	Remix and surface treatment	0.959 0.959 150 150 150 150 150 150 150 150
rith na	150-180	29145	Con- struc- tion	1927	2-H, I, 5-C	Mix and surface treatment	0.956 305 57 57 237.1 1355 1335 1335 1335 1335 1335 1335 13
back w		29088	Con- struc- tion	1927	1-A, 2-G, 5-B,	Mix and surface treatment	
an, cut	120 ation	32644	Re- treat- ment	1929	2-D	Surface treatment	0.9499 371 372 372 372 372 372 372 156 39,136 16,2 16,2 16,2 39,136 16,47 110 47 110 47 110 47 110 47 110 47 110 47 110 47 110 47 110 47 100 100 100 100 100 100 100 100 100 10
on give	100-120 penetration	29144	Con- struc- tion	1927	2-D, E, F	Mix and surface treatment	0. 957 600 1056 1056 1056 1056 1056 1056 1056
netrati		39069	Re- treat- ment	1933	$^{1-A,}_{B,}$ $^{2-A,}_{B,}$ $^{2-A,}_{C,B}$	Surface treatment	0.948 29.5 29.5 21.3 21.3 21.4 21.4 21.4 21.4 21.4 21.4 21.5 21.5 21.5 21.5 21.5 21.5 21.5 21.5
Asphalts of the penetration given, cut back with naphtha		35426	Re- treat- ment	1931	2-B, F, G, 7-A, B, C,	Surface treatment	$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$
lalts of	ation	32645	Re- treat- ment	1929	5-Å, D, C.	9 2 2 î 1 u Z Ju9mizeri	0. 944 30 31 32 31 31 31 32 55 56 66 99 32 66 99 30 56 30 30 30 30 30 30 30 30 30 30 30 30 30
Aspl	penetration	32643	Re- treat- ment	1929	2-B, C	S urface treatment	0. 953 362 362 362 362 362 362 362 362 362 36
	85-100	30993	Re- treat- ment	1928	2-B, C, D,	Remix and surface treatment	949 0. 938 0 187 29 29 29 29 20 25 3 21 2 2 25 3 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
		29883	Re- treat- ment	1927	1-B, 2-A, B, C, 8	Surface treatment	0.949 2029.0 137 137 137 137 137 137 137 137 137 137
		9 tests	Construc- tion	1927	1-B, 2-A, B, C, 5, 7,	Mix, prime, and surface treatment	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$
	D3	29746	Con- struc- tion	1927	4-C	xiM	0. 974 (0. 1322) 1322 468 9.55 224 222 199 .19 9.19 9.19 9.19 9.19 54 8 8 8 8 8 8 10 10 10 10 10 10 10 10 10 10 10 10 10
	C 3	29743	Con- struc-s tion	1927	4-B	xiM	
oils	ŝ	29148	Con- struc-s tion	1927	4-A	xiM	
Slow-curing		39068	Re- treat- s ment	1933	3, B, C	хітэЯ	$\begin{array}{ c c c c c c c c c c c c c c c c c c c$
Slow-	23	30994	Re- treat- ment	1928	3, 4-A	хітэЯ	0.972 138 138 138 138 138 138 156 100 100 000 000 000 110 45 728 128 1115 115 115 115 115 115 115 115 115 1
1. S.	A	29147	Con- Struc- tion	1927	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	Mix & nd surface furichment	0, 941 1155 133 133 5, 5, 6 100 100 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	11	29143	Con- struc-s tion	1927	00	surface tnemdoirne	0.942 150 150 8.2 8.2 8.2 99.76 99.76 5.3 5.3 5.3 5.3 5.3 5.3 5.3 5.3 5.3 5.3
Type of material	Designation	Laboratory number	Method of use	Date used.	Sections on which used	Purposes for which used	Analyses: Analyses: 0.942 0.941 0.972 1.0 Flash point. 0.942 0.941 0.972 1.0 0.972 1.0 Burning point. 0.942 0.941 0.942 0.941 0.972 1.0 Burning point. 0.942 0.943 0.941 0.972 1.0 Specific viscosity. Engler, at 50° 0.00 1.0 1.13 1.13 Specific viscosity. Engler, at 50° 0.00 1.0 1.13 1.13 Specific viscosity. Engler, at 50° 0.00 8.1 1.13 1.13 Scienting point. 0.95 0.913 0.91 0.91 1.0 Residue float at 32° 0.00 0.00 9.1 1.15 1.15 Residue float at 50° 0.00 0.00 9.76 9.76 9.76 9.76 Residue float at 50° 0.01 0.00 9.76 9.76 9.76 9.76 Residue float at 50° 0.01 0.97 9.76 9.76 9.76 9.76 9.76 9.76 9.76 9.76 9.76 9.76

	EXPERIMENT-7 SECTION-A CONSTRUCTION	EXPERIMENT-7 SECTION-B CONSTRUCTION
STA.		870 890 910 930 950
MIXED BASE	2-INCH, USING 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA, GALS PER SQ YD.	2-INCH, ISING 2 65 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
PRIME	- 2.18 - 2.19 -	0 20 GALLON 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA
SFAL	0.38 GALLON 150-200 PENETRATION ASPHALT, HOT	0.40 GALLON 150-200 PENETRATION ASPHALT, HOT
COVER	60 POUNDS 14 - 4 STONE	60 POUNDS 14 - 4 STONE
	RE TREATMENTS	RETREATMENTS
JULY 1927		
DEC 1927		
DEC. 1928		
OCT. 1929		REMIXED WITH NO DIL ADDED SEAL, 0.27 GAL 85-100 C B 30LBS $\frac{3}{4} - \frac{1}{4}$ STONE
APR 1930		· · · · · · · · · · · · · · · · · · ·
MAY 1931	0.32 GAL, 85-100 C B 40LBS 3 - 4 STONE	0.32 GAL 85-100 C 8 40L8S $\frac{3}{2} - \frac{4}{7}$ STONE
MAY 1932	0.42 GAL ISO - 200 C B 35LBS $\frac{3}{4} - \frac{1}{4}$ STONE	0.40 GAL, 150- 200 C B. 35 LB5 3 - 4 STONE
MAY 1933		
JUNE 1934		
	EXPERIMENT-7 SECTION-C CONSTRUCTION	EXPERIMENT-8 CONSTRUCTION
STA	950 960 970 980 990 1000	1020 1040 1060 1087
MIXED BASE	2-INCH, USING 2.16 GALLONS 85-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA	NONE
PRIME		-0.55 GAL 85-100 C B
COVER	0.50 GALLON B5-100 PENETRATION ASPHALT CUT BACK WITH NAPHTHA 60 POUNDS, $1\frac{2^2}{2^4} - \frac{1}{4}$ STONE	0 3B GALLON ISO - 200 PENETRATION ASPHALT, HOT 60 POUNDS $ \frac{2\pi}{4} - \frac{2\pi}{4}$ STONE
LOVEN	RE-TREATMENTS	RE-TREATMENTS
JULY 1927	e and a superior	
DEC 1927		0.21 GAL. 85 - 100 C.B. SAND
DEC. 1928		
OCT. 1929	REMIXED, NO OIL ADDED SEAL, 0.45 GAL 85-100 C B. 45LBS 14 - 4 STONE	0.42 GAL 150-200 C B. 40185 3 - 4 STONE
APR. 1930	(0.56 GAL 85-100 C 8 (45 L85 2 - 4 STONE	0.87 GAL 150-200 C 8 80 LBS 2 - 4 STONE
MAY 1931	0 32 GAL. 85-100 C.B. 40LBS. $\frac{3}{4}^{\mu} - \frac{1^{\mu}}{4}$ STONE	0.32GAL 85-100 C 8 40185 # - # STONE
MAY 1932		
MAY 1933		
JUNE 1934		

Figure 4.—Chart Showing Construction and Character of Re-treatments Applied to Experimental Sections 7-A to 8, Inclusive.

TABLE 2.—Analyses of tars used in construction and re-treatment 1

Method of use.			Construction	1		Re-treat- ment
Date used			1927			1931
Material designation	8-13 vis- cosity	1	18-25 viscosit	y	Grade 2 (hot)	35-50 viscosity
Section and purpose for which used Base mix	8		i-A, B, C, D, 6-C, D, E 6-A, B			
Laboratory no	29828	Minimum values	Maximum values	A verage of 6	29753	36043
Analyses: Specific gravity, 25°/25° C Specific viscosity, Engler, at 40° C. Float test at 32° C Bitumen soluble in CS2. Organic matter insoluble. Organic matter insoluble. Dercent. Organic matter insoluble. Dercent. Distillation, A. S. T. M. D20-27T (by weight)— -170° C. 235° -270° C. 270°-300° C. 270°-300° C. Percent. Softening point of residue. ° C.	$\begin{array}{c} 1.136\\ 10.9\\ 94.63\\ 3.80\\ .07\\ 1.50\\ 1.32\\ 5.68\\ 13.30\\ 9.94\\ 69.12\\ 39.6\end{array}$	1. 152 19. 3 03. 39 2. 66 0 1. 50 6. 10 10. 10 7. 39 6. 10 10. 10 7. 39 71. 44 45. 8	$\begin{array}{c} 1.\ 165\\ 26.\ 4\\ 95.\ 76\\ 4.\ 85\\ .06\\ 1.\ 80\\ 1.\ 15\\ 8.\ 74\\ 11.\ 16\\ 8.\ 53\\ 73.\ 63\\ 49.\ 9\end{array}$	$\begin{array}{c} 1.158\\ 22.3\\ 95.14\\ 3.17\\ .02\\ 1.67\\ 1.02\\ 7.44\\ 10.64\\ 7.86\\ 72.61\\ 47.6\end{array}$	$\begin{array}{c} 1.\ 206\\ 1.55\\ 91.\ 51\\ 8.\ 49\\ 0\\ 0\\ 0\\ 0\\ 0\\ 3.\ 35\\ 6.\ 10\\ 6.\ 16\\ 83.\ 95\\ 49.\ 5\\ 49.\ 5\\ \end{array}$	1, 151 48, 7 96, 09 3, 60 23 0 3, 60 3, 60 4, 83 10, 54 8, 91 75, 20 37, 4

¹ Data are not available for the tar of 25-35 viscosity used in surface-treating section 6-C.

TABLE 3.—Mechanical analysis of mineral aggregates used as cover material

Experiment no	2	2	1, 2, 6, 7, 8	8
Material	Pea gravel	Sand	Granite	Granite
Laboratory no	29558	29557	29630	29631
Retained on — 1 ⁴ ;inch screen 1 ⁴ inch screen 3 ⁴ ;inch screen 1 ⁴ ;inch screen No. 20 sieve No. 30 sieve No. 40 sieve No. 50 sieve No. 100 sieve No. 100 sieve No. 20 sieve			Percent 4 33 73 92 98	Percent 2 35 68 92

factory, after which the mixture was respread uniformly for compaction under traffic. Light blading was continued during compaction to obtain a smooth surface. Some difficulty was experienced in obtaining uniform distribution of traffic during this stage. Fast-moving vehicles tended to travel in the center only and slowmoving, steel-tired vehicles traveled along the edges where the wheels cut into the mixture instead of compacting it. Barriers first placed in the center of the road and then moved transversely at intervals successfully divided traffic into two lanes, causing more uniform compaction of each half of the road.

For the two sections designed for machine maintenance, this concluded the construction operation except for occasional light blading to retain surface smoothness. The analyses of the sand-clay and the resulting bituminous mixtures are given in tables 4 and 5.

AMOUNTS OF BITUMINOUS MATERIALS NEEDED IN MIXTURES WERE ESTIMATED

The remainder of the experimental sections were designed for patrol maintenance and were provided with wear-resisting surfaces obtained by two methods. One method was to enrich the surface portion of the mixed base by a light application of bitumen covered immediately with bituminous-treated soil previously windrowed to the sides of the road. The other method was to surface-treat the mixed base with bitumen and aggregate cover. This surface treatment was placed after allowing the base a period of time in which to become firm and smooth; the actual time varied from 3 or 4 days to a month. On those sections on which the bitumen used in the surface treatment was a coldapplication, low-viscosity material, the bitumen was applied directly upon the smooth, compacted, mixed base and covered immediately with the selected mineral cover material. Where the binding material was a hot application or a fairly viscous cold-application bitumen such as the 25-35 viscosity tar, the mixed base was given a light prime with the same type of bituminous material that was used in the mixed base.

The mineral cover material was spread by hand from piles along the roadside and was hand broomed to obtain uniform distribution. Following its application the surfaces were rolled with 5-ton, three-wheel rollers.

After a few days under traffic, the completed sections varied in appearance, depending upon the air temperature and the materials used. All of the tar sections TABLE 4.—Analysis of road-bed soil used in mixed base construction and as the base for surface treatment of experiment 8. All are group A-2 or A-3 materials

			Mec	hanica	l analy	sis	
Experi- ment no.	Stations repre- sented by sample	Lab- ora- tory no.	Coarse sand 2.0- 0.25 mm	Fine sand 0.25- 0.05 mm	Silt 0.05- 0.005 mm	Clay 0.005 mm	Remarks
I-A	7-12	2884	Pct. 17	Pct. 70	Pct.	Pct. 7	Sandier portion of sec-
1-A	18	$2885 \\ 3140$	14 29	65 56	9 6	12	A verage composition. Do.
2-D	228	3143	21	52	8	19	Clay area.
2-F 2-G	290 310	3141 3142	16 9	75 82	$\frac{3}{2}$	67	Sandy area.
5-B	{ 515-520 503-530	$\frac{3515}{3517}$	6 5	86 88	$\frac{2}{2}$	6	Do. A verage composition.
5-C	530-556	3516	4	77	9	10	Do.
6-A 6-B	582 - 610 610 - 636	$\frac{3684}{3685}$	5	75 67	8 13	12 12	Do. Do.
6-C 6-D	636688	3686	5	66	16	13	Do. Do.
n-D	688-742 742-755	$\frac{3687}{3676}$	4	75 80	9 8	12 8	Do.
6-E	755-768	$\frac{3677}{3568}$	4	80 70	6	10 14	Do. Do.
	768-781 781-794	3678 3679	4	82 84	6 5	8	Do. Do.
	(794-807	3680	E	81	5	9	Do.
7-A) 807-820 820-833	$\frac{3681}{3682}$	5	81 78	6 5	8 12	Do. Do.
	833-846 846-872	3683 3567	6	77 76	7	10 14	Do Do.
7-B	872-898	3688	4	86	5	5	Do.
* L'	898-924 224-956	3689 3569	4	85 77	4	7 10	Do. Do.
7-C	∫ 950-975	3572	10	71	9	10	Do,
) 975-1000 1000-1025	3574	13 26	69 58	6 6	12 10	Do. Do.
8	1015-1020 1025-1050	3575 3576	19 36	68 42	6 12	7 10	Do. Do.
	1050-1087	3577	45	38	11	6	Do.
Average			11	73	7	9	

bled freely from the start and within a few days gave the appearance of having been in service for some time. The sections on which hot asphalt was used did not bleed so markedly and retained a loose, uncompacted appearance for a longer period. One exception was the first experiment, where less cover stone was used and so much bleeding occurred that additional cover stone was required to prevent the mat from picking up under traffic. The cold-application asphalt, which was a cut-back material, readily coated the stone cover which took on a dark appearance within a few hours.

Experiment 8 was a double surface treatment applied directly to the untreated soil surface. The roadbed soil of this section, like that of the others, varied considerably in composition and degree of bond. Prior to applying the treatment the surface was swept to remove excess loose material. Depressions were filled with stone before the bitumen was applied. The prime was applied and allowed to dry for 4 to 6 days during which time traffic was detoured. The hot-application material was then spread, immediately covered with crushed stone, and lightly rolled.

In planning the experiments, the amounts of bituminous materials believed necessary were estimated, as little information upon which to design the mixtures was available at the time. During the initial construction it became apparent that the estimated quantities were too low and they were increased. The quantity used varied with the character of the soil encountered in the different sections. In sections 6-E and 7-A, however, the amounts used were varied intentionally to study the effect of such variation on service behavior.

No particular difficulty was encountered in the mixing operation. All of the bituminous materials were

Out Example Composition by weight 11 Labora Partie Par		Appearance of the mixture	Poorly bonded. D0. D0. D0. D0. D0. D0. D0. D0. Poorly bonded. Poorly bonded. Poorly bonded. Rich. Well bonded. Rich. Well bonded. Well bonded. Well bonded. Vell bonded. Well bonded. Well bonded. Well bonded. Well bonded. Well bonded. Well bonded. Well bonded after remixing. Well bonded. Well bonded. Well bonded. Well bonded. D0. D0. D0. D0. D0. D0. D0. D0. D0. D0	
Stations Longenition by weight Stations Layons Distantion by weight Distantion by weight Passe		Pass- ing No. 200		
Stations Longenition by weight Stations Layons Distantion by weight Distantion by weight Passe		Pass- ing No. 100, re- tained No. 200	Percent 112, 8 114, 0 112, 8 114, 0 114, 0 1	-
Statistical Exercted Exer		Pass- ing No. 80, re- tained No. 100	Percent 12.0 13.0 14.0 15.0 15.0 15.0 15.0 16.0 17.0 17.0 17.0 17.0 17.0	
Statistication services Lobora Distribution in the fait services Distrift services Distribution in the fait services <td></td> <td></td> <td></td> <td></td>				
Statistical section section (cry no. Lonony (cry no. Entity (cry no. Entity (cry no. Passe (cry no.	weight	Pass- ing No. 40, re- tained No. 50	Percent 11,259,20 9,259,20 9,259,20 9,259,20 9,250,20 9,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 11,250,20 12,250,20,200,200,200,200,200,200	
Stations Extracted surface Labors Extract (a) Bittuminous material (b) Bittuminous Bittuminous Bittuminous Passe (b) Passe	sition by	Pass- ing No. 30, re- tained No. 40	97 26 26 26 26 26 26 26 26 26 26 26 26 26	
Stations Expression serviced Labora (source) Bitturbul (source) Passe (source)	Compo		7 2 2 2 2 2 4 4 4 4 4 4 4 4 4 4 4 4 4	
Stations Exercted Sections Labore- Labore- section Bitter Labore- control Distantion Bitter Labore- control Pesse Labore- control Pesse Labore- contro Pesse Labore- control <t< td=""><td></td><td>Pass- ing No. 10, re- tained No. 20</td><td>Percent 15:04 4400 4400 2004 4400 2004 4400 2004 2000 2004 2000 2000 2000 2000 2000 20000 2000 2000 2000 2000 2000 2000 2000 2000 2000 2</td><td></td></t<>		Pass- ing No. 10, re- tained No. 20	Percent 15:04 4400 4400 2004 4400 2004 4400 2004 2000 2004 2000 2000 2000 2000 2000 20000 2000 2000 2000 2000 2000 2000 2000 2000 2000 2	
Stations sented sented Labor- tory no. Bituminous material Pass- Bituming Jations Stations sented Labor- tory no. Bituminous material Bituming Jations Percent Jations Stations sented Labor- tory no. 2008 Asphalt, 150-150 Denetration cut-back t. Percent Jations 2008 Asphalt, 55-100 Denetration, cut-back t. 23 23 23 2011 2008 Asphalt, 100-120 Denetration, cut-back t. 23 24 2012 2013 Silve-uning oil 0.3 21 20 23 2013 2014 Asphalt, 100-120 Denetration, cut-back t. 23 23 2014 200 211 400-25 23 23 23 2015 2104 01-25 210 21 21 21 2015 2104 21 21 21 21 21 2016 211 21 21 21 21 21 2017 21 21 21 21		Pass- ing \mathcal{V}_4 inch, retained No. 10		-
Stations repre- sented Labora fory no. sented Bituminous material Represent sented Labora fory no. sented Bituminous material Represent sented Lory no. sented Stations Represent sented 2005 Asphalt, 150-180 penetration, cut-back 1 Bituminous Represent sented 2005 Statinal, 150-180 penetration, cut-back 1 3. 4.8 Represent sented 2005 Statinal, 150-180 penetration, cut-back 1 3. 4.8 Represent senter 2005 Statinal, 150-180 penetration, cut-back 1 3. 1. 100-100 3. 1. 100-100 Represent senter 2005 Statinal, 150-180 penetration, cut-back 1 3. 1. 100 3. 1. 100 3. 1. 100 Represent senter 2005 Statinal, 150-180 penetration, cut-back 1 3. 1. 100		Pass- ing ½ inch, retained	Percent 11.7 11.7 2.0 2.0 2.0 2.0 2.0 2.0 3.2 0 1.4 4 1.4 4 1.4 1.4 2.0 2.0 2.0 3.2 0 3.2 0 3.3 2.0 1.1 7 1.7 1.7 1.7 1.7 1.7 1.7 1.7 1.7 1	
Stations Labora- trepre- sented Labora- tory no. repre- sented tory no. 29069 115 29089 29111 2005 233 29333 2005 233 29111 2012 29089 29111 2012 2013 29115 2013 2833 29115 2014 20113 29155 2015 20113 29155 2016 233 29155 2016 29155 29155 2016 29155 29155 2017 29155 29155 2018 29155 29155 2018 29155 29155 2018 29155 29155 2018 29155 29155 2018 29155 29155 2017 2916 29155 2017 29170 29170 2018 29170 29170 2017 2920 29177		Bitu- men		-
		Bituminous material	Asphalt, 150-150 penetration, cut-back ' Asphalt, 150-150 penetration, cut-back ' do. Asphalt, 100-120 penetration, cut-back ' do. Slow-curing oil B ² Slow-curing oil B ² Slow-curing oil B ² Slow-curing oil B ² Asphalt, 100-120 penetration, cut-back ' do. Asphalt, 130-25 specific viscosity ³ do. do. do. Asphalt, 85-100 penetration, cut back ' do. do. do. do. do. do. do. do. do. do.	ration given was cut back with naphtha. teed material. at 40° C. 82 and 29763 excluded from averages.
		ory no.	29089 29086 29086 29114 29114 29114 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291150 291750 297730 2977700 2977700 2977700 2977700 2977700 2977700 2977700 297770000000000	ne peneti l or crach fic viscos ples 2976
			$\left(\begin{array}{c} 70\\ 700\\ 205-228\\ 205-228\\ 205-228\\ 205-228\\ 205-228\\ 205-256\\ 502-256\\ 502-556\\ 502-556\\ 502-556\\ 502-556\\ 502-556\\ 502-556\\ 502-568\\ 502-963\\ 807-820\\ 807-820\\ 807-820\\ 807-820\\ 807-820\\ 807-820\\ 807-820\\ 807-807\\ 807-807\\ 807-807\\ 807-807\\ 807-907\\ 807$	Asphalt of the second standard of the specific specific specific specific specific standard of the standard sta
		Sec- tion	7-C 7-B 6-B 6-B 6-C 6-C 6-C 6-C 6-C 6-C 6-C 6-C 7-C 7-C 7-C 7-C 7-C 7-C 7-C 7-C 7-C 7	

January 1937

TABLE 5 .--- Analyses of bituminous mixtures used as bases and surface mats, sampled during or immediately after construction




FIGURE 5.—EXPERIMENT 7-B AT STATION 898 DURING AND AFTER CONSTRUCTION. A, LOOSENED ROADBED PRIOR TO APPLYING BITUMEN; B, MIXED BASE COMPLETED AND READY FOR SURFACE TREATMENT; C, SURFACE TREATMENT COMPLETED, ROAD READY FOR TRAFFIC; D, APPEARANCE OF ROAD 4 YEARS AFTER CONSTRUCTION AND 6 MONTHS AFTER THE ONLY SURFACE TREATMENT IT HAS RECEIVED.



FIGURE 6.—Appearance of Experiment 7–B at Station 898 Seven Years After Construction and 3 Years After the Only Surface Treatment It Has Received.

warmed to obtain uniform distribution. Mixing was carried out promptly to insure thorough and uniform coating of all particles before the volatile constituents of the bitumen should be dissipated. However, no difficulty was experienced in this respect and ample time was available for mixing and spreading the mixture, even when rainy weather temporarily interrupted the mixing operation or made additional manipulation necessary for drying the mixture.

The methods of construction just described are in common usage today and need no further explanation.

Figures 5 and 6, views taken at station 898 on experiment 7–B, illustrate the appearance of the road during its transition from an unimproved to an improved structure.

SURFACE ROUGHNESS CAUSED MAINLY BY UNSTABLE SUBGRADE

The costs of constructing the various experimental sections are given in table 6 together with the annual costs, which include re-treatments and maintenance of the bituminous mats but do not include any other maintenance costs.

The early behavior of the different experimental sections varied considerably as might be expected, but without exception, was a decided improvement over that of the untreated surface at its best. The dust nuisance was eliminated; traffic capacity was increased; riding qualities were greatly improved; there had been provided an all-weather surface which, with reasonable care, was satisfactorily maintained; and if necessary the road could have been economically bettered to meet increased demands, utilizing to a great extent the original investment.

Almost simultaneously with the completion of the sections, a number of failures demonstrated various weaknesses. The most outstanding unsatisfactory feature was surface roughness which, compared with that of the old road, was negligible but compared with that of the new surfaces in general, was very pronounced. While much of the roughness resulted from subgrade movement, other causes brought about the

60
22
0
ti
C
Se
-
al
22
63
2
13
20
d
8
0
us exper-
n
10
2
g
~
50
17
e
0
01
0
tenanc
a
3
4
3
S
u
(~
and
C II
0
e.
+
63
men
~
at
reat
-treat
e-treat
re-treat
ı, re-treat
on, re-treat
tion, re-treat
ction, re-treat
uction, re-treat
truction, re-treat
istruction, re-treat
onstruction, re-treat
construction, re-treat
f construction, re-treat
of construction, re-treat
st of construction, re-treat
ost of construction, re-treat
Co
Co
Co
Co
Co
Co
ABLE 6Co
ABLE 6Co
Co

	A ver-	age annual cost	$\begin{array}{c} 10.36\\ 10.36\\ 10.36\\ 8.66\\ 8.66\\ 8.66\\ 9.066$
		Total	C ends 26, 26, 26, 26, 26, 26, 26, 26, 26, 26,
ces only	1933-34	Main- te- nance	Central Centra
is surfac	1935	Re- treat- ment	Central 11, 12 ² 7, 11 14, 73 14, 74 14,
tuminot	2-33	Main- te- nance	Central 3, 544 2, 580 1, 999 1, 949 1, 044 1, 949 1, 1, 044 1, 1, 949 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1
Annual cost per square yard of re-treatments and maintenance of the bituminous surfaces only	1932-	Re- treat- ment	Cents 14, 11 14, 11 14, 11 14, 11 16, 08 5, 08 11, 68 11, 68 11, 68 11, 68 11, 68 11, 68 10, 59 10, 59
enance c	1931-32	Main- te- nance	Cents 1.300 1.690 1.690 1.611 1.61 1.460 1.61 1.460 1.45 1.45 1.45 1.45 1.45 1.45 1.45 1.45
l mainte	193	Re- treat- ment	Cents 9.95 9.95 9.95 9.95 2.057
ents and	1930-31	Main- te- nance	Cents 2 099 2 099 2 099 2 099 2 099 2 099 2 099 2 1 000 1 000 1 1 000 1 1 100 1 1000 1 1000 10
-treatm	193	Re- treat- ment	Cents 9, 855 9, 855 9, 856 9, 28 9, 28 9, 28 10, 10 10, 10 10, 10 10, 10 10, 10 10, 10 10, 10 10, 10 10, 23 110, 23 10, 23 10, 23 10, 23 10, 28 10, 28 20, 20, 28 20, 20, 20, 20, 20, 20, 20, 20, 20, 20,
rd of re	1929-30	Main- te- nance	Central Control Contro
luare ya	1920	Re- treat- ment	Cents 11.365 2 7.09 2 7.09 11.366 11.99 11.99 11.99 10.33 10.33 10.33 10.33 10.33 10.33 10.33 10.33 10.33 10.33 10.33 2 81 5 11 11.90 11.99 11.9
st per so	1928-29	Main- te- nance	C. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5.
nual cos	1929	Re- treat- ment	Cemts 6. 24 6. 82 6. 82 6. 82 6. 82 26. 57 1. 22 30. 45 7 1. 22 30. 45 6. 57
An	1927-28	Main- te- nance	Carter Control (Carter Control
		Re- treat- ment	Cents 4, 25 4, 25 4, 25 4, 25 4, 25 4, 25 4, 25 13, 69 31, 85 23, 40 16, 00 16, 00 33, 85 33, 85 33, 85 33, 85 33, 85 33, 85 33, 85 33, 85 33, 85 33, 85 34, 85 35, 85 34, 85 35, 85 36, 85 36, 85 36, 85 36, 85 36, 85 36, 85 36, 85 37, 85 36, 85 36, 85 37, 85 36, 85 37, 85 36, 85 37, 85 37, 85 37, 85 36, 85 37, 85 37, 85 36, 85 37, 40 37, 85 37,
	Cost	per square yard	Cents 33, 756 33, 756 33, 756 33, 551 34, 555 37, 551 37, 5515
	atment	Cover	1¼-¼-inch stone. 1¼-¼-inch stone. do. Fea gravel. Band. Fea gravel. Fea gravel. Fea gravel. Sand. r Treated soil. r Treated soil. r Treated soil. r do. r do.
Construction	Surface treatm	Bituminous material	Hot asphalt Cut-back asphalt. Cut-back asphalt. do do do do do burback burbach burback burback burback burback burback burback burback burbach
	Mixed base	Bituminous material	Cut-back asphalt do do do do do do do do do do
		Thick- ness	14
Section		Stations	$\begin{array}{c} 0 & 0 & -100 \\ 100 & -150 \\ 150 & -150 \\ 150 & -150 \\ 150 & -205 \\ 220 & -221 \\ 220 & -221 \\ 220 & -221 \\ 220 & -221 \\ 220 & -221 \\ 231 & -233 \\ 233 & -333 \\ 333 & -333 \\ 333 & -333 \\ 333 & -333 \\ 333 & -333 \\ 333 & -333 \\ 333 & -256 \\ 556 & -265 \\ 556 & -556 \\ 556 & -55$
Se		No.	777999999999999 48480088087 4804 8 00 4 8008480

 1 Includes re-treating last 500 feet of the section shortly after construction. 2 Treatment applied to part of section only but cost is prorated over entire section.





FIGURE 7.—A, FAILURE OF SURFACE TREATMENT ON EXPERI-MENT 5-D, WHICH WAS CONSTRUCTED BY ENRICHING THE TOP PORTION OF THE MIXED MAT WITH SLOW-CURING OIL. B, APPEARANCE OF EXPERIMENT 5-A SHORTLY AFTER CONSTRUC-TION. ITS SURFACE, WHICH WAS ENRICHED WITH SLOW-CURING OIL, SCALED AND POT-HOLED. THE BASE, WHICH WAS POORLY DRAINED, BECAME VERY UNSTABLE.

same result. One of these was surface enrichment of the mixed mats designed to carry traffic without additional surface treatment or the use of coarse cover material. The upper portion of the mat peeled off to about the depth of enrichment, resulting in a rough, pot-holed surface. This condition, illustrated in figure 7, was eventually eliminated by a re-treatment in which a stone cover was used.

Another cause of roughness was the instability of the mixed base itself due to an improper combination of bituminous material and sand-clay. In some cases the amount of bituminous material used was apparently incorrect for an entire section; in others it was apparently correct for the major portion of the section but unsatisfactory for other portions because of variations in the sand-clay within the section. Tables 4, 5, and 7 indicate the wide variations in grading, not only among the sections but within a given section, which made it practically impossible to design a uniformly satisfactory mixture and would have made it impossible to have applied an empirical proportioning formula had such a formula been available at the time.

The bitumen content of the mixed bases, as determined by extraction tests, varied considerably. While the resulting mixtures are probably lean and might be unable to withstand traffic without a protective covering, increased stability has probably been obtained with the result that there has been less movement of the mat than would have occurred had the mixture been richer.

The most important factor contributing to roughness during most of the life of the road has been the subgrade, which is extremely variable in composition and, in some locations, is very poorly drained. Settlement occurred




FIGURE 8.—INCIPIENT POT-HOLING, WHICH WAS CHARACTERIS-TIC OF PORTIONS OF EXPERIMENT 4.

in some areas that had appeared stable prior to constructing the bituminous mats. Investigation disclosed that the subgrade in such areas was extremely wet and plastic while material less than a foot outside of the bituminous mat was firm and relatively dry. The mat apparently prevented surface evaporation and permitted the subgrade to acquire and retain sufficient moisture to destroy its stability. Obviously, the composition could not be changed after construction but considerable effort has been expended to provide artificial drainage. The groundwater level in many cases is so high that the maximum benefit derived by the construction of side ditches is to provide a relatively shallow depth of drained base which, because of its composition, is variable in load supporting capacity.

Two other factors contributing to surface roughness were ordinary pot-holing and edge failure. The former, illustrated in figure 8, appeared in the sections designed for machine maintenance and was caused primarily by a lack of bituminous material. The latter type of failure appeared in varying degrees in most of the sections but was more pronounced on those in which fine grained or no cover materials were used. On such sections, steel-tired vehicles damaged the edges as illustrated in figure 9.

CONSTRUCTION AND RE-TREATMENT OF EACH EXPERIMENTAL SECTION DESCRIBED IN DETAIL

Another unsatisfactory and unsightly condition developed—bleeding or flushing of bitumen to the surface. This condition, which highway engineers are still striving to eliminate, appeared wherever the base became softened by an excess of bitumen, moisture, or clay, or a combination of these in an amount sufficient to permit the cover material to become embedded in the mixed bituminous base or in the sand-clay base. Where the bases were not thus softened and the cover material remained on the surface, bleeding did not occur.

Samples were taken 7 years after construction from areas representing various typical conditions. Analyses of subgrades and bituminous mats were made and are given in table 7 together with a description of the area represented at the time samples were taken.

Experiment 1, extending from station 0 to station 150, had a 2-inch mixed base of sand-clay and cut-back asphalt. It was primed with cut-back, sealed with hot asphalt, and covered with crushed stone. This experimental section, which began at the northwest city limits of Conway and extended 3 miles northwest, was divided into sections A and B, which differed only in the cut-back asphalt used in the mixed base and prime application. On section A this bituminous material was a cut-back of 150 to 180 penetration asphalt and on section B a cut-back of 85 to 100 penetration asphalt was used.

As shown in table 4, samples of the sand-clay taken from various places on the experimental section showed considerable variation in composition. Many areas were low and poorly drained, as artificial drainage was not provided until later.

This was the first experimental section built and almost immediately after construction it was apparent that the bitumen content of the base was too low. Although surface-treated with hot asphalt and stone, the edges soon crumbled and broke badly, necessitating an additional treatment for a width of a few feet at the edges. Early movement of the mat resulted in a rough riding surface which has been, in general, characteristic of a considerable portion of this experimental section. To eliminate some of this roughness a 500-foot length at the west end of section B was given a re-treatment in July 1927. This treatment added to the surface smoothness considerably but shoving later developed at the extreme west end of the section due to unsatisfactory drainage conditions.

Since construction section A has received four complete and two partial re-treatments while section B was given two complete and two partial re-treatments exclusive of the 500-foot length re-treated as a part of its original construction. These re-treatments were applied primarily to seal cracks which had developed and to eliminate surface roughness.

During this same period considerable effort was made to provide drainage by the construction and maintenance of deep side ditches and by the installation of French drains. As a routine maintenance measure, badly shoved areas were repaired by removing the unstable material below the base, placing stone-filled trench drains, refilling with satisfactory base material such as cinders or coarse crushed stone, and then replacing the bituminous mixtures or using bituminous-coated stone. On many areas the result of such repair was a smooth surface which continued in good condition, but on other portions of the section identical repairs had to be made at intervals, especially on the low side of curved areas.

Prior to applying the re-treatment in May 1933, considerable effort had been made to remove all rough areas caused by subgrade movement. This treatment, consisting of 0.65 gallon of 85 to 100 cut-back and 60 pounds of ¾- to ¾-inch stone per square yard, was the heaviest treatment applied and contained sufficient materials to produce a mat of appreciable thickness. The section at first appeared to have been greatly improved by this treatment, but by the following spring those areas on which the subgrade had previously been troublesome again developed excessive roughness, shoved considerably, and required much additional maintenance. Figure 10 illustrates an excellent as well as an unsatisfactory area typical of the section in February 1934.

The slight variation in type of bituminous materials used in the mixed bases of sections A and B was at no time reflected in their behavior. There was no greater variation in behavior between the sections than within



FIGURE 9.—STEEL-TIRED VEHICLES WERE ESPECIALLY DE-STRUCTIVE TO THE EDGES OF THE SECTIONS OF EXPERIMENTS 2 AND 5, WHICH HAD NOT RECEIVED ADEQUATE SURFACE TREATMENT. ARROWS INDICATE ORIGINAL EDGE OF THE MAT.

portions of each section. Construction and average annual maintenance costs of this experiment are shown in table 8.

PERFORMANCE OF EXPERIMENT 2 AFFECTED BY SUBGRADE AND DRAINAGE CONDITIONS

Experiment 2, extending from station 150 to station 350, had a 2-inch mixed base of sand-clay and cut-back asphalt which was sealed with cut-back asphalt and covered with crushed stone, gravel, or sand.

Experiment 2 was divided into three groups of three sections each. They were constructed indentically except that the cut-back asphalt differed in each group and also that in each group one section was covered with 1¹/₄- to ¹/₄-inch crushed stone; one was covered with pea gravel; and one was covered with sand. The cut-backs used were made of 85 to 100, 100 to 120, and 150 to 180 penetration asphalts.

As in the case of experiment 1, subgrade and drainage conditions in this experimental section were exceedingly variable. Each section had sandy areas, areas high in clay content, poorly drained areas, and areas fairly well drained. Sections A, E, F, and G, however, had somewhat better natural drainage than the other five sections of this experiment.

Rainy weather encountered during base construction necessitated a considerable amount of manipulation for drying as well as for mixing the base materials. The seal treatment was applied directly to the mixed bases after they had been subjected to traffic for periods ranging from 4 to 30 days. On each section the bituminous

			se from rainage	Right side			8					8 9 8 9 9		5 5 7 7 8	1	5) 1 7 1 4			\$ # } }	
ction)	œ	1054	Very good; stable and free from cracking or raveling; drainage good	Left side										1 1 1 1 1 1 1 1 1 1 1 1 1 1		4 2 4 2 4 2 4 2 4 2 4 2 4 2 4 2 4 2 4 2				
onstru	7-C	981	Very good; no crack-	ing or ravel- ing; drain- age good			5 T T T T T T T T T T T T T T T T T T T					1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			0 1 5 1 1 7 4	t 5 9 9 9 1				
rs after c	6-B	630	Rough	but sta- ble; drainage is good	39360	Original.	Tar	Mixed	base. 4-414	5,710	4,525	2,330	8.7		1 4	3.6	4.6.	26.2	23.2	9.8.
4 (7 yea)	6-A	585	Rough but sta- ble; lies	swampy section; natural drainage fair	39361	Original.	Tar	Mixed	base.	5,575		3,120	7.0.		t-	00	1.7	23.9	23.1	28.0
l in 193.	5-C	543	Very good:	50	39362	Original.	Cutback	Mixed	base. 2¾-3¼	5,400		1,900	2-2-6	+0	0·	1.2	1.7	11.7	22.9	31.0.
ntal road	4-C	457	Very good; some	raur- cracking but no raveling; drainage fair	39354	Remixed	S 10 W -	oil.	4-4}2	1,160	940	450	10.2	l.	0	1.5	2.1.	20.2	23.6	30.4
rperime	4	453		pitting due to clay balls; drainage fair	39355	Remixed	S 10 W -	oil. Both	3	940.		630	7.0		±.	1.8	2.7	24.2	25.7	27.3
and subgrades from areas typical of the experimental road in 1934 (7 years after construction) BITUMINOUS MIXTURES	4-B	440	Rough, unstable in warm	weather; old mat fairly firm; drainage poor	39356	Remixed	Slow-curing	Both	4	\$ 270 6 40	7 2,000	6 0-7 1,570	ர்	z		. T	с, С	15.5 23.2	33.5 20.6	32.0 26.2 7.0 14.1
t from areas typical of th BITUMINOUS MIXTURES		398	-		39357	Remixed	Slow -	oil. Both	238-234	2,910			9.2.	ų	1.2	2.1	2.9	25.5	21.6	24.0
ss from a BITUMI	0	363	Mat al- most gone;	oad area on curve; drainage poor; slight cut ⁴	39358	Remixed	S] 0 W -	oil. Both	1 (ap- prox.).	1,730		1,790	6.8		1.5	5.6	5.9	15.0.	16.8	34.7
subgrade		353	Good, smooth, un-	di di	39359	Remixed	SIOW -	oil. Both	234-3	1,620		770	7.1	0	3.1	5.4	5.4	15.5	16.5	35.9
ninous mais and	1-B	145	Very good and has	thee from cracking and raveling; drainage good ²																
TABLE 7.—Analyses of biluminous mats	1-A	63	Mat almost gone; sur- rounding area has	been heavily patched; slight fill through swampy section ¹																
TABLE 7.	- Experiment no.	Sampled at station no.		Condition of wearing surface at location sampled	Laboratory no	Original or remixed base or surface	Bituminous material used	Material represented—base or surface.	Depth of mixed base or surface, inches. Hubbard-Field stability at 77° F.,	pounds: Top inch ⁴ Second inch ⁵	Third inch ⁶ . Fourth inch ⁶ .	Composite of above, remolded ⁸ Extraction and grading:	Passing 14 inch, retained No. 10	Passing No. 10, retained No. 20	Passing No. 20, retained No. 30 Decent	No.	Passing No. 40, retained No. 50	Fassing No. 50, Fetained No. 50	Doccine No. 30, retained No. 100 Doccine No. 100 minimum Decemt.	Passing No. 200

8146		13.8 ^{45.0}	6	81 15 0	15	A-3	
8145	10 to 14	23 23 20 20	10	80 22 8 17	1.8	A-2 plastic	ant.
8144	6 to 10	2200380 2500380	10	35 35 25 25	1.5 28 27	A-2 plastic	len conte
8143	Top 6	43 15 18 24	14	74 33 14 23	1.6 26 25	A-2 plastic	its bitum
8147		0 69 13 15	0	17 17 0	19	A-3	sreent of
8169		EEEEE	(11)	16 0	5 20	A-3	to 18.44 pe
6067		72 17 17 17	11	26 9 21	$1.7 \\ 14 \\ 20 \\ 20 \\ 20 \\ 20 \\ 20 \\ 20 \\ 20 \\ 2$	A-2 plastic	uivalent t
6080		0 36 37 26	11	28 13 18	21.8 21 19	A-4	weight, eq
8148		0 77 12 12	10	99 18 0	6 21	A-3	ercent by
8149		0 655 25 7 25 7	18	99 27 13	1.8 14 19	A-2 plastic	Data for old surface prior to 1933. Under direct compression of 3,000 pounds per square inch. Mix heated in oven for 5 hours at 163° C. (325° F.) lost 1.42 percent by weight, equivalent to 18.44 percent of its bitumen content. Insufficient material.
10 6082	Next 5	0 6 9 14	10	15 0	17	A-3	per squi (325° F.
10 6081 10 6082	Top 5	$ \begin{array}{c} 0 \\ 48 \\ 10 \\ 38 \\ 38 \\ 38 \\ 38 \\ 38 \\ 38 \\ 38 \\ 38$	32	42 24 19	1.7 24 26	A-6	pounds 163° C.
8151		0 60 10 24	18	98 13 16	1.8 13 19	A-2 plastic	⁷ Data for old surface prior to 1933. ⁸ Under direct compression of 3,000 pounds per square inch. ⁹ Mix heated in oven for 5 hours at 163° C. (325° F.) lost 1.4. ¹ Insufficient material.
8152		115 16 11 16	14	93 20 18	14 14 19	A-2 plastic	surface princession of the second sec
8153		31 52 14 14	12	87 5	10 18	A-2 plastic	⁷ Data for old surface prior to 1933 ⁸ Under direct compression of 3,000 ⁹ Mix heated in oven for 5 hours at ¹⁰ Samples taken at station 436. ¹¹ Insufficient material.
8156	10 to -	$\begin{array}{c} 0\\ 15\\ 27\\ 15\\ 43\\ 43\end{array}$	36	96 29 14 -	26 26 27	9-V	7 Da 8 Un 8 Mii 10 Sau
8155	5 to 10	1800 1800 1800 1800	12	95 14 14 15 14	1.8 14 13	A-2 feebly plastic	
8154	Top 5	0 24 19 13	10	93 14 0	11 14	A-3	
8159	e inches. Top 6 6 to 12 12 to 18 Top 5 5 to 10	0 25 17 25	21	88 32 15 15	21	A-2 plastic	
8158	6 to 12	$\begin{array}{c} 47\\ 21\\ 21\\ 11\\ 21\\ 21\end{array}$	17	62 33 19 14	22 19	A-2 plastic	nd 15. ed.
8157	Top 6	0 26 40 40	32	97 41 25 13	26 24	A-6	ure 10-B are 10-A nres 14 a are 13.
Laboratory no.	Portion represented by sample inches Mechanical analysis: Particles larger than 2.0 mm	Coarse sand, 2.0–0.25 mm percent. Fina sand, 0.22–0.55 mm – do Silt, 0.05–005 mm – do Clay, smaller than 0.000 mm do Coloids, smaller than 0.000 mm do	Dercent Characteristics of material passing No. 40 sieve:	Percent passing Liquid limit Pidsuloty index Sminibage limit Sminibage resto	Centrifuge moisture equivalent Field moisture equivalent	Soil group	 ¹ Condition shown in figure 10-B. ² Condition shown by figure 10-A. ³ Condition shown by figures 14 and 15. ⁴ Condition shown by figure 13. ⁵ Field specimens tested as received.

Countinous nuoven toy ngure 10-a.
 Condition showen by figures 14 and 15.
 Field specimens fosted as recoived.
 Field specimens fosted as recoived.
 Data for new sand-oil mat built on old surface in 1933.

SUBGRADES



FIGURE 10.—TYPICAL VIEWS OF SATISFACTORY AND UNSATIS-FACTORY PORTIONS OF EXPERIMENT 1, SEVEN YEARS AFTER CONSTRUCTION. ANALYSES OF SUBGRADES FROM THESE AREAS ARE GIVEN IN TABLE 7. A, AT STATION 145 OF EX-PERIMENT 1-B. B, AT STATION 63 OF EXPERIMENT 1-A; FAILURE CAUSED BY PLASTIC SUBGRADE.

 TABLE 8.—Construction and average annual maintenance costs per square yard for experiment 1

		Average				
Section	Bitu- minous material	Stone cover	Labor and equip- ment	Total	annual mainte- nance cost	
A	<i>Cents</i> 17. 16 16. 96	<i>Cents</i> 7.64 7.65	Cents 8, 96 7, 61	Cents 33, 76 32, 22	<i>Cents</i> 10. 36 8. 69	

material used in the seal was the same as that used in the mixed base. Crushed granite, $1\frac{1}{4}$ - to $\frac{1}{4}$ -inch, was the cover material for sections A, F, and G; pea gravel was used on sections B, E, and H; and a local sand was used on sections C, D, and I.

One month after construction, section H had broken up to such an extent that it was necessary to remix it with additional bitumen and reseal it. Other sections of experiment 2 exhibited various defects which were not of sufficient proportion to warrant reconstruction.

In December 1927 experiment 2 was re-treated with the same types of bituminous and cover materials that were used in construction except that sand instead of stone cover was used on section Λ . In addition, sections G, H, and I were remixed with additional bituminous material prior to applying the re-treatment. Since 1927 the stone-covered sections have received only one re-treatment: Section Λ in 1933; and sections F and G in 1931. Of the gravel-covered sections (B, E, and H) section E continued the most satisfactory, the re-treatments having been limited to a treatment of the last 950 feet of the section in 1930 and to the entire section in 1932. Section H was re-treated in 1928, 1930, and 1933 and in each treatment stone cover was used instead of pea gravel. Section B, still maintained as a pea-gravel covered section, was re-treated in its entirety in 1928, 1931, and 1934 and approximately half its area was remixed and re-treated in 1929.

The sand-covered sections C, D, and I soon became rough, pot-holed, and unstable, and their edges raveled under steel-tired vehicles. Sand was used as the cover material in the re-treatment of the entire experiment in 1927 and to cover section C and part of section D, after they were remixed in 1928. The recurrence of surface failures, however, led to the substitution of stone as the cover material in the subsequent re-treatments applied to sections C and D in 1929, 1932, and 1934 and to section I in 1928, 1930, and 1933. Figures 9–B and 11–A illustrate the unsatisfactory

Figures 9–B and 11–A illustrate the unsatisfactory surface conditions that existed on these sections during the period when the wearing surfaces were composed of sand and cold-application bitumen. They also illustrate the unsatisfactory drainage conditions existing at the time the sections were built and during their early life.

With the substitution of stone as the cover material and with the construction of side ditches and lateral drains, the unsatisfactory behavior was largely eliminated and the service behavior of the sections became comparable to that of the other sections of this experiment.

Construction and maintenance costs of this experiment per square yard are shown in table 9.

		(Aver-				
Section	Cover	Bitu- mi- nous ma- terial	Cover mate- rial	Labor, supplies and equip- ment	Total	age an- nual main- tenance costs	
A B D E F G I	Stone Gravel Sand Gravel Stone 	Cents 23. 18 21. 83 24. 82 25. 22 27. 26 23. 57 26. 19 30. 17 23. 28	Cents 6, 72 2, 59 , 20 , 22 2, 59 6, 72 7, 45 14, 55 , 18	$\begin{array}{c} Cents \\ 5.21 \\ 5.75 \\ 9.50 \\ 11.62 \\ 5.66 \\ 6.77 \\ 11.82 \\ 9.89 \\ 12.25 \end{array}$	$\begin{array}{c} Cents\\ 35.11\\ 30.17\\ 34.52\\ 37.06\\ 35.51\\ 37.06\\ 45.46\\ 44.61\\ 35.71 \end{array}$	$\begin{array}{c} Cents \\ 4,09 \\ 10,65 \\ 15,00 \\ 10,64 \\ 4,11 \\ 4,23 \\ 7,28 \\ 10,41 \\ 9,09 \end{array}$	

¹ Includes 2 applications of gravel cover, the first of which was incorporated into the mixture when the section was reconstructed 1 month after original construction.

SURFACE CRACKS DID NOT IMPAIR EXPERIMENT 3

Experiment 3, extending from station 350 to station 400, had a 2-inch mixed base of sand-clay and slowcuring oil A. Its surface was enriched with oil A and covered with bitumen-coated sand-clay.

This experiment, approximately 1 mile in length, was one of the sections in which a slow-curing oil was used and was designed for machine maintenance.

On this experiment the subgrade and drainage were somewhat better than on the two preceding experimental sections, except for a short portion, in the vicinity of station 365, which lay in a swampy area. During construction a severe storm interrupted the mixing operation and the heavy rainfall washed a considerable but undetermined amount of oil into the side ditches. When mixing had been completed the surface did not bond and the quantity of oil, with which it was planned to enrich the top portion of the mat by penetration, was increased to 0.65 gallon per square yard. This application was covered with oil-treated sandclay. Except for occasional light blading to retain surface smoothness, this completed the construction of the section.

In general, the behavior of experiment 3 during the period covered by this report has been good. It has been scarified and remixed three times since construction. In two of these remixing operations, those of 1928 and 1933, oil was added, but the remixing in 1929 was done primarily to eliminate instability which had developed in the bituminous mat due to excess moisture.

The section was similar to a sheet asphalt pavement in texture but its color was brown and it had acquired a somewhat glazed surface under traffic. The major portion of this experiment remained fairly smooth but three relatively small areas continued rough and spongy as if excessively rich in bitumen. However, an unstable base, poor drainage, and the presence of water was the cause of instability rather than excessive bitumen. Practically all of the experimental section was covered with fine hair cracks throughout most of its life. Except in the areas more greatly affected by moisture, this cracking apparently had not seriously affected the behavior of the section. Figure 11–B illustrates the most advanced stage of cracking which, although unsightly, did not progress to the stage of disintegration.

Although designed for machine maintenance, the surface eventually crusted so that dragging for surface smoothness was not practical and depressions were usually filled with premixed material. High spots were easily cut with a blade but the material so removed was whipped from the surface by traffic rather than compacted into the low spots.

The cost per square yard of constructing this experiment was as follows:

Cen	100
Bituminous material	78
Labor, supplies, and equipment	26
Total 23. (04

The average annual maintenance cost was 5.19 cents per square yard.

In the period subsequent to that covered by this report, an unsatisfactory condition developed that seriously affected the service record of experiment 3. The surface glaze, previously referred to, became very pronounced in the intervals during which the surface was not disturbed by machining or remixing. The glazed surface became very slippery in wet weather and so dangerous to traffic that the highway department, in 1935, applied a surface treatment of cut-back asphalt and stone.

ORIGINAL CONSTRUCTION ON EXPERIMENT 4 BECAME HARD AND BRITTLE, REQUIRING RE-TREATMENT

Experiment 4, extending from station 400 to station 477, had a 3-inch mixed mat of sand-clay and slow-curing oils, B, C, and D.

Experiment 4 also was designed for machine maintenance and its construction was similar to that of experiment 3 except that all of the bitumen applied



FIGURE 11.—INADEQUATE DRAINAGE CONTRIBUTED TO BASE FAILURE ON THESE EXPERIMENTAL SECTIONS. A, BOTH BASE AND SURFACE FAILED ON EXPERIMENT 2, SECTIONS C AND D. SAND WAS USED WITH A COLD-APPLICATION MA-TERIAL FOR SURFACE TREATMENT, RESULTING IN A RICH, PLASTIC MIXTURE. B, BADLY CRACKED AREA ON EXPERI-MENT 3, CAUSED BY A PLASTIC SUBGRADE.

was mixed with sand-clay to form the mat. The experiment was divided into three sections which differed only in the kind of oil used.

Subgrade and drainage conditions were quite variable in each of the sections but were somewhat better in section C than in sections A and B. Portions of sections A and B lay in low, swampy areas where the ground water level was very close to the elevation of the road surface. The character of the sand-clay was exceedingly variable. At some time prior to construction of the experimental sections, clay had been used where needed to fill holes. Apparently, no attempt had been made to mix the clay with the material already in the road, consequently the base and the sand-clay in the mixed mat ranged from very sandy mixtures to mixtures high in clay content. This was especially true of the west portion of section B and the east portion of section C.

When the sections had been laid down and compacted under traffic, they were similar in appearance to experiment 3 except that the glaze was more pronounced and, in general, they appeared harder and less malleable. Material loosened by dragging or light blading did not readily rebond but was dissipated by traffic.

The first remixing was done to section A in 1928. The east 600 feet were not remixed, as that portion of the section was in excellent condition. The next 1,000foot portion, which had become rutted through the swampy area and also was badly pot-holed elsewhere, was scarified and remixed with approximately 1 gallon of oil A per square yard. The remaining 1,000-foot portion on the west end of the section appeared hard, firm, and only slightly pot-holed but had a decided tendency to dust under traffic. It was decided to experiment by lightly scarifying the top portion of this area, and adding about one-half gallon of oil A per square yard, which, with a small amount of sand-clay brought in from the sides, formed a thin new wearing surface for the old mat. The plan was successful as the new material bonded readily to the old mat and dusting under traffic stopped.

Sections B and C were first remixed in 1930 with approximately 0.8 gallon of oils C and D per square yard, respectively, the same oils as were used in the original construction.

All three sections were again treated in 1933. It was attempted in this treatment to raise the grade through the swamp on section A and to elevate the outside edges of two sharp curves on sections B and C. On section A the additional sand and oil added to raise the grade were mixed with the old mat which had been scarified. The curves on sections B and C were elevated by building a new mat on top of the old one. The remaining portions of this experiment were remixed with additional oil.

The remixing operations revealed considerable differences in the character of the mixture on experiment 3 as compared with experiment 4. The mat on experiment 4 broke up readily and required only a small amount of harrowing and blading to reduce it to a uniformly fine mass which did not appear at all "alive". The mat of experiment 3, on the other hand, was malleable and in spite of considerable harrowing and blading did not break down into a uniformly divided condition. Under the traffic that passed while the work was being done the pulverized material on experiment 4 compacted but did not rebond, while that on experiment 3 not only compacted but rebonded to such an extent that additional manipulation was necessary before the oil was added. Upon adding the oil and remixing, however, the scarified portions of experiment 4, in general, compacted and bonded very much better than those areas on which a new mix was built upon the old mat.

On those portions of the experimental section previously referred to as containing considerable clay, it was noted that within a few days after the mix had been relaid small areas in the center of the road were cracked and raveling. These spots and the surrounding areas were immediately remixed and relaid, and within 3 hours under traffic the same undesirable features reappeared in the same locations. Upon removing the mix a 2-inch layer of wet, sticky clay was found between the bituminous mat and the sandy base. This layer of clay was removed from portions of these areas and the bituminous mix replaced. No cracking or raveling reappeared and the small areas thus repaired remained in excellent condition. The particular locations of these areas of failure, directly under the area of concentrated traffic, suggest the possibility of movement or flow of clay under the vibrating action of traffic. It appeared most practical not to attempt to remove all of the heavy clay deposits from the base because of the irregularity of their location but to make repairs as a maintenance measure when and where necessary.

The construction and average annual maintenance costs for each of the sections of this experiment are given in table 10.

 TABLE 10.—Construction and average annual maintenance costs
 per square yard for experiment 4

	Co	Construction costs					
Section	Bituminous material	Labor, supplies, and equipment	Total	annual mainte- nance costs			
А В. С	Cents 23. 78 19. 75 23. 86	Cents 4. 64 4. 64 4. 64	Cents 28. 42 24. 39 28. 50	Cents 5.62 6.84 7.08			

A slippery surface developed on experiment 4 similar to that which developed on experiment 3, and at the same time. The same remedial measures were applied to both experimental sections at the same time.

STEEL-TIRED VEHICLES WERE DESTRUCTIVE TO EDGES OF EXPERIMENT 5

Experiment 5, extending from station 477 to station 582, had 2- and 3-inch mixed bases of sand-clay and cut-back asphalt. The surface was enriched with slow-curing oil E and cutbacks, and was covered with bituminous-treated soil.

This experiment comprised four sections—A, B, C, and D. The mixed bases of sections A and B were 2 inches thick and those of sections C and D were 3 inches thick.

The bases were mixed with 85 to 100 penetration cut-back asphalt, spread and compacted by traffic. A small amount of the mixed base was windrowed to the sides to be respread after the surface enrichment application had been made. The bituminous material used for this purpose on sections A and D was the slow-curing oil E, similar to that used in experiment 4, and on sections B and C it was a 150 to 180 penetration cut-back asphalt. Approximately 0.4 gallon per square yard was used on each of the sections.

The subgrade and drainage of this experiment, while varying somewhat, were better than on the preceding experimental sections. With the exception of part of section A, good natural drainage and fairly stable subgrade were characteristic of this experimental section. The exception was approximately the center third of section A, which lay in low swampy area very difficult to drain. Side ditches were of no great benefit as they quickly filled with sand and silt and permitted surface water to reach almost to the bituminous mat. This condition is illustrated in figure 7–B. About 1930, however, the entire swampy area was drained and the ground-water level lowered so that recently there have been no failures directly attributable to unstable subgrade.

The sections immediately after construction resembled a sheet asphalt pavement, with sections B and C appearing more substantial than sections A and D. The surfaces of sections A and D scaled and pot holed badly, section D more so than A. There appeared to be little bond between the enriched surface portion and the relatively lean base, as the surface shoved, peeled, and pot-holed to the approximate depth of enrichment. This type of failure is illustrated in figure 7–A.

Sections B and C were similar in appearance and behavior. While pot-holing and surface roughness were far less pronounced than on sections A and D, the edges of the mats did suffer severely under steeltired vehicles that cut through the mix as illustrated in figure 9-A. Considerable early maintenance, consisting of placing new mixture along the edges, was required to maintain the original road width.

Section A developed roughness, pot-holed, and became unstable due to what was thought to be excessive richness. By December 1928 it was in such unsatisfactory condition that reconstruction was deemed When the section had been scarified and advisable. pulverized it was evident that the apparent richness was caused primarily by moisture and not by excess bitumen. One and one-quarter gallons per square yard of 85 to 100 penetration cut-back asphalt were added and the section was remixed. After compaction under traffic the surface was sealed with 0.38 gallon per square yard of the same type of cut back, covered with 50 pounds per square yard of 1¹/₄- to ¹/₄-inch stone, and then rolled. Its condition prior to scarifying and re-treating is illustrated in figure 7–B.

By the fall of 1929 the section had again become unstable and extremely rough, and again it was scarified and remixed, but without adding bitumen. It was then resealed with 0.38 gallon of 85 to 100 penetration cutback asphalt and 50 pounds of 1¼- to ¼-inch stone per square yard and rolled. About this time a drainage ditch, constructed through the swamp, removed the water from the surrounding area and, with the side ditches then capable of handling surface water, the subgrade became stable and has so remained. Except for a rather lean surface appearance, the section in July 1934 was in better condition than at any previous time.

Section D, which was identical with section A except that its bituminous base was 3 inches thick, was retreated in the fall of 1929 to eliminate excessive roughness and to preserve the mixed base. The treatment consisted of applying 0.39 gallon of 85 to 100 cut-back asphalt and a cover of 40 pounds of ³/₄- to ¹/₄-inch stone per square yard. This treatment greatly benefited the section by eliminating most of the roughness and scaling of the mat.

Sections B and C continued in fair condition except for the roughness and edge failure already noted. Maintenance of these two sections consisted mainly of building up the edges and removing depressions, using for this purpose a mixture of sand-clay and cut-back asphalt. In May 1933 they were in fair condition for the surface treatment that was applied to them and to section D. The treatment consisted of 0.46 gallon of 85 to 100 penetration cut-back asphalt and 40 pounds of ³/₄- to ¹/₄-inch stone per square yard.

The construction and average annual maintenance costs per square yard for this experiment are given in table 11.

 TABLE 11.—Construction and average annual maintenance costs

 per square yard for experiment 5

	Co	Construction costs				
Section	Bitumi- nous material	Labor, supplies, and equipment	Total	annual mainte- nance costs		
A B C D	Cents 26, 60 25, 22 32, 20 32, 51	Cents 7, 10 5, 73 9, 13 8, 54	Cents 33. 70 30. 95 41. 33 41. 05	Cents 8. 67 3. 58 2. 57 4. 51		

2 GALLONS OF TAR PER SQUARE YARD FOUND TO GIVE STABLE MIXTURE

Experiment 6, extending from station 582 to station 794, had 2- and 3-inch mixed bases of sand-clay and tar. The bases were primed with tar, surface-treated with hot and cold-application tars, and covered with tar-treated sand-clay or with crushed stone.

This experiment included five sections in which the bases were sand-clay mixed with tar of 18 to 25 specific viscosity at 40° C. The bases were 2 inches in thickness except that of section B which was 3 inches.

Sections A and B were surface-treated by the enrichment method similar to that employed on experiment 5, using for this purpose the 18 to 25 viscosity tar and treated sand-clay. The surface-treatment of section C consisted of an application of tar of 25 to 35 specific viscosity at 40° C., applied cold, and a cover of $1\frac{1}{4}$ -to $\frac{1}{4}$ -inch stone. Sections D and E were surface-treated in the same manner except that the bituminous material was a hot-application tar.

Experiment 6 lies entirely in rolling country and has good natural drainage except for about 200 feet of section B which borders a swampy area. The sub-grade varied considerably in composition, the west portion of section A, the east and west ends of section B, and the east half of section C appearing to have more clay than the remainder of the experimental section. This was quite noticeable both in mixing and in the appearance of the finished mixture. Sections D and E appeared to contain little clay as the untreated material pulverized easily before the tar was applied, coated readily, and was uniform and free from uncoated clay balls when mixing was completed. Sections A, B, and C, on the other hand, required more than the usual amount of mixing, in spite of which a uniform mix was not obtained owing to the presence of many uncoated clay balls.

During the construction of sections A, B, C, and D, mixing was interrupted by rain and additional blading was necessary to dry the mixture. Under traffic the mixture, on those areas that had appeared high in clay content, did not compact into a dense uniform mat but into stratified layers, the surface being considerably marked by irregular vertical cracks.

Sections A and B, for which surface-enrichment was planned, began to dust under traffic before they had compacted. An attempt to enrich the surface of section A while in a dusty condition proved unsuccessful, so the two sections were remixed and relaid. They were then given the surface-enrichment application immediately after initial compaction had been obtained and before dusting could start—a period of about 24 hours.

The enrichment application, amounting to 0.27 gallon per square yard for section A and 0.28 gallon per square yard for section B, was lightly covered with tar-treated sand-clay which had been previously bladed from the mat and windrowed at the sides for this purpose.

Sections C and D were given a light application of 18 to 25 viscosity tar after they had been compacted and before the surface treatment was applied.

Section E varied from the other sections of experiment 6 in that different amounts of tar were used in four portions of the base, to determine, if possible, the most satisfactory amount of bitumen. The section was divided into four equal parts and the amounts of tar used originally were 1.77 gallons per square yard for the first, 2.18 gallons per square yard for the second, and 2.60 gallons per square yard for the third. When these three areas had been mixed and compacted they were given a prime application of 0.33 gallon of tar per square yard. Almost immediately, however, parts 2 and 3 shoved and rutted badly, apparently because of an excess of bitumen. Part 1 appeared lean but remained stable during a 2-week period under traffic. Parts 2 and 3 were remixed and relaid. The behavior of these 3 parts indicated that about 2.00 gallons per square yard should be nearly correct. Application of 2.08 gallons per square yard on the fourth part resulted in a mixture that was stable under traffic. Parts 2, 3, and 4 were primed with one-fourth gallon of 18 to 25 viscosity tar per square yard before the hot tar and stone cover were applied.

Within 2 months after construction sections A and B had become extremely rough and the excessive cracking which had developed gave them a very unsightly appearance. A hard, leathery crust formed on the surface, making it impossible to blade the surface to eliminate the roughness caused by shoving. After a considerable period of time the mixture apparently developed stability and internal movement decreased, but surface smoothness was never obtained to any high degree even after the sections were given a surface treatment and a stone cover in 1931.

Section C was considerably more satisfactory in behavior than sections A and B, but not nearly as satisfactory as sections D and E. The east end of section C required fairly heavy maintenance in its early life, partly because of subgrade failure and partly because of the unstable mat. This portion of the section contained a considerable amount of clay, both in the subgrade and in the mixed base.

Sections D and E were quite satisfactory from the start. Their bases were stable and their surfaces were smooth and generally free from cracking or raveling. Because of its high crown, section E required somewhat more maintenance than section D to remedy edge failure.

In 1931 the entire experimental section was given its first re-treatment which consisted of 0.36 gallon per square yard of the TC grade 5 tar having a specific viscosity of 48.7 at 40° C. and 37 pounds of $\frac{3}{4}$ - to $\frac{3}{4}$ -inch stone per square yard. This treatment considerably improved the condition of all of the sections but did not eliminate entirely the surface roughness of sections A, B, and part of C.

When inspected in March 1934 all of the sections were in need of a re-treatment. Sections A and B were both excessively rough, and on section B an appreciable portion of the base had been replaced by new mixed material to obtain stability.

EXPERIMENT 7 REMAINED IN GOOD CONDITION AND GAVE SATISFACTORY SERVICE

Sections C, D, and E had lost their uniform appearance due to whipping off of the cover stone, but with the exception of a portion of section C all were fairly smooth.

The construction and average annual maintenance costs for experiment 6 are given in table 12. The average annual maintenance costs as given might indicate equivalent behavior of section C as compared with sections D and E; however, at no time in its life was section C as satisfactory as the other two.

Experiment 7, extending from station 794 to station 1000, had a 2-inch mixed base of sand-clay and cut-

 TABLE 12.—Construction and average annual maintenance costs

 per square yard for experiment 6

		Average				
Section	Bitumi- nous ma- terial	Cover material	Labor, supplies, and equip- ment	Total	annual mainte- nance costs	
А В С D Е	Cents 38. 84 51. 96 43. 91 41. 70 37. 54	Cents 9, 58 9, 65 9, 58	Cents 10.52 11.98 9.80 10.96 12.77	Cents 49.36 63.94 63.29 62.31 59.89	Cents 3, 10 4, 18 2, 78 2, 59 2, 84	

back asphalt. It was sealed with hot asphalt or cutback and covered with crushed stone.

This experiment covers three sections in which the base was a 2-inch mixture of 85 to 100 penetration cutback asphalt. The surface treatment was a hot asphalt on sections A and B, and an 85 to 100 penetration cut-back asphalt on section C. All three sections were covered with 1½- to ½-inch stone.

The surface and subgrade on this experimental section varied somewhat throughout its 4-mile length but appeared to be of sandier composition than most of the preceding sections. The sand-clay was broken up readily with the blade and the newly exposed, untreated base broke up under traffic and also under the construction equipment so that the resulting mixed base was actually as much as 6 inches thick in the sandiest locations. Mixing was easily accomplished and, when laid down, the mixture compacted readily into a smooth, well-bonded mat that did not dust under traffic. A light prime of 85 to 100 penetration cutback was applied to sections A and B but not to section C. Sections A and B then received the application of hot asphalt and stone cover, and section C received an application of the 85 to 100 penetration cutback and a stone cover.

The design of section A of experiment 7 was similar to that of section E of experiment 6 in that varying quantities of bitumen were used in the base. The amounts originally applied were insufficient for the east half and excessive on the west half. The section was remixed, adding bitumen to the east half and additional untreated material to the west half. When the mixing was completed the mat compacted and bonded readily under traffic and when surface treated it appeared to be in excellent condition.

Considerable roughness developed on a short curved area at the east end of section B and on two areas of section C. This was caused by a combination of bad subgrade conditions and lean base. These areas were scarified, remixed, and re-treated in 1929.

Except for the failure just mentioned, experiment 7 has remained in good condition and has given excellent service. Surface roughness caused by subgrade settlement gradually developed eventually but no inherent weaknesses, that could not be eliminated by surface treatment, made their appearance. Only one re-treatment has been given since construction, and that was applied to section A in 1932 and to sections B and C in 1931. It consisted of 0.42 gallon of 150 to 200 penetration cutback and 35 pounds of $\frac{3}{4}$ - to $\frac{3}{4}$ -inch stone per square yard for section A, and 0.32 gallon of 85 to 100 penetration cutback and 40 pounds of $\frac{3}{4}$ - to $\frac{3}{4}$ -inch stone per square yard for sections B and C. The good behavior of this experimental section is reflected in its average annual maintenance cost and in its condition which, in March 1934, showed it to be stable and free from cracking, raveling, or other evidences of impending failure. Its surface roughness could be eliminated by a fairly heavy re-treatment.

The construction and average annual maintenance costs per square yard for experiment 7 are given in table 13.

 TABLE 13.--Construction and average annual maintenance costs

 per square yard for experiment 7

		Construction costs						
Section	Bitumi- nous material	Cover material	Labor, supplies, and equip- ment	Total	A verage annual mainte- nance costs			
A B C	Cents 28, 67 30, 84 25, 80	Cents 9, 58 9, 60 9, 58	Cents 7, 92 8, 20 9, 88	Cents 46, 17 48, 64 45, 26	Cents 3. 21 2. 63 3. 68			

SURFACE ON EXPERIMENT 8 WAS VERY SATISFACTORY AND ECONOMICAL

Experiment 8, extending from station 1000 to station 1087, was a surface treatment of sand-clay with a prime of tar or cut-back asphalt. It was sealed with hot asphalt and covered with crushed stone.

This experiment was included in the project for comparison with the mixed-base experiments and also with similar treatments that were constructed elsewhere in the State upon other types of bases believed at that time more suitable for such treatment.

The sand-clay surface of this experimental section was, in general, more stable than that on the other sections due to a higher percentage of coarse sand. In this respect the west half of the section appeared to be more satisfactory than the east half.

The main difficulty experienced in constructing experiment 8 was in the preparation of the surface for treatment. The road was scarified and shaped with a blade grader to produce a uniform cross-section. Compaction was obtained by traffic and only under favorable moisture conditions. Three times, each just after a rain, the surface was lightly bladed while in a moist condition, removing the blade grader before the surface dried appreciably to prevent the accumulation of loose material that would not bond when dry.

After it had been consolidated as well as possible, the surface was swept with a rotary broom and by hand. After sweeping, it presented a very ragged appearance owing to the many depressions found where sand pockets had previously existed. These depressions were filled with stone before applying the prime.

Approximately 0.3 gallon per square yard of 8 to 13 viscosity tar was applied as a prime, but many small areas were not satisfactorily covered. A light second application of tar, however, successfully covered these areas and gave the surface a uniformly well-primed appearance. The total amount of tar prime used was 0.47 gallon per square yard. As the quantity of light tar on hand was insufficient for priming the entire section, a portion at the east end of the section, stations 1000 to 1026, was primed with 85 to 100 penetration cut-back asphalt at the rate of 0.55 gallon per square yard.

After an interval of 4 to 6 days during which traffic was excluded, the primed base was given an application of 0.38 gallon per square yard of 150 to 200 penetration asphalt applied at 275° to 315° F. and was immediately covered with 60 pounds per square yard of $1\frac{1}{4}$ - to $\frac{1}{4}$ -inch stone. Light rolling followed the spreading of the stone cover and in this operation considerable care was required to prevent breaking the mat.

Rather intensive maintenance was required for the first 2 months until the first re-treatment was applied in December 1927. In spite of this, however, the cost of experiment 8 for the first year, both for maintenance and for the seal, was less than the average for the remainder of the experimental sections. Since the December 1927 treatment, experiment 8 has received only one re-treatment. The portion between stations 1026 and 1087 was re-treated in 1929 and the remainder was re-treated in 1931.

During its life the principal defect of this section has been its surface roughness which, while considerable, was not as pronounced as that of some of the other sections. Roughness was caused by slight subgrade movement, not by failure of the surface mat. Some cracking has occurred more recently but the surface has not raveled or shoved.

Considering its construction and maintenance costs, this experiment has been surprisingly satisfactory and economical. The stability developed by the sand-clay mixture was greater than had been anticipated, and construction of the waterproof surface enable the base to retain this stability. The section weathered the winter of 1933-34, which was an unusually severe one, in excellent shape, in contrast to similar projects On these latter projects clay-gravel bases nearby. with high clay contents had been constructed on the loosely bonded sand-clay surface, and upon these bases surface treatments similar to those of experiment 8 had been constructed. The repeated cycles of freezing and thawing and the effect of moisture on the clay-gravel base resulted in extensive cracking and many areas of complete disintegration of these surfaces. Surface repairs proved inadequate for such failures and the only alternative was removal of the clay-gravel base, substitution of a pre-mixed, sand-asphalt base, and the construction of a new surface. No such repairs have been required on experiment 8. Figure 12, taken 4 years after construction, is typical of the appearance and condition it has retained since construction.

The cost per square yard of constructing experiment 8 were as follows:

	Cents
Bituminous materials	8.91
Cover material	9.58
Labor, supplies and equipment	6.50
-	
Total	24.99
Average annual maintenance cost per square yard	3.54

RESULTS EMPHASIZED IMPORTANCE OF HAVING A STABLE SUBGRADE

Because of progress made in the field of low-cost bituminous construction since this experimental road was built, most of the details of construction and many of the facts established by this experiment are already well known and accepted. However, the great variety of factors covered by the experiment and the fact that it has been under close observation for 7 years justify some discussion of the observations made and the data accumulated during this period.

The discussion is based entirely upon conditions that obtained on this experimental road and consequently the conclusions drawn are not necessarily applicable to



FIGURE 12.—VIEW OF EXPERIMENT 8 TAKEN 4 YEARS AFTER CONSTRUCTION. THIS IS TYPICAL OF THE APPEARANCE AND CONDITION IT HAS RETAINED SINCE CONSTRUCTION.



FIGURE 13.—POOR DRAINAGE RESULTED IN THE UNSATISFAC-TORY CONDITION OF THIS AREA OF EXPERIMENT 3 NEAR STATION 363. ANALYSES OF MAT AND SUBGRADE FROM THIS AREA ARE GIVEN IN TABLE 7.

other projects where the soils and drainage conditions are materially different. Table 4 shows that the soil on this road is a fine-grained, sandy material containing a large percentage of fine sand and small percentages of coarse sand, silt, and clay. It cannot be safely assumed that with other fine-grained soil materials as, for example, soils of high silt content but deficient in sand, the same results would be obtained in bituminous construction of the character described in this report.

The general belief that the service behavior of any flexible pavement is, to a great degree, dependent upon the character of its supporting subgrade is further confirmed by results obtained on this experimental road. The analyses given in table 7 show the subgrade to have properties characteristic of the A-2, A-3, A-4, and A-6 soil groups. Satisfactory and unsatisfactory surface conditions were found on both A-2 and A-6 subgrades and in most instances these conditions were associated with the drainage provided. An examination of the properties of experiment 3, given in table 7, illustrates quite clearly the effect of drainage. Only one area, that in the vicinity of station 365, continued unsatisfactory for much of the 7-year period, and this area, which was in a slight cut, was poorly drained. Its usual condition, illustrated in figure 13, is in marked contrast to the generally good condition of most of the experiment of which figures 14 and 15 are typical illustrations. Apparently neither the thickness of the bituminous mat nor its inherent stability offset the detrimental effect of poor drainage of its plastic subgrade.

Experiment 8, a thin, surface-treated section on a well-drained, plastic, A-2 soil, was considerably better than the poorly drained sections of experiments 3 and 4–B, although on the latter the bituminous mats were 2 inches and 3 inches thick originally.

The lack of uniformity in the character of the subgrade materials typified by the presence of A-6 soil immediately under the bituminous mat at stations 63 and 440, as well as in a more normally expected position at station 145 as shown in table 7, indicates in a measure the character of the maintenance presumably given the old road. Little information is available concerning previous maintenance. Apparently clay was used to stabilize the more sandy portions of the road and sandy materials were used on those areas where clay pre-



Figure 14.—General View of Experiment 3 at Station 353, Showing the Usual Condition of Most of This Experimental Section. Analyses of Bituminous Mat and of Subgrade Are Given in Table 7.

dominated. Manipulation of the clay and sand to obtain a uniform surfacing material evidently had not been done.

Two comparisons for which information was desired were obscured by the effect of variations in subgrade. They were the effect of the consistency of the asphaltic cement used in the cut-back materials and the effect of the depth of the mixed bases and surfaces. Experiment 2 included sections in which the only variable in construction methods and materials was the penetration of the asphalt used in the cutback, but at no time during the period covered by this study did this difference in penetration have any apparent effect on the sections. Experiment 5 was designed to study the relative merits of 2- and 3-inch bases but here, too, the subgrade effectively prevented a true comparison.

On the other hand, the condition of the subgrade did provide one opportunity for a comparison that would not have been possible had it been either uniformly good or bad. This was a comparison of the service behavior of the slow-curing oils used in experiments 3 and 4. The construction and maintenance of these two experimental sections have been approximately the same, the only differences being the oils used and the fact that the mat on experiment 3 was 2 inches thick while that on experiment 4 was 3 inches. This fact, however, is believed to have had little bearing upon the performance of these sections. It seemed apparent that the difference in service behavior of the two sections was primarily caused by the charactenstics of the oils.

MIXTURE RETAINED HALF OF ITS ORIGINAL VOLATILE MATTER 7 YEARS AFTER CONSTRUCTION

The three types of bituminous materials used in the mixed bases were cold-application materials of relatively low viscosity. The slow-curing oils were not



FIGURE 15.—ILLUSTRATION OF THE CLOSED TEXTURE CHARAC-TERISTIC OF MOST OF EXPERIMENT 3. ANALYSES OF MAT AND OF UNDERLYING SUBGRADE AT STATION 353 ARE GIVEN IN TABLE 7.

expected to harden greatly or increase in cementitiousness in service. The cut-back asphalts and the 18 to 25 viscosity tar, however, contained volatile material which was expected to be lost during construction or shortly thereafter, leaving a bituminous residue of a consistency sufficiently high for good binding quality. During construction no difficulty was encountered in manipulating and spreading the mixtures or in remixing some of the cut-back sections after a year or two. Neither the tar nor the cutbacks stiffened appreciably except on the immediate surface until considerable time had elapsed. The actual loss of volatile matter during construction was not determined but was apparently much less than had been expected.

A sample, whose analysis is given in table 7 under laboratory no. 39362, representing the full depth of the original mixed base containing cut-back asphalt, was taken 7 years after construction to determine whether it still retained any appreciable amount of volatile matter. Upon examination it showed that 18.4 percent of the existing bitumen was volatile matter as determined by an oven test made on the mixture at 325° F. Since the cutback used originally showed a maximum loss of 33.9 percent at 325° F. in the standard oven test, it is indicated that approximately 53 percent of the volatile matter was still present after a period of 7 years. It seems apparent, therefore, that the loss of volatile matter at the surface resulted in the development of a viscous material which, in combination with the finegrained aggregate, formed a tight seal that effectively prevented the escape of the volatile matter in the binder below the surface. Evidently the rate of hardening of the cut-back asphalt was more dependent upon the manner in which it was used than upon the character of its volatile constituent.

For the conditions existing on this road it is apparent that manipulation of the mixture could well have been continued over a longer period of time. Had this been done, a higher consistency would have been developed by the bituminous material with a corresponding lessening of the effect of the variation in the grading of the mineral aggregate. Later practice has been either to continue manipulation to eliminate as much of the volatile material as possible without leaving the mixture too tacky to spread and compact, or to apply the bitumen in smaller increments and to do considerable manipulation after each application. The latter method is probably better as it would afford the engineer a better opportunity of making a final decision as to the correctness of the mixture.

The penetration of the asphalts used in the cut-backs ranged from 85 to 180. The effect of this difference in penetration was not apparent either on the relative durability of the material or upon the re-treatments required. In all cases other factors so overshadowed the difference in the cut-back asphalts that their comparative values could not be established.

The slow-curing oils differed considerably from the cut-backs in their characteristics and behavior as a binding medium. As shown by the analyses, given in table 1, they contained relatively small amounts of volatile matter as determined by the standard oven test and the residues from this test were fluid. The behavior of experiment 3 was considerably different than that of experiment 4 due to the characteristics of the oils used. The mixture of experiment 3 did not develop the brittleness and raveling typical of experiment 4. Analyses of the oils used in the two experimental sections likewise showed a considerable difference in characteristics. Oil A, which was furnished as a straight reduced material, had a low specific gravity and high solubility in naphtha. Oils B, C, and D had relatively high gravities and low solubilities in naphtha, indicating that they were more highly cracked in the process of manufacture than was oil A, or that they contained greater percentages of cracked material.

TAR MIXTURES ATTAINED GREATER STABILITY THROUGHOUT DEPTH THAN DID CUT-BACK MIXTURES

In the re-treatment of experiments 3 and 4 in 1928 and 1933 it was intended to use the same type of oil that was used in the construction of experiment 3, but analysis of the oil used showed it to have characteristics more nearly like those of oils B, C, and D, indi-

cating that it, too, was a cracked oil. Analyses of the oils used in the re-treatment of sections B and C of experiment 4 in 1930 are not available but were supposed to be the same as those of the oils used in their original construction. Considering the characteristics of the oils used in the re-treatments of 1928 and 1933, it is most likely that the oils used in 1930 were not greatly different from those used originally. The difference, if any, was at no time apparent in the behavior of sections A, B, and C.

Except for crusting of the immediate surface, experiment 3 continued more malleable throughout its life than did experiment 4. The stabilities developed by the mixtures in their early life were comparatively low and while they increased slowly, that of the mixture of experiment 4 increased more rapidly than that of experiment 3. The surface of both experimental sections was abraded somewhat by traffic and the loosened material dissipated, but experiment 3, because of its higher plasticity, in general, suffered less from mutilative traffic and, when disturbed, rebonded much better than did experiment 4. The latter experimental section, however, appeared to be less affected by moisture.

On sections A and D of experiment 5, oil E, which was similar in character to oil B, was used for the surface enrichment of the mixed base in which a cutback asphalt had been used. In this case the mixed base developed a certain degree of hardness while the upper portion, enriched with the slow-curing oil, remained more plastic. This resulted in considerable shoving and displacement of the surface which soon became so rough that re-treatment with cut-back asphalt and stone cover was necessary to restore a satisfactory degree of smoothness. Figure 7–A illustrates the rough condition of section 5–D caused by surface enrichment with slow-curing oil.

On experiment 8 a tar of 8 to 13 specific viscosity and a naphtha cut-back asphalt were used for priming the sand-clay base prior to surface treatment. Rapidcuring material such as cut-back asphalt is seldom used for priming purposes and it was used here only because of a shortage of tar prime. Little difference in behavior of the areas thus primed has been apparent so far. The area on which the cut-back was used, however, was sandier and more open than the remainder of the section, which probably accounts for the penetration of the cutback.

The 18 to 25 viscosity tar used in the mixed base of experiment 6 and in the surface enrichment of sections A and B of that experimental section was comparable in some respects to the cut-back asphalts. It was a low viscosity, cold-application material containing a considerable amount of volatile matter and, upon losing this volatile matter, it developed a residue comparable with those of the cut-back asphalts in consistency. This change in consistency, while somewhat slow, extended through the full depth of the base and was not confined to the surface alone as in the case of the cut-backs. As shown in table 7, stability tests made on samples taken 7 years after construction show that the stability of the mixture 1 and 2 inches below the surface is relatively high in comparison with the top 1-inch of the tar mixtures, but in the cut-back asphalt mixtures the corresponding stability is substantially less for portions of the mixture below the surface than at the top.

Where the 18 to 25 viscosity tar was used in the surface enrichment of sections 6-A and 6-B it readily lost sufficient of its volatile matter to produce a hard

crust which, however, was relatively thin. This same bituminous material within the mixture did not lose its volatile constituents so rapidly and as a result the base remained relatively plastic. As a consequence, considerable shoving and corrugating of the mat and cracking of the surface crust occurred. This condition continued in gradually decreasing intensity for approximately 4 years or, apparently, until the bitumen in the base had developed a consistency sufficiently high to provide the stability required. When stability had been developed as indicated by a cessation of mat movement, the sections were given the long-needed surface treatment which had been delayed for fear of retarding the slowly increasing stability.

BOTH HOT- AND COLD-APPLICATION MATERIALS USED TO SURFACE-TREAT MIXED BASES

The 25 to 35 viscosity tar and the hot tar were used as binders in the surface treatment of sections 6-C, D, and E to provide information on the relative merits of cold- and hot-application materials. At the time the 25 to 35 viscosity grade was thought to approach the maximum viscosity for cold application and though it may be considered to have been reasonably satisfactory, later experience has shown that considerably higher viscosity materials can be used advantageously. It will be recalled that in the re-treatment given experiment 6 in 1931 a tar of 48.7 viscosity at 40° C. was used. No difficulty was encountered in applying this material or in road-mixing it with the cover stone. In spite of the relatively high viscosity of the tar, approximately 10 days elapsed before the surface had stiffened sufficiently to resist picking up under traffic. This was believed due to the low rate of loss of volatile matter.

Analysis of the 25 to 35 viscosity tar is not available but it may be reasonably assumed that, like the 18 to 25 and the 48.7 viscosity tars used in the base construction and in the re-treatment of 1931, it contained some volatile matter which when lost would leave a base material sufficiently viscous to hold the cover stone. The hot material, on the other hand, would be expected to lose very little through volatilization, the fluidity desired for application purposes being obtained by heating. This basic difference between the hot- and cold-application binders was reflected in their behavior.

In surface treatment of the mixed bases both hot- and cold-application tars and asphalts were used with mineral covers. The hot-application materials, because of their high viscosity, did not penetrate into the mixed bases but remained on the surface, adequately holding the cover material to form a hard mat which received the wear of traffic.

The cold-application materials, on the other hand, penetrated into the base in varying amounts depending upon their viscosity and the denseness of the base. Penetration in any considerable amount resulted in softening of the mixed base with consequent reduction in its stability. Penetration also permitted the cover material to become embedded in the base, forming a mastic which received the wear of traffic. When less penetration occurred, softening of the base was not so pronounced, but the loss of bitumen by penetration as well as by evaporation reduced the amount available for holding the cover materials, which were thereby subject to displacement under traffic.

Where the mixed mat was well compacted before the surface treatment was applied, the cold-application

materials did not penetrate and were satisfactory. An illustration of this is experiment 2 A, which has a record of excellent service behavior at relatively low cost.

In addition to the possibility of loss by penetration, evaporation losses also reduced the net amount of bitumen correspondingly. Increasing the amount of bitumen and modifying the method of applying the treatment might have offset these losses and also might have prevented penetration in some instances. It appears advisable and more practical, however, that the surface treatment material used should be of such viscosity that it will not penetrate into the base or else that the method of applying the treatment be such that penetration is reduced to a minimum.

The amount of bitumen used in the mixes of the different sections varied considerably, as shown in table 5. Some of this variation was planned, as in the case of experiments 6-E and 7-A, but in all other sections it was the result of the method of construction.

Formulas for determining the amount of bitumen to use with aggregates of a given grading have been developed more recently and used satisfactorily by a number of States. Such formulas apparently have very narrow limits of application since none is used widely outside of the State in which it was developed, and in most cases where used by other States some modification of the formula has been found necessary. In addition, the formulas are applied to aggregates whose grading is uniform and, regardless of the correctness of the formula, uniform mixtures should be expected.

IMPOSSIBLE TO DESIGN MIXTURES BY EMPIRICAL FORMULAS

With the exception of experiments 3, 4, 5, 6-A, and 6–B, the mixed sections served as bases, surface-treated with bitumen and mineral cover; consequently, they were designed for stability primarily and as a result contain less bitumen than they would have if they had been intended to serve as wear-resisting surfaces. Comparison of their bitumen content with any empirical formula would therefore serve no useful purpose. The mixed sections designed to carry traffic without any additional wearing surface do offer an opportunity for comparison of the percentage of bitumen actually used with that required by theoretical formulas and curves, although the variation in grading of the aggregate and the frequency with which this variation occurred would have made the application of an empirical formula futile in design.

On this project, experiments 3 and 4 were of uniform composition throughout their depth, while experiments 5, 6–A, and 6–B were leaner in the lower portion and enriched in the upper portion but were not covered with wear-resisting mineral cover. To present such comparison as can be made, the analyses of samples taken from the non-surface-treated sections are retabulated in table 14 for convenience. The data given in this table indicate that neither an empirical formula nor a numerical stability value, which is a variable characteristic, should be arbitrarily selected because of its successful use under other conditions or with bituminous materials of different characteristics. Table 14 shows that considerable variation in stability is found when different bituminous materials are used and also that numerical stability value alone does not indicate probable service behavior.

TABLE 14.—Comparison	of the kind and	quantity of bitumen	with stability of bituminous	mixtures
----------------------	-----------------	---------------------	------------------------------	----------

1			Hubbar	d-Field sta 77° F.	bility at	Amou	int of bitu	men 1	
Sample	Experi- ment	Type of bitumen used				Extract-	Requir	ed by-	Remarks ³
	no.		Maxi- mum	Mini- mum	∆verage	ed from field samples	Surface- area method	Nebraska formula ²	
39359	3	Slow-curing oil	Pounds 1, 620	Pounds 1, 550	Pounds 1, 585	Percent 7.64	Percent 7.25	Percent 5. 34	Good area, stable when sampled; remains so in cool weather. Ruts slightly in warm weather but irons out under traffic.
39358	3	do	1, 730	1, 730	1, 730	7.30	7.52	5. 58	Stability appears adequate. Poorly drained area in bad condition. Behavior in dry weather same as above.
39357	3	do	2,910	830	1,870	10.14	7.30	5.51	From a cracked area affected by moisture. Service behavior
39356a	4-B	do	270	40	155	10. 14	7.17	5. 21	good. Stability appeared adequate when sampled. New mixture on old mat; has no resistance to displacement except in cool weather. Stability when sampled was inade- ouate.
39356b	4-B	do	3, 050	2,000	2, 525	10, 25	7. 57	5.67	Old mat below sample above. Stable except in very hot weather. Dusts under traffic. Stability (against shoving) adequate when sampled.
39355	4-C	do	940	700	820	7.53	7.16	5.34	Service behavior same as above. Stability when sampled was adequate.
39354	4-C	ob	1, 160	940	1, 045	11.35	7.40	5.52	Same as above.
39362	5-C	Cut-back asphalt	5, 400	2, 940	4, 170	8.35	9.15	6. 54	Retains stability irrespective of temperature. Continues in excellent condition except for edge failure. Stability ade- quate when sampled.
39361	6-A	18-25 viscosity tar	5, 575	3, 640	4, 607	7.53	7.60	5.75	Stability accompanied by dusting, increased with age. Sur- face rough, resulting from early movement. Stability ade-
39360	6-B	do	5, 710	4, 525	5, 232	9. 53	6.90	5.12	quate when sampled. Behavior and condition same as above.

In terms of dry aggregate.
P=0.02a+0.04b+0.06c+0.12d when:
P=percentage of bitumen.
a=percentage of aggregate retained on No. 50 sieve.
b=percent passing No. 50 and retained on No. 100 sieve.
c=percent passing No. 100 and retained on No. 200 sieve.
d=percent passing No. 200 sieve.
Also see table 7.

It is apparent therefore that experience, excellent judgment, and great care on the part of the engineer are of utmost importance in the construction of roadmixed surfaces under conditions characteristic of this road.

For fine-grained, poorly graded aggregates such as were found on this road, the range in bitumen content between mixtures sufficiently rich to resist abrasion without shoving and those whose richness results in shoving is very narrow. Because of this it was practically impossible to obtain a satisfactory, stable, wear-resisting mat without surface treatment. This was tried on experiments 3, 4, 5, 6-A, and 6-B and was only partially successful.

On experiment 3, when the mat was rich enough to resist abrasion it displaced under traffic, especially in warm weather. However, it retained its malleability, and such surface irregularities as occurred were readily ironed out by traffic. As the viscosity of the oil increased because of lower air temperatures or by oxidation caused by weathering, the resistance of the mat to slight movements increased and was usually accompanied by dusting. Addition of the same type of oil eliminated dusting, but, at the same time, reduced the ability of the mat to resist movement.

The behavior of experiment 4 was similar to that of experiment 3, although here greater stability as well as increased dusting and raveling were characteristic. The two sections of experiment 5, on which the slowcuring oil was used, were unsatisfactory without surface treatment because of their inability to resist displacement. The other two sections of experiment 5, on which a rapid-curing material was used in surface enrichment, continued the most stable of the sections not surface-treated. The mats were firm and hard, and did not dust appreciably under traffic. They were rather rough, however, and their edges suffered from

mutilative traffic. Sections 6-A and 6-B, which were surface enriched but not surface treated, were unsatisfactory also. The amount of bitumen required to prevent dusting produced a mixture that shoved considerably and was excessively rough.

Comparison between the surface-treated bases in general with the sections not so treated demonstrates the advisability of constructing a rather lean mat of adequate stability and upon it constructing a wearresisting surface. This method of improving the loosely bound, sand-clay roads such as were found on this road has been used by the State with considerable success on a rather extensive mileage.

MIXING OF RE-TREATMENTS GAVE BEST RESULTS

With the exception of six sections of experiment 2, all sections that were surface-treated were covered with crushed granite $1\frac{1}{4}$ to $\frac{1}{4}$ inch in size. The exceptions were sections 2-B, 2-E, and 2-H on which pea gravel was used, and 2-C, 2-D, and 2-I on which local pit-run sand was the cover material.

One of the pea-gravel sections was resurfaced with stone in its earlier life but the necessity for re-treating was not caused by any failure of the original cover material, and stone was used in the re-treatment merely as a matter of convenience. Although the gravel cover did crush somewhat under the roller and under traffic, no failures directly attributable to its use were apparent.

The sand-covered sections were re-treated early in their life and, while subgrade conditions and unstable mixed bases were the main causes for reconstruction and re-treatment, the use of sand as a cover also contributed greatly to the failure of these sections. The same lowviscosity, cold-application material used in the mixtures was used as a seal in combination with the sand in surface treatment, with the result that the sand



FIGURE 16.—Steps in the Application and Mixing of a Re-treatment. A, Applying Bitumen. End Nozzles Were Turned 90° to Obtain Heavier Application at the Edges. Note that Some Cover Material Has Been Spread Prior to Applying Bitumen. B, Spreading Cover Material Immediately After Applying the Bitumen. C, Manipulating Cover Material and Bitumen in Mixing the Re-treatment. D, Mixing the Re-treatment. Variable Appearance Results from Sufface Irregularities. Blade Picks Up Cover Material from High Spots but Cannot Remove It from Depressions, so this Work Is Done by Hand.

became a part of the mixed base instead of serving as a protection against traffic wear. Three types of failure developed in these sections; pot-holing, edge failure by abrasion under traffic, and excessive roughness caused by loss of stability in the mixture due to the increase of bitumen.

Section 2–I was covered with stone 1 year after construction and sections 2–C and 2–D were similarly treated a year later. This treatment eliminated the failure not caused by subgrade conditions.

In the re-treatments following construction, crushed granite, usually three-fourths to one-fourth inch in size, was used except on section 2–B on which the gravel cover has been retained.

In applying re-treatments to the various sections, effort was made to continue the type of experiment unchanged as long as possible, or until it was demonstrated that no useful purpose would be served by continuing it unchanged and that better service could be obtained by changing it. In the early life of the experimental sections the re-treatments consisted of applying the same type of bituminous material and of cover that were used in the original construction. The inability to differentiate between the merits of the various grades of cut-back and the unsatisfactory results obtained from using sand as a cover soon resulted in the adoption of a single grade of cut-back and the use of stone only as cover material except in the case of section 2–B.

The majority of re-treatments were applied to eliminate surface roughness caused primarily by base and subgrade settlement and by movement of the richer mixes, especially during their early life. In applying re-treatments the cover materials were spread by hand and, in the earlier treatments, they were broomed by hand and by dragging to obtain a smooth surface. Later, however, as subgrade settlement increased with a correspondingly greater surface roughness, the plan of mixing and spreading the bitumen and cover used in re-treatment with blades or drags was introduced. This method, which was an innovation at least in this part of the country, was very satisfactory and the resulting surfaces were smooth, but obviously not uniform in depth. Where the existing mat was remixed prior to applying the surface retreatment, mixing of the bitumen and aggregate composing the treatment was not done. Where the existing surface was not to be disturbed the blade-mix method was always used.

Some advantages of using the blade-mix method, which are not obtained without using it, are the elimination of pools of bitumen in low spots, a more uniform mixture, little or no loss of cover stone, and a uniformappearing surface on which traffic will travel over the full width. Where mixing is not done, considerable cover stone is lost by traffic even though the surface has been rolled, and traffic tends to travel in a single lane. Figure 16 illustrates the method of applying the later re-treatments to the sections of this road. This method is used almost entirely by the State at the present time. The surface appearances of mixed and unmixed re-treatments are shown in figures 17 and 18.



Figure 17.— Λ , Typically Uniform Appearance of a Mixed Surface Re-treatment. B, Appearance of a Newly Retreated Surface That Was Not Mixed. On Such Surfaces Traffic Has a Decided Tendency to Travel in a Single Lane.

TYPE OF EXPERIMENT HAD NO DIRECT RELATIONSHIP TO MAINTENANCE COST

Maintenance of the roadway proper consisted of such patching and replacements as were necessary and the application of re-treatments to the old or reconstructed base and surface. This work is included in the maintenance costs given herein which do not, however, include such work as the construction and maintenance of shoulders, side ditches, or the installation of supplementary drainage fixtures.

With the exception of experiments 3 and 4, the experiments were not designed for machine maintenance, and repairs were made by patching and by re-treatment. Experiments 3 and 4 were included to provide a comparison not only of the oils used but also of methods of maintenance. The mats of these two experimental sections remained relatively malleable in comparison with those in which cut-back asphalts and tars were used, but because of surface crusting caused by hardening of the bitumen at the surface they were not suited to machine maintenance, contrary to expectations. Under favorable conditions the surface could be lightly cut for smoothing purposes, though the material thus cut from high spots did not bond in the depressed areas but was whipped from the surface by traffic. Continual blading to maintain smoothness on such surfaces could only result in the dissipation of the entire mat. The alternative to excessive planing was remixing of the entire mat with or without the addition of bitumen.

Since the period covered by the cooperative study of this experimental road, considerable success has been attained in lessening the effect of certain unfavorable subgrade conditions by building a new sand-cutbackasphalt mat over the old surface. The depth of the new mat is varied from 3 to 8 inches depending upon the condition of the subgrade and old surface.

Costs of the experimental sections, both for construction and for maintenance, are given in table 6. In considering these costs it should be remembered that the old road had been maintained as a sand-clay project whose behavior has already been described and also that supplementary drainage had not been provided, nor had any grade lines been established. Work of this character which has been done since construction, such as installing French drains and pipe, and banking curves, has necessitated additional patching and the use of extra surfacing materials, and as a result has had some effect on the cost of maintenance. The shortness of the sections and the variety of materials used both in construction and early maintenance also added to the costs.

It might be expected that the maintenance cost would be about inversely proportional to the construction cost. Such, however, was not the case nor did the type of experiment bear any direct relationship to the maintenance cost. Experiments 1-B, 7-A, and 7-B were identical in construction, differences in cost being due primarily to length of haul. The maintenance cost of experiment 1-B, however, is 2.7 and 3.3 times that of 7-A and 7-B, respectively, and its total cost for the period is more than 50 percent greater than these two in spite of the fact that they cost approximately 50 percent more to construct. This difference in maintenance cost can be attributed almost entirely to the additional maintenance required on experiment 1-B because of subgrade failure. The low maintenance cost of experiment 6 cannot be assumed to indicate continued satisfactory service for, as stated previously, the instability of the mixture on this experiment made it inadvisable to apply surface treatments which should have been applied to eliminate the surface roughness that was characteristic of the experiment throughout most of the period.

CONSTRUCTION AND RE-TREATMENT OPERATIONS DID NOT INTERFERE WITH TRAFFIC

Sections A, F, and G of experiment 2 were identical except for the consistency of the base asphalt used in the cut-back. Sections B, E, and H, and C, D, and I were alike in the same way. The difference in maintenance cost between A, F, and G, represents approximately the differences in subgrade conditions, and the same applies also to sections B, E, and H. Sections D, E, and F were the same except for the cover materials which were sand, gravel, and stone, respectively. Subgrade conditions appeared about the same on sections D and E and were better than on F, and the differences in cost fairly well reflect the differences in amount of surface maintenance required.

Experiment 8, the double surface-treatment constructed on sand-clay, was maintained at a relatively low cost in spite of its low construction cost. The subgrade soil on this experiment, contrary to early expectations, proved quite satisfactory for the type of construction used because the drainage was apparently adequate.

Another item entering into the cost of maintenance but not indicated by the figures alone was the additional work done in superelevating some of the curves, nor is the actual condition of the sections from day to day indicated by a study of the cost figures. Some sections were decidedly smoother than others, some were rather rough most of the time, and some, such as experiments 3 and 4, continued in a loose condition for some time after re-treatment and, even after they had become compacted, became soft during hot weather. All such points must receive consideration in any attempt to evaluate the different sections from the standpoint of cost and adequacy.

The experimental road, at the time of its completion, did not connect with or touch any part of an improved highway system with all-weather surfaces. The traffic carried by the road prior to construction was mostly local, a fair proportion of which was horse-drawn vehicles carrying from light to relatively heavy loads. Some motor vehicles used the road, but few trucks or busses. The last traffic count, taken before the experimental sections were constructed, showed the road to be carrying 486 vehicles daily. One year after construction it was carrying an average of 559 vehicles daily.

With the gradual improvement of highways in this area other satisfactory travel routes became available for both local and through traffic. Despite this fact, however, the 1935 count shows a considerable increase in traffic since construction of the project. In addition it shows the relatively heavy traffic carried during the summer months when the stability of the various sections is presumably the lowest. Differentiation is also made between the traffic carried by the eastern and western portions of the road. The eastern portion extends from Homewood to Conway, is a part of both United States Highways Nos. 501 and 701, and embraces experiment 1 and about half of 2–A. The western portion of the road extends from Homewood to Gallivants Ferry, and is a part of United States Highway No. 501 only. The average daily traffic recorded for 1935 is shown in table 15.

TABLE	15Dailu	average traffi	ic carried b	u the ex	perimental road	l

Portion represented	Daily aver- age traffic for 1935	Daily aver- age traffic for June, July, and August 1935	Daily aver- age traffic, remainder of 1935
Conway-Homewood Homewood-Gallivants Ferry	Number 977 558	Number 1, 087 701	Number 942 511

The fact that the road surface is still in service and is in better condition generally than at any previous time has demonstrated the practicability of correcting, by subsequent maintenance and retreatment, many errors made initially in the choice of materials or in the methods employed. In effect, the road has been built by stage construction, with the maintenance and each re-treatment adding something to the permanent improvement of the road structure. For this reason, therefore, an appreciable part of the accumulated maintenance cost might be more properly charged on the side of construction.

Another feature merits special attention. During the construction period and also while the re-treatments were being applied, traffic was never seriously interfered with and was only slightly inconvenienced at the most. This fact is of no small importance when the matter of




FIGURE 18.—APPEARANCES OF SURFACES OF MIXED RE-TREAT-MENTS. A, AGGREGATE IS ³/₄- TO ¹/₄-INCH STONE. B, AGGRE-GATE IS PEA GRAVEL.

detours is considered, especially in localities where the topography is such that detours not only are expensive to provide and to maintain but may become traffic hazards of decided proportions. So far as the experimental project is concerned, passing traffic not only was not detrimental, but during construction served the very useful purpose of providing compaction for the mixed mats and in so doing made it possible more accurately to determine the correctness of their proportions.

CONCLUSIONS

The facts that appear to have been established during the period covered by this report may be summarized as follows:

1. The serviceability of the experimental surfaces which comprised this project was more greatly affected by the character of the subgrade than by the type of bituminous surface.

2. Failures caused by unsatisfactory subgrade conditions were not eliminated by repairs to the bituminous bases and surfaces but by the removal of the unsatisfactory subgrade materials or by providing adequate drainage.

3. Provision of a substantial subbase prior to construction of the bituminous mat will reduce considerably the cost of maintenance, which is a continuous cost.

4. The surface portions of loosely bonded sandy soils containing little or no clay were treated with a bituminous binding material to form bases satisfactory for thin bituminous wearing surfaces. 5. For loosely bonded, poorly graded, fine-grained aggregates the bituminous material must provide the stability lacking in the aggregate.

6. Manipulation of mixtures containing low-viscosity, cut-back materials should be continued until a considerable portion of the volatile matter has been dissipated.

7. The consistency of the bituminous material used in surface treatment exclusive of the priming application should be such that it will not penetrate into the base, or the method of applying the treatment should be such that penetration is reduced to a minimum.

8. Slow-curing oils that retained their fluidity for a considerable period of time did not compensate for a lack of mechanical stability in the fine aggregate but did produce mixtures that remained plastic under traffic and that, when remixed, readily rebonded with or without additional oil.

9. Slow-curing oils whose fluidity decreased because of weathering developed some binding property but produced mixtures that became brittle and subject to dusting under traffic, and did not rebond without additional oil.

10. With fine-grained, poorly-graded aggregate it was difficult to obtain a bituminous mixture that was sufficiently stable and at the same time would withstand abrasion under traffic.

11. Mixtures of the type used on this road that were sufficiently stable to resist shoving proved more satisfactory when protected with a wear-resisting surface than those that were sufficiently rich to resist traffic abrasion without a protective covering.

12. In re-treatment, a higher degree of smoothness was obtained by machine mixing and spreading the bitumen and aggregate than by hand spreading and brooming alone.

			4	AS OF DE	DECEMBER	31, 1936					
			COMPLETED		UNDER	R CONSTRUCTION		APPROVE	APPROVED FOR CONSTRUCTION	7	BALANCE OF
STATE	APPORTIONMENT	Estimated Total Cost	Federal Aid	Miles	Estimated Total Cost	Federal Aid	Miles	Estimated Total Cost	Federal Aid	Miles	FUNDS AVAIL- ABLE FOR NEW PROJECTS
Alaberna Arizona Arizona Arizonas	\$ 5,208,287 3,564,709 4,275,929	# 51,600 1,845,199	\$ 25,800 1,436,431	9.0 102.5	\$ 697,081 1,045,703 170,883	# 348.540 812.377 470.465	20.1 38.8 11.8	# 730,700 276,405 1,951,873	♣ 365,350 194,359 1,950,625	35.3 6.0 8.1	# 4,468,597 1,121,542 1,854,839
California Colorado Connecticut	9,508,671 4,575,144	5.088,641 3.314,813 501,875	2.926.297 1.767.167	138.8 129.1 0 5	8,786,655 2,977,467 700,601	5.039.277 1.634.259 3555 508	212.8 108.0	1,585,854 1,2224,055 281, 230	912,613 696,403	146.6 1491	630,484 477,315 827,498
Delaware Florida Georgia	1,218,750 3,315,558	305,920 826,514	152,960 1407,878	20.3	114.598 598.555	201.754 299.273		1,476,200	167,257 738,100	10.00	1,870,307
Idaho Illinois Indiana	3,065,304 10,325,922 6,184,258	2,478,020 6,685,740 5,149,031	1,474,863 3,334,610 2,567,006	250.6 124.9	5,763,051	538,712 538,712 2,847,051	58°4	759,995 3,999,4445	454.626 1.976.570	111.0	2,167,691
lowa Kansas Kentucky	6,466,628 6,631,085 4,611,955	7,020,5566 2,987,075 2,213,018	3, 340, 862 1,492,735 1,081,477	1466.7 606.4 142.2	2,954,783 4,679,106	1,476,205 2,313,100 500,890	376.0	2,324,349 2,402,395 830,608	1,124,024 1,201,174 415,303	123.2	1,624,076
Louisiane Maine Maryland	2,557,930 2,177,197	1,780,307	951,618	58.7	799,888	299,944	21-5 23-5 23-5 24-5 24-5 24-5 24-5 24-5 24-5 24-5 24	870,287 1484,2280 587 671	170,845 242,140	14.9	583,495
Massachusetts Mitchigan Minnesota	3,485,364 7,668,768 6,849,307	333,935 8,336,486 8,155,385	166,968 4,180,672 3.811,905	319.5	4,432,049 5,732,812 2,122,228	2,166,024 2,866,406 1,061,114	136.5	968,000 968,000	2473,742 1484,000	10.00 10.00 10.00 10.00	905.630 137.690
Mississippi Missouri Montana	4.387.636 7.601.200 5.122.333	3,992,349 7,760.971	1,992,287	435.8 384.1	768,840 6,452,361 2,616,105	3,225,855 3,225,855	240.3 240.3	937,771 2,695,727 649,237	1,337,179 725,316	119.7	3.534.131 1.045.879 1.226.625
Nebraskø Nevada New Hampshire	5,167,930 3,189,479 1,218,750	2,740,846 1,448,617 857,796	1,268,005 1,249,457 1,422,345	269.5	2,902,737 691,419 182,789	1.456,951 594,683 90.742	288 14 14 288 14 14 14	6,602 9,602 9,550	3,301 8,300 7,275	<u>د</u> ،	2,339,674 1,337,039 1,3388
New Jersey New Merico New York	3,352,469 3,990,023 12,306,710	2,198,966 3,167,008 7,169,115	1,099,332 1,947,138 3,528,507	30.4 265.7	2,569,048 1,955,831	1,207,229 1,186,499 6,817,222	29.0 103.4	19,989 197,684 7 400. 7	302,687 302,687	26.2	555.914 555.699
North Caroline North Dakota Ohio	5,879,466 3,918,269 9,131,204	2,232,465 2,334,794	1,115,370	299•2 hin o	2,748,112 384,820 6 010 220	1.362,658 204,581 2 814, 1106	215.6 .4	1,920,000	900,300	87.0	2.501,138 3.713.688 1.750 261
Oklahoma Oregon Pennsylvania	5,884,927 4,089,711 10,695,4448	2,435,519 2,708,655 6,019,128	1,264,426 1,636,974 3,009,119	82.3 101.6	2,689,102 2,689,102 7,687,391	1.054.588 1.593.680 3.835.761	79.2 113.6	450.796 781.181 2.817.007	236,891 1453,691	14	3,329,021 2,119,249
Rhode Island South Carolina South Dakota	1.218.750 3.381.337 4.078.647	213,888 176,882 1.396,263	106,944	12.9	560,780 3,893,703 160,979	280,390 1,612,170 99,019	251.53	329,667 1,341,443 782,482	164,834 495,000 420 540	110.6	666.583 1,194,167 2,766.084
Tennessee Texas Utah	5,268,270 15,548,821 2,826,960	2,170,243 10,486,420 1.992,673	1,082,992 5,227,704 1,426,511	94.2 604.0	579,456 5,308,788 779,689	2.651,430 5.251,430 5.22,715	252.5	6,055,373	2,964,628	371-7	7,490,565 4,705,059 629,972
Vermont Virginia Washington	1,218,750 4,559,200 3,904,738	1,323,337 2,427,708 2,629,667	659,042 1,211,498 1,908,725	62.9 93.7	2,239,553 2,105,186	354.748 1,119.770	20.2 109.7 811.8	1.527.537	763,768	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1,464,163
West Virginia Wisconsin Wyoming	2,716,754 6,090,504 3,121,972	477,989 4,102,133 2,830,630	238,995 1,968,299 1,741,663	28.0 164.7 367.6	1,124,522 3,833,485 1,090,246	1,862,474 665,987	32.0 129.5 125.1	692,967 802,883 µ17,860	746,484 400,385 254,870	15.9	1,569,027 1,859,347 1,59,452
District of Columbia Hawaii	1,218,750				537.793	265,921	8.6	421,060	210,195	8°,4	742,634
TOTALS	243,750,000	132,271,489	69,034,719	7.513.9	127,763,866	65,663,856	4.519.9	56,197,544	29,059,313	2,062,4	79,992,112

CTS		N BALANCL OF	Miles FUNDS AVAILS ABLE FOR SUW PROJECTS	\$ \$0.310 55.948 11.0 11.0	-	21. 1 25,360 21. 1 25,360 21. 1 2, 122,002		1		3.3 3.3 3.3 716,375 7.52 7.52 7.52		012010		10.0 20.2 58.2 148,496	200.01	N 01	18.9 614,240 10.0 53,161 3.5 93,819		-9 96,987 20,579 281,321	8.li 16.044	11, 494, 11 6.774
Y PROJECTS		APPROVED FOR CONSTRUCTION	Works Program Funds	\$ 34,000 55,221		66,957	36,000	21,450 6,600	192,802 52,100	141,900	220,759 1129,568	117.894 21.998 36.583	185.087 93.636 728.700	141.431 159.611 1.120.130	606,299 69,592 1,960,907	9,673 244,009 106,870	511,050 89,975 90,221	135,181	61,438	285,884	9,359,841
HIGHWAY	ACT OF 1935)	APPROVEL	Estimated Total Cost	\$ 34,000		66.957	19,658 36,000	57.723 6,600	230,428 52,100	141,900	220.759 597.073	117.894 21.098 36.688	194,056 93,636 728.700	177.371	618,286 69,992 1,966,721	9,673 257,317 106,870	511,050 138,047 90,221	135,181	92,170	286,422	9.964.822
PROGRAM			Miles	58.7 27.2 104.8	53.5	0 min	88 88 11 10 10	10041	105.8	10.7 6	1608	117.6 12.0	34.8	159-0 299-0 4-0 4-0	171.0 8.0 56.2	131.8	28.4 217.8 31.6	1.55.1	67.6 30.4	0.0 4	2,116.0
	2F APPROPRIATION 31,1936	UNDER CONSTRUCTION	Works Program	\$ 1,617,853 339,234 884,849	2,878,028 239,470	377,916 377,916 1,287,266	1,657,140	2,520,723 2,831,762	1,654,283 382,292 500 705	2,286,856	2,149,902	1,313,958 266,225 255,249	2,202,123 605,168 h,167,450	2,601,571 1,147,560 3,700,911	1,650,119 799,892 2,090,718	1.357.932	3,011,798 513,678	142,065 677,701 747,376	1.679.711 542.287 582.876	395.297	61.924.125
'ES WORKS	RELII 1BER	IGNN	Estimated Total Cost	* 1.617,853 565,900 886,651	2,899,548 239,486	1,287,266	1,637,140	2,673,790 2,848,316 827,502	1,855,385	2.640,216 197.071	1.476,644 2.265,859 244,036	1,315,462 266,225 257,992	2,215,275 605,168 4,295,350	2,664,760 1,150,996 3,779,307	1,651,715 1,161,327 2,140,556	1,406,463	3,290,763 3,545,041	178,368 690,775 892,267	1,680,051 699,752 601,745	25,600 401,856	EE DEC DIT
STATES	EMERGENCY AS OF DECEM		Miles	79.6 161.8 242.3	201.8	14. 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	173.7 382.7 76.6	322.3 226.1 287.5	20.00	283.0	123. 2 695. 8 185. 1	240.1 79.4	14.0 158.4	117.6 206.0 106.8	185.1 149.3 77.4	18.8 84.5 372.4	894.1 5894.1	860.1 157.7	22.0 312.8 123.1	8.6 4.0	U TUG O
UNITED	BY THE	COMPLETED	Works Program Funds	\$2,418,952 2,174,659 2,370,461	4,790,066 1,855,276	387,034 1,178,106 1,1178,106	2,043,061 6,999,745 1,776,311	2, 154, 850 2, 154, 850 2, 379, 085	884,805 884,805 1,224,205	5,957,970 b, 758, 759	1,699,701 3,370,237 3,388,267	2,139,164 1,704,805 551,621	652.052 2.030.572 6.535.331	1,816,868 1,360,193 2,701,278	2,077,953 2,035,590 1,490,359	979.535 800.528 1.902.393	2,072,209 8,834,417 1,359,436	2,661,344 2,278,785	393,276 4,261,018 1,598,095	930 , 398 228,809	100 211 247
STATUS OF	(AS PROVIDED		Estimated Total Cost	* 2,419,252 2,488,635 2,388,448	4,973,493 1,892,021	390.511	2,111,190 7,038,863	2,550,516 2,155,310 2,388,502	1,039,962 1,225,576	6,018,500 6,105,678	1,703,768 3,401,605 3,388,933	2,232,450 1,758,455 576,606	652,052 2,081,276 6,822,509	1,316,868 1,361,931 2,733,841	2,054,417 2,054,423 1,552,018	990, 131 846, 994 1,902, 992	2.079.059 9.734.549 9.734.549	2,509,038	396,480 4,798,904 1,598,113	930 , 398 2444 , C440	112.821.0691
CURRENT STA	(A)		APPORTIONMUNT	# 4,151,115 2,569,841 3,352,061	7.747.928 3.395.263	2.557.1144	2,222,747 8,694,009 4,011,255	4, 991, 664 4, 994, 975 7, 726, 271	2,890,429 1,676,799	5,262,885 6,301,414 5,277,145	3.457.552 6.012.652 3.676.416	3,870,739 2,243,074 945,225	3,129,805 2,871,397 11,046,377	4,720,173 2,867,245 7,670,815	4,580,670 3,038,642 9,347,797	989,208 2,702,012 2,976,454	11.989.350 2.067.154	924,306 3,652,667 3,026,161	2.231,412 4.823,884 2.219,155	949.496 926.033	195,000,000
CUR			STATE	Alabama Arizona Arkanaas	Cuiifornia Colorado Connecticut	Delaware Florida Georgia	Idaho Illinois Indiana	lowa Kansas Kentucky	Louisiana Maine Maryland	Massachusetts Michigan Minnesota	Mississippi Missouri Montana	Nebraska Nevada New Hampshire	New Jerscy New Mexico New York	North Carolina North Dakota Ohio	Oklahoma Oregon Pennsylvania	Rhode Island South Carolina South Dakota	Temessee Texas Utah	Vermont Virginia Washington	West Virginia Wisconsin Wyoming	District of Columbia Hawaii	TOTALS

CURRENT STATUS OF UNITED STATES WORKS PROGRAM GRADE CROSSING PROJECTS

(AS PROVIDED BY THE EMERGENCY RELIEF APPROPRIATION ACT OF 1935)

AS OF DECEMBER 31,1936

	NUMBER BALANCE OF	Grade Grade Grade Grade Grade Coracte Constant C	8 \$ 220,057 86,558 29 171,901	2116,426 316,426 804,261	۳ ۲		3 1,049,115	2 8441,272 268,066 2 8 570.311	-	2 646.786 2 80.187 68.730	1 19 75,988 5 EC 111	2 1.150.967	5 1,743,591 1 15 843,330 266,610	1.354,607 10.798 2.1484,423			2 11 1,107,493 3 255,401		14,000
CONSTRUCTION	IN	Crossings Crossings Eliminated by Separa- tion or Relocation	7 1 7	~ ~ ~	100		1 0 10	0 - 0		1 1		ya Na	0 10 0 15 0 25			N 10	00 2 7 72 12	55	
APPROVED FOR CON		Works Program Funds	^{\$} 141,867	284.732 261.044	228,200 481,243	25,265 1,901,700 363,120	255,980 46,611 184,391	922,04 927,16	249,991	33,400 253,300	433.559	305,27	334.720 780.180 657.820			720,356 679,541 2.400	29,000 501,185 9,967	371.23	
APPR		Estimated Total Cost	* 144.867 1487.346	284.733 261.044	228,200 1481,243	25,265 1,901,700 399,720	371.061 46.611 184.391	966.512 77,464	249,991 58 1428	33,400	433,559	305.279	334.720 780.180 657.820	522.967 34.950	242,803 289,025	720.356 679.547 22.400	58,600 501,186 9,967	371,232	
	ER	Crade Crossings R Protect- ed by ct- Signals ct- or Other- wise		-		-	2-0	11	4 1 tt		ы.	-	99	001 - M		tt 3	1 3 2 1 3 1	0100	
	NUMBER	Grade Grade Crossings Crossing Eliminated Struct by Separa tures Re- tion or construct Relocation ed	28 6 21	537	- 0.8					16 16 16 19		16	227 30					1- 11A-	2
UNDER CONSTRUCTION		Works Program Funds by 5	# 2,409,673 554,816 1.648,268	_	1,275,101 1,275,101	5,455,790 5,455,790 3,713,698	3,632,948 4,425,590 2,173,545	1,447,148 584,103 595,123	2,450,301 3,602,197 2,27 1459	5,499,685	1.523.787	2,294,2490 1,059,479	2,523,748 1,848,657	1,892,426 1,447,128 6,260,721	276.739 1.389.482 1.556.719	1.547,863 6.667,1443 1.092,428	176,930 914,599 1,966,506	1,332,631 2,979,068 723,832	396,804
U		Estimated Total Cost	\$2,409,673 566,261 1.651,166	3.919.677 847.708 719.457	143,486 1,276,024 422,893	5,626,077 3,836,817	3,668,194 4,490,655 2,463,277	1,1117,1148 584,695 595,122	2,450,301 3,602,197	1,943,378 5,695,929	1.523.787 211.658	2,305,294	2.579.248 1.849.657	4,100,171 1,892,426 1,528,728 6 206,127	277,805 1,400,825	1,547,863 6,673,820 1,109,086	191.630 953.598 1.966.931	3.077,522	425,564
		Grade Crossings Protect- ed by Signals or Other- wise	Ţ,			-	Μ	CJ	2	-	-			Q	mi	10	<u></u> б с		
	NUMBER	Grade Crossing Struc- tures Re- construct- ed	t	2	5	- M	10 -	7	nou z o	nm u		n cu	-103	2010-	- 01-	- 0-	6667	4	
	-	Grade Crossings Eliminated by Separa- Relocation	20	5.02	7	2 <u>2 2 2</u>				18 18			1111	26 8 31	0.078	52	26	55	
COMPLETED		Works Program Funds	# 1,360,021 614,725 1.267,250	3,373,754	992,948 12,090	893,543 2,912,094 1,034,272	1.649.719 774.057 265.336	197.227 706	198,005 3,123,475 2,715,679	617,911 308,981	1.523,107	241.148 233,331 665 807	2,066,173 676,700 434,386	1,234.711 841.329 607 001	398,464 475,124 475,124	358,211	474,639 1,251,010 865,167	1.867.957	
		Estimated Total Cost	\$1,360,021 618,960 1.271.375	3,494,543	994,679 12,090	2,912,631 2,912,631 1,034,272	1,696,581 774,057 265,336	497.560	7,167,975 3,167,975	617,911 308,981	1,524,429	241.149 233,331 666 807	2,070,973 676,700 4134,386	1,234,711 841,868 671,165	798, 464 1482, 776 630, 112	358,211 3,066,914	1,321,875	1,896,054	
		APPORTIONMENT	* 4,034,617 1,256,099 3,574,060	7,486,362 2,631,567 1.712,684	1,18,239 2,827,883 1,895,949	1,674,479 10,307,184 5,111,096	5, 246, 258 5, 246, 258 3, 672, 387	3,213,467 1,426,861	4,210,833 6,765,197 5,305 M1	3,241,475 6,142,153 9,729,327	3,556,441	3,983,826	13.577.189 14.823.958 3.207.473	5,004,711 2,334,204	5,059,691 3,059,956 7,210,086	3,903,979 10,855,982	729,857 3,774,287 3,005,001	5.022.683	410.804
		STATE	Alabama Arizona Arkansas	California Colorado Connecticut	Delaware Florida Georgia	Idaho Illinois Indiana	Jowa Kansas Kentucky	Louisiana Maine Maryland	Massachusetts Michigan Minnesota	Mississippi Missouri Montana	Nebraska Nevada New Hamoshire	New Jersey New Mexico	New York North Carolina North Dakota Ohiti	Oklahoma Oregon Pennsylvania	Rhode Island South Carolina South Dakota	Tennessee Texas Utah	Vermont Virginia Washington	West Virginia Wisconsin Wyoming	Dist of Columbia

BALANCE OF FUNDS AVAILABLE FOR NEW PROJECTS 1,464,037 1935 Public Works Funds 28,258 24,400 9,988 91,865 65,783 317,063 46.567 37.530 142.098 2,682 18,016 1,127,968 38,050 32,978 80,388 59.688 48,876 8,738 352,376 173,824 6,992 269,552 38,304 60.939 11.999 21,800 7,111 14,793 95.985 15.575 87.784 62,967 1400,415 54,817 2.476 74.680 45.364 14.525 5,337 87,970 17,622 117,140 37,613 37.712 4,863 23,966 1934 Public Works Funds 14.719 121 24,925 3,825 # 16,076 7,1415 7,059 41,034 8,033 87,489 19,582 39.564 76,951 13,250 1,719,550 24.932 3.849 47.854 8,909 12,405 1,649,1 44,366 84,037 149.563 72.745 14.272 15,368 97.724 61.051 27.419 3.226 58,391 148,620 43.624 284 301,796 4.888 AS PROVIDED BY SECTION 204 OF THE NATIONAL INDUSTRIAL RECOVERY ACT (1934 FUNDS) AND BY THE ACT OF JUNE 18, 1934 (1935 FUNDS) Milcage 3.6 1.5 12.8 1.1 5.9 •6 4.3 27.9 4.2 3.9 9.9 124.6 3.63 8.6 APPROVED FOR CONSTRUCTION 1935 Public Works Funds 285,822 27,086 66,425 2,720 21,300 1,886 7,100 58,728 72,999 26,540 285,453 91,944 40,000 34,800 41.503 63.537 108.487 2.695 119.856 200,000 153,680 87,639 174,301 26,981 149,500 122.701 103,961 59,917 14,000 2,899,857 160,706 21,599 CURRENT STATUS OF UNITED STATES PUBLIC WORKS ROAD CONSTRUCTION 1934 Public Works Funds 56.300 84.072 3,960 39,772 60.772 664 82,145 127.947 34,023 151,626 45,034 12,000 7,035 4,176 770.933 8,569 **:#**}: 366.0 6.9 3.4 1.6 1.0.1 20.8 4.8 ٦. 11.2 11.5 5.3 1.2 27.7 5.9 27.0 4.0 30.5 11.4 ņ Mileage 1935 Public Works Funds 52.034 987.756 202.963 321,000 61,887 216,151 1,127,050 56,546 265, hgh 25, 004 58,080 124,120 326,551 232,044 12,500 43,836 144.368 564,155 107,130 963,899 105,855 64,222 377,896 127.073 178.372 177.644 38.290 206,941 46,596 115,836 105,524 298,765 598,934 194,632 161,772 1460,028 2,668 646,859 10,669,781 UNDER CONSTRUCTION 1934 Public Works Funds 70,019 58,110 120,518 291,910 106,183 73,790 60.231 2,797 83,534 52,665 59,618 305,409 15,000 165,697 399,810 11.308 Slt.042 2.790.763 5.780 689*80+ AS OF DECEMBER 31,1936 Estimated Total Cost 284,709 12,500 114,076 115,898 6,619 59,618 54,193 1,420,426 332,046 340,072 126,993 216,151 258,115 15,000 162,147 367,062 630,562 1,130,984 56,546 272.820 25.004 4,174 1,118,813 107,130 1,459,830 287,505 296,615 46,596 591,626 2,668 5,781 650,838 109,467 323,079 007,623 349,990 230,303 429,258 105.855 75.530 196.520 178,372 180,444 70,718 14,452,895 1.018.4 758.8 78.3 85.9 743.9 821.1 Mileage 1,1222.2 1,132.3 811.4 766.9 723.3 1,441.2 1,058.4 805.5 1468.0 192.3 2.779.9 211.1 619.7 1.037.7 770.0 74.0 1.345.8 2.127.0 787.7 89.1 618.2 1.571.5 141.0 51.1 128.3 305.6 750.8 259.5 193.5 35,025.8 500.5 712.3 474.1 1935 Public Works Funds 2,647,424 1,676,308 1,010,456 2,995,555 4,923,651 3,701,189 2,452,252 2,816,300 10,156,383 1,012,094 2,446,499 2,859,784 4,030,578 1,788,904 3,410,560 3,027,370 1,636,742 4,898,836 2,228,700 968,979 3.713.718 2.605.035 3.347.140 7.769.804 3.441.857 1.312.770 2,344,563 3,225,883 2.185.517 7.893.567 4.746.885 4,797,361 4,996,100 3,571,866 3,079,706 6,261,188 4,857,905 4,313,159 2,940,828 8,746,329 3,613,533 2,268,591 950,495 181,966,325 COMPLETED 8.301.392 5.204.512 6.631.484 1,210,800 1, 367, 452 7, 300, 754 6, 112, 042 1934 Public Works Funds 15,582,422 6,870,681 2,758,269 1,818,804 5,175,534 9,296,628 4,416,568 7,182,552 9,896,355 10,055,161 10,089,600 7,507,142 5.787.557 3.346.879 3.477.038 6,552,734 12,736,227 10,514,422 107.561 7.813.593 4.545.917 1.904.951 6.045.652 5.731.884 21.774.925 9,213,572 6,037,198 18,514,079 5,239,840 5,239,181 8,490,706 4,189,662 4,150,917 9.720.705 1.915,469 388.718.754 15,525,961 8,981,820 10,947,995 0,585,103 1,258,083 4,514,512 2,680,794 8,910,496 13,271,065 7,024,481 26,113,952 15,388,828 15,455,458 15,428,707 12,036,112 5,252,649 5,554,198 12,720,298 12,837,672 7,065,551 3,003,046 9,096,708 8,783,298 39,097,150 14.957.059 8.635.442 24.589.953 14,623,860 9,901,295 28,747,852 3,144,150 7,999,369 9,275,815 .562.878 .900.154 .337.575 3,165,570 1,659,062 9,399,840 261,183 1444,406 2,680,982 ,289,929 ,647,283 626.769.78th Cost Total 973,842 949,778 Act of June 18, 1934 (1935 Fund) 4,259,842 2,641,935 3,428,049 ,932,206 ,454,868 2,661,345 5,113,491 2,277,486 5,921,401 5,088,963 1118,361 1117,675 8,818,311 350,474 452,568 425,551 3,540,227 6,173,740 3,769,734 2,302,356 969,462 3,220,879 2,941,700 11,327,921 ,840,941 ,938,967 ,865,012 585,180 097,814 590,788 .014.572 .770.954 5.047.643 , 202, 991 , 291, 253 3,765,387 3,106,412 2,280,335 4,941,837 2,287,712 200,000,000 APPORTIONMENTS Sec. 204 of the Act of June 16, 1933 (1934 Fund) 8.370.133 5.211.960 6.748.335 15,607,354 6,874,530 2,865,740 4,486,249 17.570.770 10.037,843 6,597,100 12,736,227 10,656,569 9,522,293 5,804,448 15,484,592 1,998,708 5,459,165 6,011,479 1,819,088 5,231,834 10,091,185 10.055.660 10.089.504 7.517.359 5,828,591 3,369,917 3,564,527 6.978.675 12.180.306 7.439.748 6,346,039 5,792,935 22,330,101 9.216.798 6.106.896 13.891,004 8,492,619 24,244,024 4,194,708 1,867,573 7,416,757 6,115,867 4,474,234 9,724,881 4,501,327 1,918,469 7,828,961 4,545,917 1,909,839 394,000,000 District of Columbia Hawaii Rhode Island. South Carolina South Dakota STATE North Carolina. North Dakota Ohio Massachusetts. Michigan Minnesota Nebraska Nevada New Hampshire West Virginia Wisconsin Wyoming Oklahoma Oregon Pennsylvania TOTALS. New Jersey New Mexico. New York California Colorado Connecticut. Mississippi. Missouri. Montana... Virginia Washington Louisiana. Maine Maryland. Alabama... Arizona... Arkansas.. Delaware Florida Georgia Iowa Kansas Kentucky Tennessee. Texas Utah Vermont. Idaho Illinois Indiana

