### SAFETY COMPLIANCE TESTING FOR FMVSS 111

REARVIEW MIRRORS (Other Than School Buses)

> 2004 SUZUKI VERONA 4 DOOR SEDAN

NHTSA NO. C40502

PREPARED BY: KARCO ENGINEERING 9270 HOLLY ROAD ADELANTO, CALIFORNIA 92301



June 30, 2004

FINAL REPORT

PREPARED FOR: U.S. DEPARTMENT OF TRANSPORTATION NATIONAL HIGHWAY TRAFFIC SAFETY ADMINISTRATION ENFORCEMENT OFFICE OF VEHICLE SAFETY COMPLIANCE ROOM 6115 (NVS-220) 400 SEVENTH STREET, SW WASHINGTON, D.C. 20590

This final test report was prepared for the U.S. Department of Transportation, National Highway Traffic Safety Administration, under Contract DTNH22-01-C-31025.

This publication is distributed by the U.S. Department of Transportation, National Highway Traffic Safety Administration in the interest of information exchange. The opinions, findings and conclusions expressed in this publication are those of the author(s) and not necessarily those of the Department of Transportation or the National Highway Traffic Safety Administration. The United States Government assumes no liability for its contents or use thereof. If trade or manufacturers' names or products are mentioned, it is only because they are considered essential to the object of the publication and should not be construed as an endorsement. The United States Government does not endorse products or manufacturers.

Prepared by:	Birch J. Path	. Date: _	June 30, 2004	_
	Mr. Biren J. Patel, Project Engineer KARCO Engineering			
Reviewed by:	My Jerry L. Kratzke, Director of Operations	Date:	June 30, 2004	-
	MARCO Engineering	<b>.</b>		
Approved by:	Mr. Frank D. Richardson, Program Manager KARCO Engineering	Date: _	June 30, 2004	
FINAL REPORT	ACCEPTED BY:	9,	•••	
Accepted By:	It from		·	
Acceptance Date:	8/6/04			

**Technical Report Documentation Page** 

<u></u>	Compon boothers	Starr + Alle	
1. Report No. 111-KAR-04-005	2. Government Accession No.	3. Recipient's Catali	og No.
4. Title and Subtitie Final Report of FMVSS 111 Compli	6. Report Date June 30, 2004		
Testing of 2004 Suzuki Verone 4 Do NHTSA NO.: C40502		6. Performing Organi KAR	zation Code
7. Autror(s) Mr. Biren J. Patel, Proje Mr. Frank D. Richardson	ct Engineer, KARCO n, Program Manager, KARCO	8. Performing Organi 111-KAR-04-00	
Performing Organization Name and Addi     KARCO Engineering	7868	10. Work unit No.	
9270 Holly Road Adelanto, California 92301		11. Contract or Grad DTNH22-01-C-	
12. Sponsoring Agency Name and Address U.S. Department of Transportation		13. Type of report at Final Report-	nd Period Covered
National Highway Traffic Safety Adr Enforcement Office of Vehicle Safety Compliance 400 Seventh Street, SW, Room 611 Washington, D.C. 20590	14. Sponsoring Agency Code NVS 221		
16. Supplementary Notice		-	•
16. Abstract  Compliance tests were conducted on accordance with the apecifications of determination of FMVSS 111 compliants.	the Office of Vehicle Safety Comp	ilance Teat Procedur	through June 24, 2004 in e No. TP111V90 for the
17. Key Words			rt are avallable from:
Compliance Testing	National Highway Traffic Safety Admin. Technical Information Services (TIS)		
Safety Engineering	Room 5108 (NAD-	40)	
PMVSS 111		400 Seventh St., S Waehington, DC 2	
19. Security Constitution (of this report) UNCLASSIFIED	20. Security Classification (of this page) UNCLASSIFIED	21. No. of Pages	92. Price
Form OOT F1700 7 /R-72)			

### **TABLE OF CONTENTS**

Sectio	Ω	<u>Page</u>
1	Purpose of Compliance Test	1
2	Test Procedure and Data Summary	2
3	Test Data	5
Apper	ndix	
Α	Photographs	A
В	Data Plots	В
c	Test Equipment List and Calibration Information	С
D	Eyelipse Locations Supplied by Manufacturer	D
	LIST OF PHOTOGRAPHS	
		Dogo
<u>Figure</u>		Page
1	Left Front % View	A-1
2	Left Side View	A-2
3	Right Rear % View	A-3
4	Right Side View	A-4
5	Manufacturer's Label	A-5
6	Tire Placard	A-6
7	Driver Side Rearview Mirror and Mounting	A-7
8	Passenger Side Rearview Mirror and Mounting	A-8 A-9
9	Inside Rearview Mirror and Mounting	A-10
10	Test Set-up	A-10 A-11
11	Camera Set-up for Photographing Reference Board	A-12
12	Overall Set-up and Instrumentation for Mirror Break-Away Test	A-13
13	Close-Up of Mirror Break-Away Test  Reflection Test Set-up (Typical)	A-14
14 15	Reflection Test Set-up (Typical) Typical Mirror Set-up for Area Measurement	A-15
16	Left Eye Field of View Test (Inside Mirror)	A-16
17	Reference Board for Inside Mirror, Left Eye (From Rear of Vehicle)	A-17
18	Right Eye Flekt of View Test (Inside Mirror)	A-18
19	Reference Board for Inside Mirror, Right Eye (From Rear of Vehicle)	A-19
20	Left Eye Field of View Test (Driver Side Mirror)	A-20
21	Right Eye Field of View Test (Driver Side Mirror)	A-21
22	Reference Board for Driver Side Mirror (From Rear of Vehicle)	A-22

### LIST OF DATA PLOTS

<u>Figure</u>		<u>Page</u>
1	Force vs. Displacement and Displacement vs. Time 0°/90°	B-1
2	Force vs. Displacement and Displacement vs. Time +45°/90°	B-2
3	Force vs. Displacement and Displacement vs. Time -45°/90°	B-3
4	Force vs. Displacement and Displacement vs. Time -45°/+45°	B-4
6	Force vs. Displacement and Displacement vs. Time +45°/+45°	<b>B</b> -5
6	Force vs. Displacement and Displacement vs. Time +45°/-45°	B-6
7	Force vs. Displacement and Displacement vs. Time -45°/-45°	B-7

# SECTION 1 PURPOSE OF COMPLIANCE TEST

### 1. PURPOSE OF COMPLIANCE TEST

Tests were conducted on a 2004 Suzuki Verona 4 Door Sedan, manufactured by Daewoo Auto and Technology Company, to determine compliance with FMVSS 111, "Rearview Mirrors (Other than School Buses)". The purpose of this standard is to reduce the number of deaths and injuries that occur when the driver of a motor vehicle does not have a clear and reasonably unobstructed view to the rear.

All tests were conducted based on the current National Highway Traffic Safety Administration (NHTSA), Office of Vehicle Safety Compliance (OVSC) Laboratory Procedures, TP-111V-00, dated October 28, 1999, and corresponding KARCO Engineering test procedure KTP-111, dated April 18, 2001. Detailed procedures for receiving, inspecting, testing and reporting of test results are described in the test procedures and are not repeated in this report.

This report is organized in sections containing pertinent test information and data tables as follows:

Section 2 - Compliance Test Procedure and Data Summary

Section 3 - Test Results

Appendix A - Photographs

Appendix B - Data Plots

Appendix C - Test Equipment List and Calibration Information

Appendix D - Manufacturer Eyelipse Locations

SECTION 2

COMPLIANCE TEST PROCEDURE AND DATA SUMMARY

### 2. COMPLIANCE TEST PROCEDURE AND DATA SUMMARY

A 2004 Suzuki Verona 4 Door Sedan was subjected to FMVSS 111 compliance testing. The tests were conducted at KARCO Engineering in Adelanto, California on May 27 through June 24, 2004. Summary data is shown on page 23, Data Sheet No. 8. The following tests were performed:

- Inspection
- Mounting Adequacy Test
- Field-of-View Test, Inside Rearview Mirror
- Fleid-of-View Test, Driver's Side Outside Mirror
- Reflectance Test
- Breakaway Test
- Unit Magnification and Convex Mirror Tests

The tests were conducted per the FMVSS 111 test procedure. The significant aspects of the test procedure are described in the following paragraphs.

### A. INSPECTION

Inspect the installation of the inside and outside rearview mirrors.

### B. MOUNTING ADEQUACY TEST – ALL REARVIEW MIRRORS

### **B.1** INSIDE MIRROR (\$5.1.2)

Determine that the mirror is securely mounted and determine the positive and negative angles of adjustment for both the vertical and horizontal directions.

### B.2 OUTSIDE MIRROR(S) (95.2.2 and 95.3)

Determine that the mirror(s) is (are) securely mounted. Determine that the driver's side mirror can be tilted in both horizontal and vertical directions from the driver's seated position. Determine that the passenger's side mirror is capable of adjustment by tilting in both the horizontal and vertical directions. Determine the positive and negative angles of adjustment for both horizontal and vertical directions for all outside mirrors. Determine that all outside mirrors are free of sharp points or edges that could contribute to pedestrian injury.

### C. FIELD-OF-VIEW TEST - INSIDE REARVIEW MIRROR

### C.1 REQUIREMENTS (\$5.1.1)

The mirror shall provide a field of view with an included horizontal angle measured from the projected eye point of at least 20 degrees, and sufficient vertical angle to provide a view of a level road surface extending to the horizon beginning at a point not greater than 61m (200 feet) to the rear of the vehicle when the vehicle is occupied by the driver and four passengers or the designated occupant capacity, if less. The line of sight may be partially obscured by seated occupants or by head restraints.

Each car whose inside mirror does not meet the field of view requirements of S5.1.1 shall have an outside mirror of unit magnification or a convex mirror installed on the passenger's side. (S5.3)

### D. FIELD-OF-VIEW TEST, DRIVER'S SIDE OUTSIDE REARVIEW MIRROR

### D.1 REQUIREMENTS (85.2)

Each passenger car shall have an outside mirror of unit magnification. The mirror shall provide the driver a view of a level road surface extending to the horizon from a line, perpendicular to a longitudinal plane tangent to the driver's side of the vehicle at the widest point, extending 2.4 meters (8 feet) out from the tangent plane 10.7 meters (35 feet) behind the driver's eyes, with the seat in the rearmost position. The line of sight may be partially obscured by rear body or fender contours. (\$5.2.1)

Neither the mirror nor the mounting shall protrude farther than the widest part of the vehicle body except to the extent necessary to produce a field of view meeting or exceeding the requirements of S5.2.1. The mirror shall not be obscured by the un-wiped portion of the windshield. (S5.2.2)

### E. REFLECTANCE TEST – ALL MIRRORS

### E.1 REQUIREMENT (\$11)

All single reflectance mirrors shall have an average reflectance of at least 35 percent. If a mirror is capable of multiple reflectance levels, the minimum reflectance level in the day mode shall be at least 35 percent and the minimum reflectance level in the night mode shall be at least 4 percent. The average reflectance of any mirror required by this standard shall be determined in accordance with SAE Recommended Practice J964, OCT 84.

### F. BREAKAWAY TEST – INSIDE REARVIEW MIRROR

### F.1 REQUIREMENTS (95.1.2)

If the mirror is in the head impact area, the mounting shall deflect, collapse, or break away without leaving sharp edges when the reflective surface of the mirror is subjected to a force of 400 N (90 lb) in any forward direction that is not more than 45 degrees from the longitudinal direction.

### G. UNIT MAGNIFICATION AND CONVEX MIRROR TESTS

### G.1 REQUIREMENTS FOR PASSENGER CARS (85.3 and 85.4)

The driver's side rearview mirror and the inside rearview mirror shall be unit magnification. If the field-of-view requirements are not met with the inside rearview mirror then the passenger's side rearview mirror is required. It can be either unit magnification or convex.

If the passenger's side mirror is convex, the average radius of curvature shall be not less than 889 mm (35 Inches) and not more than 1651 millimeters (65 Inches) and shall not deviate from the average by more than plus or minus 12.5 percent. The convex mirror shall have permanently and indelibly marked at the lower edge of the mirror's reflective surface in letters not less than 4.8 mm (3/16 inch) nor more than 6.4 mm (0.25 inch) high the words, "Objects in Mirror Are Closer Than They Appear."

SECTION 3

TEST DATA

### 3. TEST DATA

The results of FMVSS 111 compliance tests that were conducted on the 2004 Suzuki Verona 4 Door Sedan on May 27 through June 24, 2004 to determine compliance with FMVSS 111, "Rearview Mirrors (other than School Buses)" are presented in this section.

### DATA SHEET NO. 1

### **VEHICLE INSPECTION AND IDENTIFICATION**

TEST VEHICLE INFORMATION				
Manufacturer	DAEWOO AUTO AND TECHNOLOGY COMPANY	VIN	KL5VJ52L34B098285	
Manufacturing Date	07/03	Delivery Date	04/06/04	
Dealer	LANCASTER AUTO GROUP	NHTSA No.	C40502	
Odometer Reading (mi.)	64	Fuel Type	GAS	
Engine Displacement	2.5	Cylinders	4	
Transmission	AUTOMATIC	Final Drive	FRONT	
Engine Placement	TRANSVERSE	Color	TEAL	
Tire Press/Mex. Cap. Front	44	Cold Tire Press. Front	30	
Tire Press./Max. Cap. Rear	44	Cold Tire Press. Rear	30	
Recommend Tire Size	P205/65R15	Type of Spare	P205/65R15	
Tire Size on Vehicle	P205/65R15	Manufacturer	кимно	
GVWR	4279	Cargo Capacity	898	
GAWR Front	2165	GAWR Rear	2114	
Air Conditioning	YES	Power Steering	YES	
Power Brakes	YES	AM/FM/Cassette	YES	
Disc Brakes (Front)	YES	Disc Brakes (Rear)	YES	
Power Windows	YES	Tilt Steering	YES	
Anti-lock Brakes (ABS)	NO	Power Seats	NO	
Oriver Airbag	YES	Passenger Airbag	YES	

TEST VEHICLE ATTITUDE (mm)

ATTITUDE	LF	RF	LR	RR
As Delivered	686	696	685	689
As Tested	661	671	633	641
Rear View Mirror	1310			

VEHICLE						
YEAR	2004	MAKE	SUZUKI			
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN			
NHTSA NO.	C40502	VIN	KL5VJ52L34B098285			
TEST DATE:	05/27/04	TEMPERATURE:	84°F			

LEGEND: LE = Left Eye; RE = Right Eye; P = Neck Pivot Point, SRP = Seating Reference Point

### COORDINATE SYSTEM:

X = Longitudinal Dimension

Y = Lateral Dimension

Z = Vertical Dimension

### Positive Values are as follows:

X = Forward of Reference Point

Y = Outboard of Reference Point (to driver's side)

Z = Above Reference Point

Provide Reference Point or Body Fiduciary Point that dimensions below are measured from. (Point should be usable by laboratory personnel, i.e., center of an anchorage bolt, door jam latch, etc.).

COOR		LEFT SIDE MIRROR			INSIDE MIRROR			RIGHT SIDE MIRROR		SRP
ES	P1	LE1	RE1	P2	LE2	RE2	P3	LE3	RE3	
Х		130	130		130	180		130	130	
Y		272.8	337.8		272.6	337.8		272.6	337.8	
Z		870.3	870.3		870.3	870.3		870.3	870.3	
Mirror Mfr., Model And Part No.	9646083	11		9621843	<b>16</b>		9649244	11		
SRP Travel and Eye- Ilipse	N/A									

Reference Point- Front Outer seat track mounting bolt. Co-ordinates X = 3305.0, Y = 675.3, Z = 209.2

DATE OF INSPECTION/IDENTIFICATION:	05/27/04
TYPES OF REARVIEW MIRRORS:	
INSIDE REARVIEW	WINDSHIELD MOUNTED DAY/NIGHT
DRIVER'S SIDE OUTSIDE-	FLAT
PASSENGER'S SIDE OUTSIDE	CONVEX
LOCATION AND DESCRIPTION OF FIDUCIAL MARKS:	SEE PREVIOUS PAGE
MAXIMUM NUMBER OF OCCUPANTS:	5

MPANIMON NOMBER OF COCC	- AITIO:	<b>3</b>		
RESULTS OR RECEIVING INS	PECTION:			
1200210 011120211110 1110				
PASS	X			
FAIL				
CONDITIONAL				
CONDITIONS:				
DISPOSITION/ACTION:				
REMARKS:				
		-		

RECORDED BY:	PABLO VEGA	DATE:	05/27/04
APPROVED BY:	MATTHEW A. IVORY	DATE:	05/27/04

### DATA SHEET NO. 2

### MOUNTING AND TILTING ADEQUACY TEST

VEHICLE						
YEAR 2004 MAKE SUZUKI						
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN			
NHTSA NO.	C40502	VIN	KL5VJ52L34B096285			
TEST DATE:	05/27/04	TEMPERATURE:	84°F			

MIRROR MOUNTING PROVIDES A STABLE SUPPORT	PASS	FAIL	CONDITIONAL
INSIDE REARVIEW MIRROR	X		
DRIVER SIDE OUTSIDE MIRROR	X		
PASSENGER SIDE OUTSIDE MIRROR	X		NOT REQUIRED

OUTSIDE MIRRORS FREE OF SHARP POINTS OR EDGES	PA8S	FAIL
DRIVER SIDE OUTSIDE MIRROR	X	
PASSENGER SIDE OUTSIDE MIRROR	X	

MIRROR IS ADJUSTABLE VERTICALLY & HORIZONTALLY	PASS	FAIL	CONDITIONAL
INSIDE REARVIEW MIRROR	x		
DRIVER SIDE OUTSIDE MIRROR	X		
PASSENGER SIDE OUTSIDE MIRROR	X		NOT REQUIRED

DRIVER'S OUTSIDE MIRROR ADJUSTABLE FROM THE DRIVER'S SEATED POSITION	PASS	FAIL
DRIVER SIDE OUTSIDE MIRROR	X.	

MIRROR ADJUSTMENT ANGLE	V+	٧-	H+	₩
INSIDE REARVIEW MIRROR	21.5	-43.4	35	-25
DRIVER SIDE OUTSIDE MIRROR	11	-5.5	24	-13
PASSENGER SIDE OUTSIDE MIRROR	11	-5.5	-33	-26

THIS SECTION IS RESERVED FOR MPVs, TRUCKS AND BUSES, OTHER THAN SCHOOL BUSES, NOT CONFORMING TO PASSENGER CAR REQUIREMENTS

MIRROR PROVIDES A VIEW TO THE REAR ALONG BOTH SIDES OF THE VEHICLE	PASS	FAIL	CONDITIONAL
DRIVER SIDE OUTSIDE MIRROR	N/A		
PASSENGER SIDE OUTSIDE MIRROR	N/A		

TEST STATUS:	PASSED	X	FAILED —	
RECORDED BY:	PABLO VEGA		DATE:	05/27/04
APPROVED BY:	MATTHEW A. IVORY	•	DATE:	05/27/04
	9		111-	-KAR-04-005

### DATA SHEET NO. 3

### FIELD OF VIEW TEST - INSIDE REARVIEW MIRROR

VEHICLE					
YEAR	2004	MAKE	SUZUKI		
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN		
NHTSA NO.	C40502	VIN	KL5VJ52L34B098285		
TEST DATE:	05/27/04	TEMPERATURE:	85°F		

E	Distance from center of mirror to projected eye point location =	530.0 mm
A	Distance from rear of vehicle to projected eye point location =	3280.0mm
X1	Distance from rear of vehicle to field of view grid =	8280.4 mm
Z1	Vertical distance to lowest point of field of view at distance X1	730.0 mm
<b>Z2</b>	Height of center of mirror =	1310.0mm
X2	Distance from rear of vehicle where the road surface is first visible X2 = [(Z2 x X1) + (Z1 x A)]/(Z2 - Z1) = (S111 REQUIREMENT = 61m maximum)	22830.55mm (22.83 m)

EYE LOCATION	MONOCULAR DATA (ALR & ARL ARE ANGLES)					
	YL (mm)	YR (mm)	ALR (°)	ARL (°)		
LEFT EYE POINT	YLL =2210	YRL =2615		13.04		
RIGHT EYE POINT	YLR =3005	YRR = 1930	15.06			

### CALCULATED HORIZONTAL AMBINOCULAR VIEW ANGLE (AB)


ANGLE AB = ANGLE ALR + ANGLE ARL

 $ALR = TAN - [1YLR/(X1 + A)] \qquad \qquad ARL = TAN - [1YRL/(X1 + A)]$ 


ANGLE AB = \_\_\_\_\_\_ (S111 REQUIREMENT = 20 degrees minimum)


TEST STATUS:	PASSED —	· x	FAILED —	

## INSIDE REARVIEW MIRROR FIELD OF VIEW TEST GRID AND MARKER SETUP




DRIVER SIDE MIRI	ROR (S5.2)				
MIRROR OBSCURED BY UNWIPED PORTION OF WINDSHIELD					_NO _X
HEIGHT OF TARG	ET DISC ON MIRROF	२		11	43 mm
DISTANCE OF TAR TANGENT PLANE	RGET DISC ON MIRR	OR FROM VEHICLE		58	mm
TARGET DISC LOC	CATION RELATIVE T	O VEHICLE TANGEN	T PLANE		BOARD or Outboard)
ENTIRE TRIANGUI	LAR TEST TARGET	AREA ON SCREEN VI	SIBLE	YES <u>X</u>	_NO
MIRROR PROTRU	DES BEYOND VEHIC	LE TANGENT PLANE	<b></b>	YES <u>X</u>	_ NO
PROTRUSION REC	QUIRED TO MEET FI	ELD OF VIEW REQUI	REMENT	YES <u>X</u>	_NO
TEST STATUS:	PASSED —	X	FAILED -	-	
	: MIRROR (S5.3 or M : MIRROR TYPE (con	FG. OPTION) vex or unit magnificati	on)		ONVEX
REMARKS:					
VEHICLE ATTITUD	E AND GROUND LE	VEL WERE RAISED 4	<b>t".</b>		
RECORDED BY:	PABLO VEGA		DATE	<b>!</b> :	05/27/04
APPROVED BY:	MATTHEW A. IVORY	<u> </u>	DATE	 E	05/27/04






### DRIVER SIDE OUTSIDE MIRROR TARGET DISC LOCATION WITH X AND H DIMENSIONS



### DRIVER SIDE OUTSIDE MIRROR REQUIRED FIELD OF VIEW TRIANGLE



### **DATA SHEET NO. 4**

### REFLECTANCE TEST

VEHICLE					
YEAR	2004	MAKE	SUZUKI		
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN		
NHTSA NO.	C40502	VIN	KL5VJ52L34B098285		
TEST DATE:	05/27/04	TEMPERATURE:	72°F		

DESCRIPTION OF TEST APPARATUS: THE APPARATUS CONSISTS OF AN INCANDESCENT TUNGSTEN FILAMENT LAMP OPERATING AT A NOMINAL COLOR TEMPERATURE OF 2,856 K, COLUMATING OPTICS, A SAMPLE HOLDER POSITIONED AT 25°, A SILICON PHOTOCELL, AND A FLUKE 45 DUAL DISPLAY MULTIMETER (CALIBRATION DUE DATE 3-21-05). REFLECTANCE TESTS ARE CONDUCTED IN A 4'X6' WOODEN CABINET PAINTED FLAT BLACK.

MIRROR DESCRIPTION: INTERIOR DAY/NIGHT REAR VIEW MIRROR

VOLTAGE READING FROM CALIBRATION (Average Value): \_\_\_\_\_295 mV

VOLTAGE READING FROM LIGHT REFLECTED BY DAY MIRROR (Average Value): 280 mV

REFLECTOMETER VOLTAGE READINGS						
DAY MIRROR NIGHT MIRROR						
TEST NO. 1	279 mV	208 mV				
TEST NO. 2	280 mV	209 mV				
TEST NO. 3	279 mV	208 mV				
TEST NO. 4	280 mV	208 mV				
TEST NO. 5	280 mV	209 mV				

<sup>\*</sup>Day/night portion of mirror was electronic and required a voltage to keep the night portion active.

As the tests progressed, the voltage of our supply battery dropped causing the reflectance level to increase. The mirror still met the reflectance requirements of FMVSS 111.

REFLECTANCE (Day) = Voltage (Refl)/Voltage (Cal) = 0. 949 x 100 = 94.9 percent (Min. Required = 35%)

VOLTAGE READING FROM CALIBRATION (Average Value) = -

295 mV

VOLTAGE READING FROM LIGHT REFLECTED BY NIGHT MIRROR (Average Value): 208 mV

REFLECTANCE (Night) = Voltage (Reft)/Voltage (Cal) = 0. 705 × 100 = 70.5 percent (Min. Required = 4%)

NOTE: If meter reading directly in percent is used, record only percent

	SALAGI	1221 140. 4 (OOIII	andody			
MIRROR DESCRIPTION: DRIVER SIDE OUTSIDE MIRROR.						
VOLTAGE READI	NG FROM CALIBRAT	ION (Average Value)	):	295 mV		
VOLTAGE READI	NG FROM LIGHT REF	LECTED BY DAY M	IIRROR (Average Value):	274 mV		
ı	REFLEC	TOMETER VOLTAG	E READINGS	$\neg$		
	TEST NO. 1		274 mV			
	TEST NO. 2		274 mV			
	TEST NO. 3		274 mV	$\dashv$		
	TEST NO. 4		274 mV	<del></del>		
	TEST NO. 5		274 mV	$\dashv$		
REFLECTANCE (I		/oltage (Cal) = 0,9/	28 x 100 = <u>92.8</u> (Min. Requir	percent percent ed = 35%)		
VOLTAGE READI	NG FROM CALIBRATI	IQN. (Average Value)	) =	295 mV		
NOTE: If meter rea	ading directly in percen	it is used, record only	y percent			
TEST STATUS:	PASSED —	х	FAILED —			
RECORDED BY:	PABLO VEGA		DATE:	05/27/04		

DATE:

05/27/04

APPROVED BY: MATTHEW A. IVORY

**DATA SHEET NO. 5** 

### **BREAKAWAY TEST - INSIDE REARVIEW MIRROR**

VEHICLE				
YEAR	2004	MAKE	SUZUKI	
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN	
NHTSA NO.	C40502	VIN	KL5VJ52L34B098285	
TEST DATE:	5/27/04	TEMPERATURE:	86° F	

MOUNTING OF MIRROR (INSIDE) DESCRIPTION: TAB GLUED TO WINDSHIELD. MIRROR BASE SLIPS OVER BASE AND HELD IN PLACE WITH SET SCREW.

(Requirement: the mirror shall deflect, collapse or break away when it is subjected to a force of 400 N or less)

11 01 1000,					
TEST	LOAD DIRECTION	MAXIMUM	DISPLACEMENT	PASS	FAIL
NO.	VERTICAL/HORIZONTAL	FORCE (N)	(MM)		
1	0-90 DEGREES	811.0	8.1	X	
2	+45/90 DEGREES	273.1	6.4	_ X	
3	-45/90 DEGREES	192.0	19.8	X	
4	-45/+45 DEGREES	74.4	18.8	X	
5	+45/+45 DEGREES	224.4	24.9	Х	
6	+45/-45 DEGREES	301.4	34.7	X	
7	-45/-45 DEGREES	233.9	26.0	Х	

REMARKS:

### BREAKAWAY TEST - INSIDE REARVIEW MIRROR FAILURE TYPE - DESCRIPTION:

FAILURE TYPE - DESCRIPTION:

NONE

TEST STATUS:	PASSED —	Х	FAILED —	
--------------	----------	---	----------	--

REMARKS:

APPROVED BY: MATTHEW A. IVORY DATE: 05/27/04

### DATA SHEET NO. 6

### **UNIT MAGNIFICATION AND CONVEX MIRROR TESTS**

VEHICLE				
YEAR	2004	MAKE	SUZŲKI	
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN	
NHTSA NO.	C40502	VIN	KL5VJ52L34B09B285	
TEST DATE:	05/27/04	TEMPERATURE:	82°F	

DESCRIPTION OF TEST APPARATUS: 3-POINT LINEAR SPHEROMETER MANUFACTURED BY AMERICAN OPTICAL CORPORATION, GENEVA LENS MEASURE M667 1.53. SERIAL NUMBER 78622. THE SPHEROMETER USED DID NOT MEET THE ACCURACY REQUIREMENTS OF FMVSS 111. GAGE MEASURED IN DIOPTERS. RADIUS OF CURVATURE WAS CALCULATED USING THE EQUATION:

### RADIUS IN INCHES = (530)(0.03937)/GAGE READING

### DRIVER'S SIDE & INSIDE REARVIEW MIRRORS:

DRIVER SI	DRIVER SIDE MIRROR				
TEST POSITION	DIAL READINGS				
1	0				
2	0				
3	0				
4	0				
5	0				
6	0				
7	0				
8	0				
9	0				
10	0				

INSIDE MIRROR				
TEST POSITION	DIAL READINGS			
1	0			
2	0			
3	0			
4	0			
5	0			
6	0			
7	0			
8	0			
9	0			
10	0			

All dist indicator readings for unit magnification mirrors must be zero.

### **UNIT MAGNIFICATION AND CONVEX MIRROR TESTS**

### PASSENGER SIDE REARVIEW MIRROR:

## CONVERSION TABLE FROM SPHEROMETER DIAL READING TO RADIUS OF CURVATURE

TEST	DIAL	RADIUS OF	DEVIATION BETWEEN THE	PERCENT
POSITION	READINGS	CURVATURE	AVERAGE RADIUS OF	DEVIATION FROM
	(DIOPTERS)	(mm)	CURVATURE AND THE	THE AVERAGE
	PASSENGER		TEST POSITION RADIUS	RADIUS OF
			OF CURVATURE (mm)	CURVATURE
1	0.300	1778.0	0	0
2	0.300	1778.0	0	Ö
3	0.300	1778.0	0	0
4	0.300	1778.0	0	0
5	0.300	1778.0	0	0
6	0.300	1778.0	O .	0
7	0.300	1778.0	0	0
В	0.300	1776.0	0	G
9	0.300	1778.0	0	O
10	0.300	1778.0	0	0
Average Ra	dius of Curvature	1778.0	Greatest Percent Deviation	0

REMARKS:

MIRROR NOT REQUIRED TO MEET FMVSS 111 REQUIREMENTS.

### UNIT MAGNIFICATION AND CONVEX MIRROR TESTS

PASSENGER'S S	IDE REARVIEW MIRR	OR				
IF CONVEX, ARE MIRROR SURFACE	THERE ANY DISCON	TINUITIES IN THE	SLOPE OF THE	YE\$ NOX		
IF CONVEX, ARE	THE WORDS, <b>"OBJE</b> EAR" PRESENT	CTS IN THE MIRRO	OR ARE CLOSER	YES X NO		
IF CONVEX, MEA	SURE LETTER HEIGH	IT OF WORDS		5.0 mm		
IF CONVEX, LET	YES _ X _ NO					
IF CONVEX, THE RA IF UNIT MAGNIFI	IF CONVEX, RADIUS OF CURVATURE NOT < 889 mm OR > 1651 mm  IF CONVEX, THE GREATEST PERCENT DEVIATION FROM AVERAGE  RADIUS OF CURVATURE IS ± 12.5 %  IF UNIT MAGNIFICATION, ALL DIAL READINGS ARE ZERO ± 0.  YES X NO					
NOTE: PASSENG 111.	ER SIDE MIRROR NO	T REQUIRED TO N	IEET REQUIREME	ENTS OF FMVSS		
TEST STATUS:	PASSED —	N/A	FAILED —			
RECORDED BY:	PABLO VEGA		DATE:	05/27/04		
APPROVED BY:	MATTHEW A. IVORY	,	DATE:	05/27/04		
,		·	<b></b> · · · <b>_</b> _			

## DATA SHEET NO. 7 MIRROR REFLECTIVE SURFACE AREA TEST

VEHICLE					
YEAR	2004	MAKE	SUZUKI		
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN		
NHT\$A NO.	C40502	VIN	KL5VJ52L34B098285		
TEST DATE:	05/27/04	TEMPERATURE:	82°F		

### MPVs. TRUCKS & BUSES (OTHER THAN SCHOOL BUSES)

### DATA TABLE FOR SURFACE AREA

MIRRORS	AREA (cm²)	REQUIREMENT		RESULTS	
		GVWR <u>&lt;</u> 4536 kg	GVWR ≥ 4536 kg	PASS	FAIL
Outside Driver's Side	156. <b>64</b> cm²	126 cm²	323cm²	N/A	
Outside Passenger Side	153.96 cm²	126 cm²	323 cm²	N/A	

MIRRORS LOCATED SO AS TO PROVIDE DRIVER A VIEW TO THE REAR:					
LEFT	SIDE YES	S_X_NO			
RIGH	T SIDE YES	s_x_no			
TEST STATUS:	PASSED —	N/A	FAILED —		

REMARKS: NO SURFACE AREA REQUIREMENTS

RECORDED BY:	PABLO VEGA	DATE:	05/27/04
APPROVED BY:	MATTHEW A. IVORY	DATE:	05/27/04

### **DATA SHEET NO. 8**

### **TEST SUMMARY-FMVSS 111-REARVIEW MIRRORS**

VEHICLE				
YEAR	2004	MAKE	SUZUKI	
MODEL	VERONA	BODY STYLE	4 DOOR SEDAN	
NHTSA NO.	C40502	VIN	KL5VJ52L34B098285	
TEST DATE:	05/27/04	TEMPERATURE:	N/A	

### PASSENGER VEHICLE TESTING:


OUTSIDE DRIVER SIDE MIRROR	PASS	FAIL	COMMENTS
STABLE SUPPORT	Х		
DOES NOT PROTRUDE BEYOND VEHICLE BODY	х		
NOT OBSCURED BY UNWIPED PORTION OF WINDSHIELD	x		
ADJUSTABLE BY TILTING	X		
ADJUSTABLE FROM DRIVER SEAT	X		
FREE OF SHARP EDGES	Х		
FIELD-OF-VIEW	X		
REFLECTANCE	X		
UNIT MAGNIFICATION	X		


INSIDE REARVIEW MIRROR	PASS	FAIL	COMMENTS
STABLE SUPPORT	X		
ADJUSTABLE BY TILTING	X		
FIELD-OF-VIEW	X		
REFLECTANCE	X		
BREAK AWAY	x		
UNIT MAGNIFICATION	X		

OUTSIDE PASSENGER MIRROR * (IF REQUIRED)	PASS	FAIL	COMMENTS
STABLE SUPPORT	x		
ADJUSTABLE BY TILTING	x		
FREE OF SHARP EDGES	x		
UNIT OR CONVEX			Convex
LABELING	Х		
REFLECTANCE	N/A		

<sup>\*</sup>NOT REQUIRED


APPENDIX A
PHOTOGRAPHS






2004 SUZUKI VERONA NHTSA NO. C40502 FMVSS NO. 111

FIGURE 2: LEFT SIDE VIEW




2004 SUZUKI VERONA NHTSA NO. C40502 FMVSS NO. 111

FIGURE 3: RIGHT REAR % VIEW




2004 SUZUKI VERONA **NHTSA NO. C40502 FMV\$S NO. 111** 


FIGURE 4: RIGHT SIDE VIEW



2004 SUZUKI VERONA **NHTSA NO. C40502 FMVSS NO. 111** 


FIGURE 6:TIRE PLACARD





2004 SUZUKI VERONA NHTSA NO. C40502 **FMVSS NO. 111** 

FIGURE 8: PASSENGER SIDE REAR VIEW MIRROR AND MOUNTING



2004 SUZUKI VERONA NHTSA NO. C40502 FMVSS NO. 111






FIGURE 10:TEST SET-UP



2004 SUZUKI VERONA NHTSA NO. C40502 FMVSS NO. 111 FIGURE 11:CAMERA SET-UP FOR PHOTOGRAPHING REFERENCE BOARD



2004 SUZUKI VERONA FIGURE 12: OVERALL SET-UP AND INSTRUMENTATION FOR MIRROR BREAK- AWAY TEST NHTSA NO. C40502 FMVSS NO. 111




2004 SUZUKI VERONA NHT\$A NO. C40502 FMVSS NO. 111

FIGURE 13:CLOSE-UP OF MIRROR BREAK- AWAY TEST


FIGURE 14:REFLECTION TEST SET-UP


## FMVSS III 2004 SUZUKI VERONA C40502












2004 SUZUKI VERONA NHTSA NO. C40502 FMVSS NO. 111

FIGURE 20:LEFT EYE FIELD OF VIEW TEST (DRIVER SIDE MIRROR)




2004 SUZUKI VERDNA NHTSA NO. C40502 **FMVSS NO. 111** 

FIGURE 21:RIGHT EYE FIELD OF VIEW TEST (DRIVER SIDE MIRROR)



FIGURE 22: REFERENCE BOARD FOR DRIVER SIDE MIRROR

APPENDIX B
DATA PLOTS



	10 -		<u> </u>	<u> </u>		.	<del></del>	_
	8 -			· 		: 		<i>j</i>
	6 -		ļ 	 	 		/ <sup>N</sup>	
MM	4 -			! 		<b>/</b>		
	2 -		~	\/\/		<u> </u> 		
	٥.		<u> </u>	-	<u> </u>			
	-2 -	3	0	3	6	9	12	15
				Time	- Second	В		

Curve Description	CURNO	Туре
Force vs. Displacement	001	FIL

Units	Peak Force	Displacement	Filter (Hz)
Newtons	311.0	6.8	1


Curve Description	CURNO	Туре
Displacement vs. Time	002	FIL

Units	Max	Time	Dispt. Rate (mm/min.)	Filter (Hz)
MM	8.1	14.0	34.5	1

2004 FMVSS 111 Rearview Mirrors Test No.: 1 2004 Suzuki Verona No.: C40502

Load Direction: Test Date: 0 / 90 5/27/04





	7]		 					]
	6 -		<u> </u>	<del> </del>	! 	$\int$	<u>\</u>	-
i	5 -	<u></u> .	<u> </u> 		$\sim$	1	!	
	4 -		<u> </u> 	- 	-		 	$\frac{1}{1}$
MM	3-			1		 	<u> </u>	
	2 -		_/				 	
	1 -		1		 		! !	
	0 -		/	 				-
	-1 -	2	0	2 .	! <b>:</b>	8	8	10
				Time - Se	conds			

Curve Description	CURNO	Туре
Force vs. Displecement	001	FIL.

Units	Peak Force	Displacement	Filter (Hz)
Newtons	273.1	€.3	1


Curve Description	CURNO	Туре
Displacement vs. Time	002	FIL


Units	Max	Time	Displ. Rate (mm/min.)	Filter (Hz)
MM	6.4	7.9	47.4	1

2004 FMVSS 111 Rearview Mirrors Test No.: 2
2004 Suzuki Verona No.: C40502

Load Direction: Test Date: +45 / 90 6/3/04







Curve Description	CURNO	Туре
Force vs. Displacement	001	FIL


Units	Peak Force	Displacement	Filter (Hz)
Newtons	192.0	18.2	1

Curve Description	CURNO	Туре
Displacement vs. Time	002	FL

Units	Mex	Time	Displ. Rate (mm/mln.)	Filter (Hz)
MM	19.8	35.9	33.0	1

2004 FMVSS 111 Rearview Mirrors Test No.: 3 2004 Suzuki Verona No.: C40502 Load Direction: Test Date: -45 / 90 6/24/04





	21 -		<u> </u>	····	!	!	
	18 -	<b></b>	<u> </u> 	_ :			
	15 -	<b></b>	· 	<del> </del>	<u> </u>	ا المر	
	12 -		- <del></del>	<u> </u>	Market State	,	
MM	9 -		<u> </u>	 		·   - · · · - ·	
	6 -	<u></u>	! <del> </del>	- Jan			
	3 -			, M			_
	o -		M		-   		
	-3 -	10	0	10	20	30	40
				Time - Se	conds		

Curve Description	CURNO	Туре	
Force vs. Displacement	001	FIL	

Units	Peak Force	Displacement	Filter (Hz)
Newtons	74.4	16.7	1


Curve Description	CURNO	Type
Displacement vs. Time	002	FIL

Units	Max	Time	Displ. Rate (mm/mln.)	Filter (Hz)
MM	18.8	33.9	32.1	1

2004 FMVSS 111 Rearview Mirrors Test No.: 4
2004 Suzuki Verona No.: C40502

Load Direction: Test Date: -45 / +45 6/24/04





	30 -		i		i		:	$\neg$
	25 -	<u></u>	· <del> </del> · · · · ·	<u> </u>   <del> </del> 		<u> </u>	لىمد	,
	20 -	L	<u> </u>			_ <u> </u>	<i>y</i> /	
	15 -		<u> </u>		-			
MM	10 -	<u></u>	!	-				-
	5 -			7	/			
	g -		~~	-	<u> </u> 		.—- <del> </del>	
	-5 - -	10	0	10	20	30	40	50
L,				Time	- Second	<b>\$</b>		

Curve Description	CURNO	Туре
Force vs. Displacement	001	FIL


Unite	Peak Force	Displacement	Fiter (Hz)
Newtons	224.4	14.3	1


Curve Description	CURNO	Type
Displacement vs. Time	002	FIL

Units	Max	Time	Displ. Rate (mm/min.)	Filter (Hz)
MM	24.9	45.2	32.3	1

2004 FMVSS 111 Rearview Mirrors Test No.: 5 2004 Suzuki Verona No.: C40502 Load Direction: Test Date: +45 / +45 5/25/04







Curva Description	CURNO	Туре	
Force vs. Displacement	001	FIL	

Units	Peak Force	Displecement	Filter (Hz)
Newtons	301.4	32.4	1

Curve Description	 CURNO	Туре
Displacement vs. Time	 002	FIL


Units	Max	Time	Displ. Rate (mm/mln.)	Filter (Hz)
MM	34.7	58.9	35.4	. 1

2004 FMVSS 111 Rearview Mirrors Test No.: 6
2004 Suzuki Verona No.: C40502

Load Direction: Test Date:

tion: +45 / -45 5/24/04





	30 -		! !		İ	<u> </u>	<u>;</u> !	
	25 -	<u></u>	! 	<u> </u>	<u> </u>		-\ <u>\</u>	
	20 -		. <del> </del> 	<u> </u>	<u> </u>	-   	<u>/</u>	_
	15 -		! 	 	لسمر ا			
MM	10 -		-	 لسر	<b>/</b>	-		
	5		/					
	0 -		<u> </u>	<u> </u>				
	-5 ·	10	0	10	20	30	40	50
L				Time -	Second	ı		

Curve Description	CURNO	Туре
Force vs. Displacement	001	FIL

	Displacer	nent vs. Tim	1 <del>0</del>		002
	Units	Max	Time	Displ. Rate	(.mm/min

45.0

Units	Peak Force	Displacement	Fitter (Hz)	
Newtons	233.9	26.0	1	

Test Program: Test Vehicle:

2004 FMVSS 111 Rearview	Мітогв	Test No.: 7
2004 Suzuki Verona	No.: <u>C</u> 4	10502

Load Direction: Test Date:

ММ

Curve Description

26.0

-45 / -45 6/24/04



Type FIL

Filter (Hz)

CURNO

34.1

## APPENDIX C TEST EQUIPMENT LIST AND CALIBRATION INFORMATION

## 2004 FMVSS 111 Rearview Mirrors Test Equipment List 5/26/04 2004 Suzuki Verona

Description	Manufacturer	Model No.	Serial No.	⊔mlt	Accuracy	Cal. Date	Due Cal.
Hydraulic Pump	Lincoln	T-3625-C	2460952	8 gpm @ 2700 psi	N/A	N/A	N/A
Computer	Panasonic	CF-71	8IMAA01852	N/A	N/A	N/A	N/A
TDAS	DTS	TDAS	DM0103	N/A	<b>ŞAE J211</b>	11/28/03	11/27/04
Load Cell	Lebow	3167	1573	667 N	±1.0%	6/1/04	6/1/05
Displacement Xdcr.	Celesco	PTX101-0030	J0654652	76 CM	± 1.0%	7/1/03	6/30/04

111-KAR-04-005



## APPENDIX D EYELIPSE LOCATIONS SUPPLIED BY MANUFACTURER

FMV	222	111	EYE	TAIOS	LOCA	TIONS
	33			CVIII		,,,,,,,

Make: GMDAT

Model: VERONA

Year: MY04

Coordinate System:

X = Longitudinal Dimension

Y = Lateral Dimension

Z = Vertical Dimension

Positive Values ere as follows:

X = Forward of Reference Point

Y = Outboard of Reference Point (to driver's side)

Z = Above Reference Point

Provide Reference/Body Fiducial Point that dimensions below are measured from. Point must be easily accessible and usable by test laboratory personnel, i.e. seat track mounting bolt, seat belt anchorage bolt, door latch also pillar striker. (Provide sketch of reference point if necessary.)

COORDINATES	LEFT SIDS MIRROR		INSIDE MARROR		RIGHT SIDE MIRROR	
	LE1 (left eye)	RE1 (right eye)	LIÉ2	RE2	LES	RES
×	130mm	130mm	130 mm	130mm	130mm	130mm
Ψ	272.8mm	337.8mm	272.8mm	837.8mm	272.6mm	337.8mm
Z	870.3mm	870.3mm	870.3mm	870.3mm	870.3mm	870.3mm
Mirror Attr., Model Part No.	96460831	ı	96218436	,	96492441	•

